

Application to Commit Energy
Efficiency/Peak Demand
Reduction Programs
(Mercantile Customers Only)

Case No.: <u>12-2672 -E</u>L-EEC

Mercantile Customer: Cincinnati Public Schools (Hartwell)

Electric Utility: **Duke Energy**

Program Title or

Description: HVAC and Lighting (CUSTOM)

Rule 4901:1-39-05(F), Ohio Administrative Code (O.A.C.), permits a mercantile customer to file, either individually or jointly with an electric utility, an application to commit the customer's existing demand reduction, demand response, and energy efficiency programs for integration with the electric utility's programs. The following application form is to be used by mercantile customers, either individually or jointly with their electric utility, to apply for commitment of such programs in accordance with the Commission's pilot program established in Case No. <u>10-834-EL-POR</u>

Completed applications requesting the cash rebate reasonable arrangement option (Option 1) in lieu of an exemption from the electric utility's energy efficiency and demand reduction (EEDR) rider will be automatically approved on the sixty-first calendar day after filing, unless the Commission, or an attorney examiner, suspends or denies the application prior to that time. Completed applications requesting the exemption from the EEDR rider (Option 2) will also qualify for the 60-day automatic approval so long as the exemption period does not exceed 24 months. Rider exemptions for periods of more than 24 months will be reviewed by the Commission Staff and are only approved up the issuance of a Commission order.

Complete a separate application for each customer program. Projects undertaken by a customer as a single program at a single location or at various locations within the same service territory should be submitted together as a single program filing, when possible. Check all boxes that are applicable to your program. For each box checked, be sure to complete all subparts of the question, and provide all requested additional information. Submittal of incomplete applications may result in a suspension of the automatic approval process or denial of the application.

Any confidential or trade secret information may be submitted to Staff on disc or via email at <u>ee-pdr@puc.state.oh.us</u>.

Section 1: Mercantile Customer Information

Name: Cincinnati Public Schools

Principal address: 2651 Burnet Avenue Cincinnati, Ohio 45219

Address of facility for which this energy efficiency program applies:

8320 Vine Cincinnati Ohio 45238 (Hartwell)

Name and telephone number for responses to questions:

Grady Reid Jr 513-287-1038

Electricity use by the customer (check the box(es) that apply):

- The customer uses more than seven hundred thousand kilowatt hours per year at the above facility. (See Appendix A)
- ☐ The customer is part of a national account involving multiple facilities in one or more states. (Please attach documentation.)

Section 2: Application Information

- A) The customer is filing this application (choose which applies):
 - ☐ Individually, without electric utility participation.
 - ✓ Jointly with the electric utility.
- B) The electric utility is: **Duke Energy**
- C) The customer is offering to commit (check any that apply):
 - □ Energy savings from the customer's energy efficiency program. (Complete Sections 3, 5, 6, and 7.)
 - □ Capacity savings from the customer's demand response/demand reduction program. (Complete Sections 4, 5, 6, and 7.)
 - **✓** Both the energy savings and the capacity savings from the customer's energy efficiency program. (Complete all sections of the Application.)

Section 3: Energy Efficiency Programs

| A) | The | e customer's energy efficiency program involves (check those that apply): |
|-----------|-----|--|
| | | Early replacement of fully functioning equipment with new equipment. (Provide the date on which the customer replaced fully functioning equipment, and the date on which the customer would have replaced such equipment if it had not been replaced early. Please include a brief explanation for how the customer determined this future replacement date (or, if not known, please explain why this is not known)). |
| | | Installation of new equipment to replace equipment that needed to be replaced The customer installed new equipment on the following date(s): |
| | ✓ | Installation of new equipment for new construction or facility expansion. The customer installed new equipment on the following date(s): October 2010 |
| | | Behavioral or operational improvement. |
| В) | Ene | ergy savings achieved/to be achieved by the energy efficiency program: |
| | 1) | If you checked the box indicating that the project involves the early replacement of fully functioning equipment replaced with new equipment, then calculate the annual savings [(kWh used by the original equipment) – (kWh used by new equipment) = (kWh per year saved)]. Please attach your calculations and record the results below: |
| | | Annual savings:kWh |
| | 2) | If you checked the box indicating that the customer installed new equipment to replace equipment that needed to be replaced, then calculate the annual savings [(kWh used by less efficient new equipment) – (kWh used by the higher efficiency new equipment) = (kWh per year saved)]. Please attach your calculations and record the results below: |
| | | Annual savings:kWh |
| | | Please describe any less efficient new equipment that was rejected in favor of the more efficient new equipment. |
| Revised (| | If you checked the box indicating that the project involves equipment for new construction or facility expansion, then calculate the annual savings [(kWh used by less efficient new equipment) – (kWh used by higher er 4, 2011 |

efficiency new equipment) = (kWh per year saved)]. Please attach your calculations and record the results below:

Annual savings: 70,544 kWh savings (Refer to Appendix B for calculations and supporting documents).

Please describe the less efficient new equipment that was rejected in favor of the more efficient new equipment.

4) If you checked the box indicating that the project involves behavioral or operational improvements, provide a description of how the annual savings were determined.

Revised October 4, 2011

Section 4: Demand Reduction/Demand Response Programs

- A) The customer's program involves (check the one that applies):
 - ✓ Coincident peak-demand savings from the customer's energy efficiency program.
 - Actual peak-demand reduction. (Attach a description and documentation of the peak-demand reduction.)
 - □ Potential peak-demand reduction (check the one that applies):
 - ☐ The customer's peak-demand reduction program meets the requirements to be counted as a capacity resource under a tariff of a regional transmission organization (RTO) approved by the Federal Energy Regulatory Commission.
 - ☐ The customer's peak-demand reduction program meets the requirements to be counted as a capacity resource under a program that is equivalent to an RTO program, which has been approved by the Public Utilities Commission of Ohio.
- B) On what date did the customer initiate its demand reduction program?

October 2010

C) What is the peak demand reduction achieved or capable of being achieved (show calculations through which this was determined):

28.2 KW

Refer to Appendix B for calculations and supporting documentation

Section 5: Request for Cash Rebate Reasonable **Arrangement (Option 1) or Exemption from Rider (Option 2)**

Under this section, check the box that applies and fill in all blanks relating to that choice.

Note: If Ontion 2 is selected the application will not qualify for the 60 da automatic is by the

| app | | . All | applications, however, will be considered on a timely basis by the | | | |
|-----|---|--------|--|--|--|--|
| A) | The customer is applying for: | | | | | |
| | ✓ Option 1: A cash rebate reasonable arrangement. | | | | | |
| | OR | | | | | |
| | | - | on 2: An exemption from the energy efficiency cost recovery anism implemented by the electric utility. | | | |
| | OR | | | | | |
| | | Com | mitment payment | | | |
| B) | The | value | of the option that the customer is seeking is: | | | |
| | Opt | ion 1: | A cash rebate reasonable arrangement, which is the lesser of (show both amounts): | | | |
| | | | ✓ A cash rebate of \$4,500.00. Refer to Appendix C. | | | |
| | Opt | ion 2: | An exemption from payment of the electric utility's energy efficiency/peak demand reduction rider. | | | |
| | | | An exemption from payment of the electric utility's energy efficiency/peak demand reduction rider for months (not to exceed 24 months). (Attach calculations showing how this time period was determined.) | | | |
| | | | OR | | | |
| | | | □ A commitment payment valued at no more than \$ (Attach documentation and | | | |

calculations showing how this payment amount was determined.)

OR

Ongoing exemption from payment of the electric utility's energy efficiency/peak demand reduction rider for an initial period of 24 months because this program is part of the customer's ongoing efficiency program. (Attach documentation that establishes the ongoing nature of the program.) In order to continue the exemption beyond the initial 24 month period, the customer will need to provide a future application establishing additional energy savings and the continuance of the organization's energy efficiency program.)

Section 6: Cost Effectiveness

The program is cost effective because it has a benefit/cost ratio greater than 1 using the (choose which applies):

| Total Resource Cost (TRC) Test. | The calculated TRC value is: | |
|-------------------------------------|------------------------------|--|
| (Continue to Subsection 1, then ski | p Subsection 2) | |

| ✓ | Utility Cost Test (UCT). The calculated UCT value is 10.13(Skip to | | | | |
|---|--|--|--|--|--|
| | Subsection 2.) Refer to Appendix D for calculations and | | | | |
| | supporting documents. | | | | |

Subsection 1: TRC Test Used (please fill in all blanks).

The TRC value of the program is calculated by dividing the value of our avoided supply costs (generation capacity, energy, and any transmission or distribution) by the sum of our program overhead and installation costs and any incremental measure costs paid by either the customer or the electric utility.

| The electric utility's avoided supply costs were | <u> </u> |
|--|----------|
| Our program costs were | |
| The incremental measure costs were | |

Subsection 2: UCT Used (please fill in all blanks).

We calculated the UCT value of our program by dividing the value of our avoided supply costs (capacity and energy) by the costs to our electric utility (including administrative costs and incentives paid or rider exemption costs) to obtain our commitment.

Our avoided supply costs were \$70,165

The utility's program costs were \$2,425

The utility's incentive costs/rebate costs were \$4,500

Refer to Appendix D for calculations

Section 7: Additional Information

Please attach the following supporting documentation to this application:

Narrative description of the program including, but not limited to, make, model, and year of any installed and replaced equipment.

A copy of the formal declaration or agreement that commits the program or measure to the electric utility, including:

- 1) any confidentiality requirements associated with the agreement;
- 2) a description of any consequences of noncompliance with the terms of the commitment;
- 3) a description of coordination requirements between the customer and the electric utility with regard to peak demand reduction;
- 4) permission by the customer to the electric utility and Commission staff and consultants to measure and verify energy savings and/or peak-demand reductions resulting from your program; and,
- 5) a commitment by the customer to provide an annual report on your energy savings and electric utility peak-demand reductions achieved.

Refer to Rebate Offer Letter following this application

A description of all methodologies, protocols, and practices used or proposed to be used in measuring and verifying program results. Additionally, identify and explain all deviations from any program measurement and verification guidelines that may be published by the Commission.



DUKE ENERGY
Mercantile Self Direct Program
139 East Fourth Street
Cincinnati, OH 45202
513 629 5572 fax

September 17, 2012

Mr. Don Elbe Cincinnati Public Schools (Hartwell) 2651 Burnet Avenue Cincinnati, Ohio 45219

Subject: Your (Custom) Application for a Duke Energy (HVAC and Lighting) Mercantile Self-Direct Rebate

Dear Mr. Elbe:

Thank you for your Duke Energy Mercantile Self Direct rebate application. As noted in the Energy Conservation Measure (ECM) chart on page two, a total rebate of \$4,500.00 has been proposed for your HVAC and lighting project completed in the October 2010 calendar year. All Self Direct Rebates are contingent upon approval by the Public Utilities Commission of Ohio (PUCO).

At your earliest convenience, please indicate if you accept this rebate by

- providing your signature on page two
- completing the PUCO-required affidavit on page three.

Please return the documents to my attention via fax at 513-629-5572 or e-mail to SelfDirect@Duke-Energy.com. Upon receipt, Duke Energy will submit the necessary documentation to PUCO. Following PUCO's approval, Duke Energy will remit payment.

At Duke Energy, we value your business and look forward to working with you on this and future energy efficiency projects. We hope you will consider our Smart \$aver® incentives, when applicable. Please contact me if you have any questions.

Sincerely,

Grady Reid, Jr Product Manager Mercantile Self Direct Rebates

cc: Mike Heath, Duke Energy Rob Jung, WECC Lucas Dixon, PlugSmart

| Please indicate your response to this re | date offer within 30 day | уѕ от гесеірт. |
|---|--|---|
| Rebate is accepted. | Rebate is decline | ed. |
| By accepting this rebate, Cincinnati Put energy efficiency projects listed on the f demand response and/or energy efficie | ollowing pages into Du | _ |
| Additionally, Cincinnati Public Schools a necessary to secure approval of this arr information and reporting requirements | angement as required | by PUCO and to comply with any |
| Finally, Cincinnati Public Schools affirm pursuant to this rebate offer is true and limited to, project scope, equipment spe project completion dates, and the quant | accurate. Information cifications, equipment | in question would include, but not be operational details, project costs, |
| If rebate is accepted, will you use the m reduction projects? | onies to fund future en | ergy efficiency and/or demand |
| □YES ☑NO | | |
| If rebate is declined, please indicate rea | son (optional): | |
| Don Elle Don | Elbe | 9-19-12 |
| Customer Signature Printed | Name | Date |

Proposed Rebate Amounts

| Measure ID | Energy Conservation Measure (ECM) | Proposed Rebate Amount |
|--|-----------------------------------|---------------------------|
| ECM-1 | \$2000.00 | |
| ECM-2 | \$1900.00 | |
| ECM-3 Hartwell – New Construction Lighting | | \$600.00 |
| · Total | | \$4500.00 |

Ohio Public Utilities Commission

Application to Commit Energy Efficiency/Peak **Demand Reduction Programs** (Mercantile Customers Only)

| Case No.:EL-EEC |
|--|
| State of Ohio: |
| Don Elbe, Affiant, being duly sworn according to law, deposes and says that: |
| 1. I am the duly authorized representative of: Cincinnati Public Schools [insert customer or EDU company name and any applicable name(s) doing business as] |
| I have personally examined all the information contained in the foregoing application, including any exhibits and attachments. Based upon my examination and inquiry of those persons immediately responsible for obtaining the information contained in the application, I believe that the information is true, accurate and complete. |
| 3. I am aware of fines and penalties which may be imposed under Ohio Revised Code Sections 2921.11, 2921.31, 4903.02, 4903.03, and 4903.99 for submitting false information. |
| Signature of Affiant & Title |
| Sworn and subscribed before me this 19th day of Scatenber, 2012 Month/Year |
| Signature of official administering oath Angelia F. Tolle, No tary Public Print Name and Title |
| My commission expires on Sept 11, 2013 ANGELA F. TOXIII Netsry Public, State of the Commission Experience of Exp |

Appendix A

| 91103676 01 | | |
|---------------------------|------|------------|
| CINCINNATI PUBLIC SCHOOLS | | |
| 5945 MONTGOMERY RD | | |
| CINCINNATI, OH 45213 | | |
| Date | Days | Actual KWH |
| 12/29/2011 | 30 | 89,624 |
| 11/29/2011 | 33 | 99,166 |
| 10/27/2011 | 29 | 102,362 |
| 9/28/2011 | 30 | 119,392 |
| 8/29/2011 | 31 | 166,765 |
| 7/29/2011 | 30 | 162,193 |
| 6/29/2011 | 29 | 132,830 |
| 5/31/2011 | 32 | 118,148 |
| 4/29/2011 | 30 | 105,178 |
| 3/30/2011 | 29 | 115,864 |
| 3/1/2011 | 29 | 118,427 |
| 1/31/2011 | 32 | 128,341 |
| Total | | 1,458,290 |

Appendix B - Hartwell Energy Savings Achieved

| | | Baseline Used | | Post Project Actual | | | | Sa | vings | |
|-------|-------------------|--|---------|---------------------|---|---------|------------|------------------------|--------|------------|
| | | | | Summer | | | Summer | | | Summer |
| | | | Annual | Coincident | | Annual | Coincident | Hours of | Annual | Coincident |
| ECM # | Facility | Description | kWh | kW | Description | kWh | kW | Operation ¹ | kWh | kW |
| 1 | Hartwell | 25,540 CFM for AHU 1 without heat recovery | 35,963 | 29.4 | Heat recovery unit added to AHU 1 | 9,622 | 7.9 | 1,225 | 26,341 | 21.5 |
| 2 | Hartwell | 24,400 CFM for AHU 2 without heat recovery | 34,218 | 27.9 | Heat recovery unit added to AHU 2 | 9,872 | 8.1 | 1,225 | 24,346 | 19.8 |
| | | | | | Lighting Power Density Improvement Over | | | | | |
| 3 | Hartwell | Lighting Power Density Per Code | 175,242 | See Note 2 | Code As Per Application | 159,852 | See Note 2 | 2,080 | 15,390 | 7.0 |
| | Totals 245,423 57 | | | | | 179,346 | 16 | | 66,077 | 48 |

After consideration of line losses, total energy savings are 70,544 kWh and 28.2 summer coincident kW. These values may also reflect minor DSMore modeling software rounding error.

Notes:

- 1 Hours of operation do not apply simply to heat recovery unit measures. kWh and kW values presented are the results of bin analysis presented in the attached pages.
- 2 Building Code baseline lighting power density allowances as well as the as installed fixture wattages & quantities are detailed on the attached pages.

 Annual energy (kWh) savings values validated in the applicant lighting energy model were input into the DSMore analysis software and modeled against a representative customer load shape to determine the coincident peak demand (kW) savings for this application

DETAILED CALCULATIONS

IAN 2012 V2.0

| JAN 2012 V2.0 | | | _ | | | |
|-----------------------------|-----------------------------|---|---------------|----------------|------|--|
| Salesforce Opportunity Name | | Cincinnati Public Schools - Hartwell - HVAC and Lig | Application # | 12-313 MSD Rev | . 0 | |
| Project Name | Cincinnati Public Schools - | - Hartwell - HVAC and Lighting | _ | State | . OH | |
| ECM | 1 | | | | | |

Note: all data from Part 2 of the application, except as otherwise noted

| 2,080 | hr/yr operation - before implementation |
|-------|---|
| 2,080 | hr/yr operation - after implementation |

| | | Ex | isting | | | | | Pro | oposed | | | | Sa | avings | | |
|------|---------------------|--------|-----------|---------|-------|----------|----------------------|-----|---------|---------|-------|----------|-------|----------|---------|----------------|
| | | | | | | | | | Watts | | | | | | Other | Incremental |
| Site | | | Watts | kw per | total | | | | per | kw per | total | | | | Annual | Implementation |
| ID | Square Footage | Qty | per sq ft | fixture | kw | kw-hr/yr | Type -Fixture | Qty | fixture | fixture | kw | kw-hr/yr | kw | kw-hr/yr | Savings | Costs |
| 1 | Floor area affected | 70,209 | 1.2 | 0.001 | 84.3 | 175,242 | A1-2L 4' T8 32W HP | 68 | 59 | 0.059 | 4.0 | 8,345 | 80.2 | 166,897 | | \$ 7,289.60 |
| | | | | 0.000 | 0.0 | 0 | A2-2L 4' T8 32W HP | 37 | 58 | 0.058 | 2.1 | 4,464 | -2.1 | -4,464 | | \$ 4,565.80 |
| | | | | 0.000 | 0.0 | 0 | A31 3L 4' T8 32W | 17 | 84 | 0.084 | 1.4 | 2,970 | -1.4 | -2,970 | | \$ 2,306.90 |
| | | | | 0.000 | 0.0 | 0 | B24-2L 4' T8 32W | 4 | 63 | 0.063 | 0.3 | 524 | -0.3 | -524 | | \$ 536.48 |
| | | | | 0.000 | 0.0 | 0 | B28-4L 8' T8 32W | 55 | 126 | 0.126 | 6.9 | 14,414 | -6.9 | -14,414 | | \$ 7,970.05 |
| | | | | 0.000 | 0.0 | 0 | B34- 3L 4' T8 32W | 18 | 97 | 0.097 | 1.7 | 3,632 | -1.7 | -3,632 | | \$ 2,751.48 |
| | | | | 0.000 | 0.0 | 0 | B38-3L 8' T8 32W | 150 | 194 | 0.194 | 29.1 | 60,528 | -29.1 | -60,528 | | \$ 26,037.00 |
| | | | | 0.000 | 0.0 | | C31-3L 2X4 T8 32W | 22 | 91 | 0.091 | 2.0 | 4,164 | -2.0 | -4,164 | | \$ 3,198.80 |
| | | | | 0.000 | 0.0 | 0 | C32 -3L 2X4 T8 32W | 20 | | 0.091 | 1.8 | 3,786 | -1.8 | -3,786 | | \$ 2,908.00 |
| | | | | 0.000 | 0.0 | | D5-2L WB T8 32W | 13 | 63 | 0.063 | 0.8 | 1,704 | -0.8 | -1,704 | | \$ 3,817.97 |
| | | | | 0.000 | 0.0 | 0 | D7 -2LWP T8 32W | 7 | 63 | 0.063 | 0.4 | 917 | -0.4 | -917 | | \$ 758.59 |
| | | | | 0.000 | 0.0 | 0 | G3-3L 2X4 T8 32W | 13 | 87 | 0.087 | 1.1 | 2,352 | -1.1 | -2,352 | | \$ 1,541.80 |
| | | | | 0.000 | 0.0 | | J31-3L 2X4 T8 32W | 82 | | 0.091 | 7.5 | 15,521 | -7.5 | -15,521 | | \$ 22,082.60 |
| | | | | 0.000 | 0.0 | | J32-3L 2X4 T8 32W | 6 | 91 | 0.091 | 0.5 | 1,136 | -0.5 | -1,136 | | \$ 1,615.80 |
| | | | | 0.000 | 0.0 | 0 | K-2L 4' IND T8 32W | 21 | 63 | 0.063 | 1.3 | 2,752 | -1.3 | -2,752 | | \$ 1,134.21 |
| | | | | 0.000 | 0.0 | | K4 -2L 4' IND T8 32W | 22 | | 0.074 | 1.6 | 3,386 | -1.6 | -3,386 | | \$ 1,567.50 |
| | | | | 0.000 | 0.0 | | K8 -4L 8' IND T8 32W | 39 | | 0.074 | 2.9 | 6,003 | -2.9 | -6,003 | | \$ 3,829.80 |
| | | | | 0.000 | 0.0 | | L14 1L STRIP T8 32W | 10 | | 0.034 | 0.3 | 707 | -0.3 | -707 | | \$ 844.50 |
| | | | | 0.000 | 0.0 | | PS2 TRI 4PIN 32W | 18 | | 0.064 | 1.2 | 2,396 | -1.2 | -2,396 | | \$ 2,884.86 |
| | | | | 0.000 | 0.0 | | PS3 TT 4L 24W PEND | 10 | | 0.106 | | 2,205 | -1.1 | -2,205 | | \$ 4,812.50 |
| | | | | 0.000 | 0.0 | | S1 TRI 4PIN 32W | 2 | | 0.036 | | 150 | -0.1 | -150 | | \$ 212.40 |
| | | | | 0.000 | 0.0 | 0 | XBA 8L TRI 4PIN 42W | 23 | | 0.372 | 8.6 | 17,796 | -8.6 | -17,796 | | \$ 6,297.17 |
| | Totals | 70,209 | | | 84.3 | 175,242 | | 657 | | | 76.9 | 159,852 | 7.4 | 15,390 | \$ - | \$ 108,963.81 |

DETAILED CALCULATIONS

JAN 2012 V2.0

Salesforce Opportunity Name Cincinnati Public Schools - Hartwell - HVAC and Lighting Project Name Cincinnati Public Schools - Hartwell - HVAC and Lighting ECM Cincinnati Public Schools - Hartwell - HVAC and Lighting - Energy Recovery Wheel for AHU-1

Application # 12-313 MSD

Note: all data from "Hartwell.HRW.Calcs.xlsx", except as otherwise noted

USA_OH_Cincinnati.Muni.AP-Lunken.Field.724297_TMY3.bin HEAT RECOVERY WHEEL SAVINGS

> Minimum Fraction Outdoor Air: 43.18% Heat Recover Effectiveness: 77.10% Set Point Temperature: 75.6 F Set Point Enthalpy: 27.281 Btu/lba Supply Air Temperature: 51.4 F Supply Air Enthalpy: 20.996 Btu/lba Supply Air Volume: 25,540 cfm Supply Air Density: 0.075 lb/ft^3

| | Supp.y, | an Density. | 0.075 | 10/113 | | | | Savings | Baseline | Proposed |
|-------------------------|-------------------|-------------|------------------|--------|-------------|------------|------------------|--------------|--------------|--------------|
| StrTemp (F) | EndTemp (F) | Toa (F) | hoa (Btu/lba) | hrs | foa | Tma (F) | hma (Btu/lba) | Q (mmBTU) | Q (mmBTU) | Q (mmBTU) |
| 105 | 109 | 107.0 | 0 | 0 | 43% | 89.2 | 15.50 | 0.00 | 0.00 | 0.00 |
| 100 | 104 | 102.0 | 0 | 0 | 43% | 87.0 | 15.50 | 0.00 | 0.00 | 0.00 |
| 95 | 99 | 96.1 | 42.6 | 12 | 43% | 84.5 | 33.90 | 7.03 | 9.12 | 2.09 |
| 90 | 94 | 92.2 | 39.6 | 41 | 43% | 82.8 | 32.60 | 19.32 | 25.06 | 5.74 |
| 85 | 89 | 87.6 | 37.7 | 142 | 43% | 80.8 | 31.78 | 56.60 | 73.41 | 16.81 |
| 80 | 84 | 82.4 | 35.0 | 250 | 43% | 78.5 | 30.61 | 73.83 | 95.76 | 21.93 |
| 75 | 79 | 77.2 | 33.4 | 287 | 43% | 76.3 | 29.92 | 67.19 | 87.14 | 19.96 |
| 70 | 74 | 72.5 | 31.9 | 241 | 100% | 72.5 | 31.90 | 98.64 | 127.94 | 29.30 |
| 65 | 69 | 68.0 | 29.1 | 252 | 100% | 68.0 | 29.10 | 40.62 | 52.68 | 12.06 |
| 60 | 64 | 62.6 | 24.8 | 322 | 100% | 62.6 | 24.80 | 0.00 | 0.00 | 0.00 |
| 55 | 59 | 57.1 | 21.9 | 222 | 100% | 57.1 | 21.90 | 0.00 | 0.00 | 0.00 |
| 50 | 54 | 52.0 | 19.2 | 226 | 100% | 52.0 | 19.20 | 0.00 | 0.00 | 0.00 |
| 45 | 49 | 47.5 | 17.3 | 151 | 86% | 51.4 | 18.69 | 0.00 | 0.00 | 0.00 |
| 40 | 44 | 43.1 | 15.2 | 211 | 74% | 51.4 | 18.29 | 0.00 | 0.00 | 0.00 |
| 35 | 39 | 37.6 | 12.9 | 206 | 64% | 51.4 | 18.12 | 0.00 | 0.00 | 0.00 |
| 30 | 34 | 32.4 | 10.8 | 135 | 56% | 51.4 | 18.05 | 0.00 | 0.00 | 0.00 |
| 25 | 29 | 27.7 | 9.0 | 99 | 51% | 51.4 | 18.05 | 0.00 | 0.00 | 0.00 |
| 20 | 24 | 23.3 | 7.5 | 66 | 46% | 51.4 | 18.13 | 0.00 | 0.00 | 0.00 |
| 15 | 19 | 18.3 | 5.9 | 36 | 43% | 50.9 | 18.05 | 0.00 | 0.00 | 0.00 |
| 10 | 14 | 12.5 | 4.1 | 16 | 43% | 48.4 | 17.27 | 0.00 | 0.00 | 0.00 |
| 5 | 9 | 7.5 | 2.7 | 5 | 43% | 46.2 | 16.67 | 0.00 | 0.00 | 0.00 |
| 0 | 4 | 3.0 | 1.4 | 0 | 43% | 44.3 | 16.11 | 0.00 | 0.00 | 0.00 |
| | | | | | | Annual Tot | | 363.23 | 471.12 | 107.89 |
| Energy r | ecovery wheel mo | | | | | | Ton-hours: | 30,269 | 39,260 | 8,991 |
| | Motor Size hp: | 1.50 | | | | | chiller IPLV: | 13.1 | 13.1 | 13.1 |
| Load Factor: 0.85 | | | | | | | er kW/Ton: | 0.916 | 0.916 | 0.916 |
| Motor Efficiency: 84.0% | | | | | | | oling kWh: | 27,728 | 35,963 | 8,236 |
| hp | to kW conversion: | 0.7456 | | H | leat Recove | | 1,225 | 1,225 | 1,225 | |
| | Motor kW: | 1.132 | | | | C | ooling kW: | 22.63 | 29.36 | 6.72 |
| | Motor kWh: | 1,386 | | | | | | | | |

Allocation of annual savings by month (Added During Tech Review)

Trade ally only provided annual savings numbers. Combine HRW savings and motor use, then use % of cooling degree days by month to distribute annual savings appropriately.

| Cooling Degree Day Source. | | HLLD.//WWW | w.ciimate-zt | Jiic.com/cm | mate/ united | a States/ Offi | O/ greater c | incilliati ali | DUIT | | | | |
|----------------------------|------|------------|--------------|-------------|--------------|----------------|--------------|----------------|-------|------|------|------|--------|
| | Jan | Feb | Mar | April | May | June | July | Aug | Sep | Oct | Nov | Dec | Annual |
| CDD by Month | 0.0 | 0.0 | 0.0 | 0.0 | 86.0 | 191.0 | 313.0 | 266.0 | 120.0 | 20.0 | 0.0 | 0.0 | 996.0 |
| Degree Days % of Annual | 0.0% | 0.0% | 0.0% | 0.0% | 8.6% | 19.2% | 31.4% | 26.7% | 12.0% | 2.0% | 0.0% | 0.0% | 100% |
| Degree Days % of Maximum | 0.0% | 0.0% | 0.0% | 0.0% | 27.5% | 61.0% | 100.0% | 85.0% | 38.3% | 6.4% | 0.0% | 0.0% | |
| Baseline kWh | 0 | 0 | 0 | 0 | 3,105 | 6,897 | 11,302 | 9,605 | 4,333 | 722 | 0 | 0 | 35,963 |
| Proposed kWh | 0 | 0 | 0 | 0 | 831 | 1,845 | 3,024 | 2,570 | 1,159 | 193 | 0 | 0 | 9,622 |
| kWh Savings | 0 | 0 | 0 | 0 | 2,274 | 5,051 | 8,278 | 7,035 | 3,174 | 529 | 0 | 0 | 26,341 |
| Baseline kW | 0.00 | 0.00 | 0.00 | 0.00 | 8.07 | 17.91 | 29.36 | 24.95 | 11.26 | 1.88 | 0.00 | 0.00 | 29.36 |
| Proposed kW | 0.00 | 0.00 | 0.00 | 0.00 | 2.16 | 4.79 | 7.85 | 6.68 | 3.01 | 0.50 | 0.00 | 0.00 | 7.85 |
| kW Savings | 0.00 | 0.00 | 0.00 | 0.00 | 5.91 | 13.12 | 21.50 | 18.27 | 8.24 | 1.37 | 0.00 | 0.00 | 21.50 |

DETAILED CALCULATIONS

JAN 2012 V2.0

Salesforce Opportunity Name Cincinnati Public Schools - Hartwell - HVAC and Lighting Application # 12-313 MSD Project Name Cincinnati Public Schools - Hartwell - HVAC and Lighting ECM Cincinnati Public Schools - Hartwell - HVAC and Lighting - Energy Recovery Wheel for AHU-2

Note: all data from "Hartwell.HRW.Calcs.xlsx", except as otherwise noted

USA_OH_Cincinnati.Muni.AP-Lunken.Field.724297_TMY3.bin HEAT RECOVERY WHEEL SAVINGS

> Minimum Fraction Outdoor Air: 42.89% Heat Recover Effectiveness: 75.20% Set Point Temperature: 75.6 F Set Point Enthalpy: 27.281 Btu/lba Supply Air Temperature: 51.4 F Supply Air Enthalpy: 20.996 Btu/lba Supply Air Volume: 24,400 cfm Supply Air Density: 0.075 lb/ft^3

| | Supply / | an Density. | 0.075 | 10/11/3 | | | | | | |
|-----------------------------|-------------------|-------------|------------------|-----------------------------------|------|------------|------------------|--------------|--------------|--------------|
| | | | | | | | | Savings | Baseline | Proposed |
| StrTemp (F) | EndTemp (F) | Toa (F) | hoa (Btu/lba) | hrs | foa | Tma (F) | hma (Btu/lba) | Q (mmBTU) | Q (mmBTU) | Q (mmBTU) |
| 105 | 109 | 107.0 | 0 | 0 | 43% | 89.1 | 15.58 | 0.00 | 0.00 | 0.00 |
| 100 | 104 | 102.0 | 0 | 0 | 43% | 86.9 | 15.58 | 0.00 | 0.00 | 0.00 |
| 95 | 99 | 96.1 | 42.6 | 12 | 43% | 84.4 | 33.85 | 6.51 | 8.66 | 2.15 |
| 90 | 94 | 92.2 | 39.6 | 41 | 43% | 82.7 | 32.56 | 17.89 | 23.79 | 5.90 |
| 85 | 89 | 87.6 | 37.7 | 142 | 43% | 80.7 | 31.75 | 52.39 | 69.67 | 17.28 |
| 80 | 84 | 82.4 | 35.0 | 250 | 43% | 78.5 | 30.59 | 68.34 | 90.88 | 22.54 |
| 75 | 79 | 77.2 | 33.4 | 287 | 43% | 76.3 | 29.91 | 62.19 | 82.70 | 20.51 |
| 70 | 74 | 72.5 | 31.9 | 241 | 100% | 72.5 | 31.90 | 91.91 | 122.23 | 30.31 |
| 65 | 69 | 68.0 | 29.1 | 252 | 100% | 68.0 | 29.10 | 37.85 | 50.33 | 12.48 |
| 60 | 64 | 62.6 | 24.8 | 322 | 100% | 62.6 | 24.80 | 0.00 | 0.00 | 0.00 |
| 55 | 59 | 57.1 | 21.9 | 222 | 100% | 57.1 | 21.90 | 0.00 | 0.00 | 0.00 |
| 50 | 54 | 52.0 | 19.2 | 226 | 100% | 52.0 | 19.20 | 0.00 | 0.00 | 0.00 |
| 45 | 49 | 47.5 | 17.3 | 151 | 86% | 51.4 | 18.69 | 0.00 | 0.00 | 0.00 |
| 40 | 44 | 43.1 | 15.2 | 211 | 74% | 51.4 | 18.29 | 0.00 | 0.00 | 0.00 |
| 35 | 39 | 37.6 | 12.9 | 206 | 64% | 51.4 | 18.12 | 0.00 | 0.00 | 0.00 |
| 30 | 34 | 32.4 | 10.8 | 135 | 56% | 51.4 | 18.05 | 0.00 | 0.00 | 0.00 |
| 25 | 29 | 27.7 | 9.0 | 99 | 51% | 51.4 | 18.05 | 0.00 | 0.00 | 0.00 |
| 20 | 24 | 23.3 | 7.5 | 66 | 46% | 51.4 | 18.13 | 0.00 | 0.00 | 0.00 |
| 15 | 19 | 18.3 | 5.9 | 36 | 43% | 51.0 | 18.11 | 0.00 | 0.00 | 0.00 |
| 10 | 14 | 12.5 | 4.1 | 16 | 43% | 48.5 | 17.34 | 0.00 | 0.00 | 0.00 |
| 5 | 9 | 7.5 | 2.7 | 5 | 43% | 46.4 | 16.74 | 0.00 | 0.00 | 0.00 |
| 0 | 4 | 3.0 | 1.4 | 0 | 43% | 44.5 | 16.18 | 0.00 | | 0.00 |
| | | | | | | Annual Tot | al mmBTU: | 337.09 | 448.25 | 111.17 |
| Energy r | recovery wheel mo | | | | | Annual | Ton-hours: | 28,090 | 37,354 | 9,264 |
| | Motor Size hp: | 1.50 | | | | (| Chiller IPLV: | 13.1 | 13.1 | 13.1 |
| Load Factor: 0.85 | | | | Chiller kW/Ton: | | | | 0.916 | 0.916 | 0.916 |
| Motor Efficiency: 84.0% | | | | | | | oling kWh: | 25,732 | 34,218 | 8,486 |
| hp to kW conversion: 0.7456 | | | | Heat Recovery Hours of Operation: | | | | 1,225 | 1,225 | 1,225 |
| Motor kW: 1.132 | | | | | | C | 21.01 | 27.93 | 6.93 | |
| | Motor kWh: | 1,386 | | | | | | | | |

Allocation of annual savings by month (Added During Tech Review)

Trade ally only provided annual savings numbers. Combine HRW savings and motor use, then use % of cooling degree days by month to distribute annual savings appropriately.

| Cooling Degree Day Source. | | TILLD.// WWY | w.ciiiiiate-zc | one.com/cm | nate/ united | a states/one | O/greater c | memmati an | porty | | | | |
|----------------------------|------|--------------|----------------|------------|--------------|--------------|-------------|------------|-------|------|------|------|--------|
| | Jan | Feb | Mar | April | May | June | July | Aug | Sep | Oct | Nov | Dec | Annual |
| CDD by Month | 0.0 | 0.0 | 0.0 | 0.0 | 86.0 | 191.0 | 313.0 | 266.0 | 120.0 | 20.0 | 0.0 | 0.0 | 996.0 |
| Degree Days % of Annual | 0.0% | 0.0% | 0.0% | 0.0% | 8.6% | 19.2% | 31.4% | 26.7% | 12.0% | 2.0% | 0.0% | 0.0% | 100% |
| Degree Days % of Maximum | 0.0% | 0.0% | 0.0% | 0.0% | 27.5% | 61.0% | 100.0% | 85.0% | 38.3% | 6.4% | 0.0% | 0.0% | |
| Baseline kWh | 0 | 0 | 0 | 0 | 2,955 | 6,562 | 10,753 | 9,138 | 4,123 | 687 | 0 | 0 | 34,218 |
| Proposed kWh | 0 | 0 | 0 | 0 | 852 | 1,893 | 3,102 | 2,637 | 1,189 | 198 | 0 | 0 | 9,872 |
| kWh Savings | 0 | 0 | 0 | 0 | 2,102 | 4,669 | 7,651 | 6,502 | 2,933 | 489 | 0 | 0 | 24,345 |
| Baseline kW | 0.00 | 0.00 | 0.00 | 0.00 | 7.67 | 17.05 | 27.93 | 23.74 | 10.71 | 1.78 | 0.00 | 0.00 | 27.93 |
| Proposed kW | 0.00 | 0.00 | 0.00 | 0.00 | 2.21 | 4.92 | 8.06 | 6.85 | 3.09 | 0.51 | 0.00 | 0.00 | 8.06 |
| kW Savings | 0.00 | 0.00 | 0.00 | 0.00 | 5.46 | 12.13 | 19.87 | 16.89 | 7.62 | 1.27 | 0.00 | 0.00 | 19.87 |

Appendix C - Hartwell - Cash Rebate Calculation

HVAC and Lighting

| Measure | Quantity | Cash Rebate Rate | Cash Rebate |
|---|----------|---|-------------|
| | | 50% of incentive that would be offered by | |
| Heat Recovery Unit Added - AHU - 1 | 1 | the Smart \$aver Custom program | \$2,000.00 |
| | | 50% of incentive that would be offered by | |
| Heat Recovery Unit Added - AHU - 2 | 1 | the Smart \$aver Custom program | \$1,900.00 |
| | | 50% of incentive that would be offered by | |
| Lighting Power Density Improvement Over Code As Per Application | 1 | the Smart \$aver Custom program | \$600.00 |
| Totals | 3 | | \$4,500.00 |

Appendix D -Hartwell - UCT Value

HVAC and Lighting

| Measure | Total Avoided Cost | Program Cost | Incentive | Quantity | Measure UCT |
|---|---------------------------|---------------------|-----------|----------|-------------|
| Heat Recovery Unit Added - AHU - 1 | \$31,813 | \$1,053 | \$2,000 | 1 | 10.42 |
| Heat Recovery Unit Added - AHU - 2 | \$29,403 | \$995 | \$1,900 | 1 | 10.16 |
| Lighting Power Density Improvement Over Code As Per | | | | | |
| Application | \$8,949 | \$377 | \$600 | 1 | 9.16 |
| Totals | \$70,165 | \$2,425 | \$4,500 | 3 | |

Total Avoided Supply Costs \$70,165

Total Program Costs \$2,425.00

Total Incentive \$4,500

Aggregate Application UCT

10.13

Cincinnati Public Schools (Hartwell)
Mercantile Self Direct Custom Application
Documents Not Attached Due To Size But
Available Upon Request

- Lighting Plans
- Lighting Specifications

Ohio Mercantile Self Direct Program

Application Guide & Cover Sheet

Questions? Call 1-866-380-9580 or visit www.duke-energy.com.

Email this form along with <u>completed Mercantile Self Direct Prescriptive or Custom applications</u>, proof of payment, energy savings calculations and spec sheets to <u>SelfDirect@Duke-Energy.com</u>. You may also fax to 1-513-419-5572.

| Mercantile customers, defined as using at least 700,000 kWh annually are eligible for the Mercantile Self Direct program. Please indicate mercantile qualification: a single Duke Energy Ohio account multiple accounts in Ohio (energy usage with other utilities may be counted toward the total) | | | | | | | | |
|---|------------------------------------|--|-------------------------------------|--|--|--|--|--|
| Please list Duke Energy account | numbers below (attach listing of m | ultiple accounts an/or billing history | y for other utilities as required): | | | | | |
| Account Number | Annual Usage | Account Number | Annual Usage | | | | | |
| 0250-2096-01 | | | | | | | | |

Self Direct rebates are available for completed Custom projects that have not previously received a Duke Energy Smart \$aver® Custom Incentive. Self Direct incentives are applicable to Prescriptive measures that were installed more than 90 days prior to submission to Duke Energy and have not previously received a Duke Energy Prescriptive rebate.

Self Direct Program requirements dictate that certain projects that may be Prescriptive in nature under the Smart \$aver program must be evaluated using the Custom process. Use the table on page two as a guide to determine which Self Direct program fits your project(s). Apply for Self Direct projects using the appropriate application forms in conjunction with this cover sheet. Where Mercantile Self Direct Prescriptive applications are listed, please refer to the measure list on that application. If your measure is not listed, you may be eligible for a Self Direct Custom rebate. Self Direct Custom applications, like Smart \$aver Custom applications, should include detailed analysis of pre-project and post-project energy usage and project costs. Please indicate which type of rebate applications are included in the table provided on page two.

Please check each box to indicate completion of the following program requirements:

| Tiense enteen enen con to marente con | inpretion of the folio wing program re- | quirements. | |
|---------------------------------------|---|----------------------------|---------------------------------|
| | | Manufacturer's Spec sheets | □ Energy model/calculations and |
| application(s) are completed | | | detailed inputs for Custom |
| | | | applications |

^{*} If a single payment record is intended to demonstrate the costs of both Prescriptive & Custom projects, please include an additional document with an estimated breakout of costs for each Prescriptive and Custom energy conservation measure.

| Application Type | Replaced equipment at end of lifetime or because equipment failed** | Replaced fully operational equipment to improve efficiency*** | New Construction |
|---|---|---|--|
| | MSD Custom Part 1 | MSD Prescriptive Lighting | MSD Prescriptive Lighting |
| Lighting | Custom Lighting Worksheet | MSD Custom Part 1 Custom Lighting Worksheet | MSD Custom Part 1 ⊠ Custom Lighting Worksheet ⊠ |
| Heating & Cooling | MSD Custom Part 1 | MSD Custom Part 1 | MSD Prescriptive Heating & Cooling |
| Treating & Cooning | MSD Custom General Worksheet | MSD Custom General Worksheet | MSD Custom Part 1 ⊠ MSD Custom General Worksheet ⊠ |
| Window Films, Programmable Thermostats, & Guest Room Energy Management Systems | MSD Custom Part 1 ☐ MSD Custom General and/or EMS Worksheet(s) ☐ | MSD Prescriptive Heating & Cooling | MSD Custom Part 1 ☐ MSD Custom General and/or EMS Worksheet(s) ☐ |
| Chillers & Thermal | MSD Custom Part 1 | MSD Custom Part 1 | MSD Prescriptive Chillers & Thermal Storage □ |
| Storage | MSD Custom General Worksheet | MSD Custom General Worksheet | MSD Custom Part 1 MSD Custom General Worksheet |
| Motors & Dumns | MSD Custom Part 1 | MSD Custom Part 1 | MSD Prescriptive Motors, Pumps & Drives |
| Motors & Pumps | MSD Custom General Worksheet | MSD Custom General Worksheet | MSD Custom Part 1 MSD Custom General Worksheet |
| 17ED | N (A - 1' - 1 1 | MSD Prescriptive Motors, Pumps & Drives □ | MSD Custom Part 1 |
| VFDs | Not Applicable | MSD Custom Part 1 MSD Custom VFD Worksheet | MSD Custom VFD Worksheet |
| | MSD Custom Part 1 | MSD Custom Part 1 | MSD Prescriptive Food Service |
| Food Service | MSD Custom General Worksheet | MSD Custom General Worksheet | MSD Custom Part 1 ☐ MSD Custom General Worksheet ☐ |
| | MSD Custom Part 1 | MSD Prescriptive Process | MSD Custom Part 1 |
| Process | MSD Custom General Worksheet | MSD Custom Part 1 ☐ MSD Custom General Worksheet ☐ | MSD Custom General Worksheet |
| Energy Management Systems | MSD Custom Part 1 MSD Custom EMS Worksheet | MSD Custom Part 1 MSD Custom EMS Worksheet | MSD Custom Part 1 MSD Custom EMS Worksheet |
| Behavioral*** & No/Low Cost | | MSD Custom Part 1 | |

^{**} Under the Self Direct program, failed equipment and equipment at the end of its useful life are evaluated differently than early replacement of fully functioning equipment. **All equipment replacements due to failure or old age will be evaluated via the Custom program.**

^{***} Please ensure that you include the age of the replaced equipment for measures classified as "Early Replacement" in your application as well as the estimated date that you would have otherwise replaced the existing equipment if you had not chosen a more energy efficient option.

^{****} Behavioral energy efficiency and demand reduction projects must be both measurable and verifiable. Provide justification with your application.



Proposed energy efficiency measures may be eligible for Self-Direct Custom rebates if they clearly reduce electrical consumption and/or demand as compared to the appropriate baseline.

Before you complete this application, please note the following important criteria:

- Submitting this application does not guarantee a rebate will be approved.
- Rebates are based on electricity conservation only.
- Electric demand and/or energy reductions must be well documented with auditable calculations.
- Incomplete applications cannot be reviewed; all fields are required.

Refer to the complete list of Instructions and Disclaimers, beginning on page 6.

Notes on the Application Process

If you have any questions concerning how to complete any portion of the application or what supplementary information is required, please contact your Duke Energy Ohio, Inc account manager or the Duke Energy Smart \$aver® team at 1-866-380-9580.

Every application must include calculations of the baseline electrical usage and the electrical usage of the proposed high-efficiency equipment/system. Monthly calculations are best. You, the Duke Energy Ohio customer, or your equipment vendor / engineer should perform these calculations and submit them to Duke Energy for review. We strongly encourage the use of modeling software (such as eQuest or comparable) for complex projects.

Upon receipt of your application, an acknowledgement email will be sent to you with an estimated response time based on an initial assessment of your application. The application review may include some communication to resolve any questions about the project or to request additional information. Applications that are received complete without missing information have a faster review time.

There are two ways to submit your completed application.

Email your scanned form to: <u>SelfDirect@duke-energy.com</u>

Or, fax your form to 513-419-5572

Page 1 Rev 7/11



1. Contact Information (Required)

| Duke Energy Cu | stomer Co | ontact Ir | formation | | | | | | | |
|--|---|----------------------------------|------------------|-------|-------|-------|------------|------|---------|--|
| Company Name | Cincinnat | ncinnati Public Schools | | | | | | | | |
| Address | 2651 Bur | 551 Burnett Ave | | | | | | | | |
| Project Contact | Don Elbe | on Elbe | | | | | | | | |
| City | Cincinnat | ncinnati State OH Zip Code 45219 | | | | | | | | |
| Title | | | | | | | | | | |
| Office Phone | | Mobile Phone Fax | | | | | | | | |
| E-mail Address | | | | | | | | | | |
| | | | | | | | | | | |
| Equipment Vendor / Contractor / Architect / Engineer Contact Information | | | | | | | | | | |
| Company Name | Plug Sma | rt | | | | | | | | |
| Address | 1275 Kin | near Roa | d Suite 229 | | | | | | | |
| City | Columbu | S | | State | ОН | Zip C | ode | 430 | 085 | |
| Project Contact | Lucas Dix | Lucas Dixon | | | | | | | | |
| Title | Operation | ns Manag | ger | | | | | | | |
| Office Phone | 614-580- | 3352 | Mobile Phone | | | Fax | 1-8 | 00-5 | 18-5576 | |
| E-mail Address | lucas.dixo | on@plug | smart.com | | | | | | | |
| Describe Role | | | | | | | | | | |
| | | | | | | | | | | |
| Payment Informa | tion | | | | | | | | | |
| Payee Legal Com Name (as shown of Federal income ta | on . | Cincinn | ati Public Schoo | ls | | | | | | |
| Mailing Address | • | 2651 B | urnett Ave | 1 | | | | ı | | |
| City | Cincinnati State OH Zip Code 45219 | | | | | | | | | |
| Type of organization | nization (check one) Individual/Sole Proprietor Corporation Partnership overnment Non-Profit (non-corporation) | | | | | | | | | |
| Payee Federal Tax | | | | 1011) | | | | | | |
| Company Name A | bove: | | 31-6000758 | | _ | _ | | | | |
| Who should receive | e incentive | e payme | nt? (select one) | ⊠ Cus | tomer | | dor (Cu | | | |
| | must sign below) If the vendor is to receive payment, please sign below: I hereby authorize payment of incentive directly to vendor: | | | | | | <u>v j</u> | | | |

Page 2 Rev 7/11

Customer Signature ______ Date___/___(mm/dd/yyyy)



2. Project Information (Required)

| A. | Please indicate project type: New Construction Expansion at an existing facility Replacing equipment due to equipment failure Replacing equipment that is estimated to have remaining useful life of 2 years or less Replacing equipment that is estimated to have remaining useful life of more than 2 years Behavioral, operational and/or procedural programs/projects |
|-----|---|
| B. | Please describe your project, or attach a detailed project description that describes the project. Addition of heal wheels to a new air handler, lighting compliance check |
| C. | When did you start and complete implementation? Start date / (mm/yyyy) End date / (mm/yyyy) |
| D. | Are you also applying for Self-Direct Prescriptive incentives and, if so, which one(s) ¹ ? Premium efficient motors, prescriptive occupancy sensors |
| E. | Please indicate which worksheet(s) you are submitting for this application (check all that apply): Lighting Variable Frequency Drive (VFD) Compressed Air Energy Management System (EMS) General (for projects not easily submitted using one of the above worksheets) |
| F. | Please tell us if there is anything about your electrical energy projections (either for the baseline or the proposed project) that you are either unsure about or for which you have made significant assumptions. Attach additional sheets as needed. |
| the | quired: Attach a supplier or contractor invoice or other equivalent information documenting Implementation Cost for each project listed in your application. (Note: self-install costs not be included in the Implementation Cost) |

Page 3 Rev 7/11

¹ If your project involves some equipment that is eligible for prescriptive incentives and some equipment that is likely eligible for custom incentives, and if it is feasible to separate the equipment for the energy analysis, then the equipment will be evaluated separately. If it is not feasible to separate the equipment for analysis, then the equipment will be evaluated together in the custom application.



3. Signature (Required - must be signed by Duke Energy customer)

Customer Consent to Release of Personal Information

Inc Account Number and Federal Tax ID Number in the strictest of confidence.

I, (insert name) <u>Fibe</u>, do hereby consent to Duke Energy disclosing my Duke Energy Ohio, Inc Account Number and Federal Tax ID Number to its subcontractors solely for the purpose of administering Duke Energy Ohio's Mercantile Self-Direct Program. I understand that such subcontractors are contractually bound to otherwise maintain my Duke Energy Ohio,

I realize that under the rules and regulations of the public utilities commission, I may refuse to allow Duke Energy Ohio, Inc to release the information set forth above. By my signature, I freely give Duke Energy Ohio, Inc permission to release the information designated above.

Application Signature

I certify that I meet the eligibility requirements of the Duke Energy Ohio, Inc Mercantile Self Direct Custom Incentives Program and that all information provided within this application is correct to the best of my knowledge. I agree to the terms and conditions set forth for this program. I certify that the numbers, energy savings, and responses shown on this form are correct. Further, I certify that the taxpayer identification number is current and correct. I am not subject to backup withholding because: (a) I am exempt from backup withholding; or (b) I have not been notified by the IRS that I am subject to backup withholding as a result of a failure to report all interest or dividends; or (c) the IRS has notified me that I am no longer subject to backup withholding. I am a U.S. citizen (includes a U.S. resident alien).

Duke Energy Ohio, Inc Customer Signature

Print Name Don Elbe

Date 6-6-12



Checklist for completing the Application

INCOMPLETE APPLICATIONS WILL RESULT IN DELAYS IN DUKE ENERGY PROCESSING YOUR APPLICATION AND NOTIFYING YOU CONCERNING AY REBATES. Before submitting the application and the required supplementary information, use the following checklist to ensure that your application is complete and the information in the application is accurate. (Note: this checklist is <u>for your use only</u> – do not submit this checklist with your application)

| Section No. & Title | Have You: |
|--------------------------------------|---|
| Contact Information | ☐ Completed the contact information for the Duke Energy customer? ☐ Completed the contact information for the equipment vendor / project engineer that can answer questions about the technical aspects of the project, if that is a different person than above? |
| 2. Project Information | Answered the questions A-E, including providing a description of your project. Completed and attached the lighting, compressed air, VFD, EMS and/or General worksheet(s)? |
| 3. Signature | Signed your name?Printed your name?Entered the date? |
| Supplementary information (Required) | ☐ Attached a supplier or contractor's invoice or other equivalent information documenting the Implementation Cost for projects listed in your application? (Note: self-install costs cannot be included in the Implementation Cost) ☐ (If submitting the General Worksheet) attached calculations documenting the energy usage and energy savings for each project listed in your application? |

If you have any questions concerning how to complete any portion of the application or what supplementary information is required, please contact:

- your Duke Energy account manager or
- the Duke Energy Smart \$aver® team at 1-866-380-9580.

Page 5 Rev 7/11



Instructions/Terms/Conditions

Note: Please keep for your records- do not submit with the application

- Energy service companies or contractors may assist in preparing the application, but an authorized representative of the customer must sign this application to be eligible to participate in the Mercantile Self Direct Program. Completion of this application does not guarantee the approval of a Self Direct Custom Rebate.
- 2. Once all documentation requested in this application is received by *Duke Energy Ohio, Inc,* and any follow-up information requested by *Duke Energy* is received, the rebate amount for each Energy Conservation Measure (ECM) will be communicated to the customer. The rebate amount will be based on ECM energy savings and ECM incremental installation cost.
- 3. All rebates require approval by the Public Utilities Commission of Ohio. *Duke Energy Ohio, Inc* will submit an application for rebate on the customer's behalf upon customer attestation to program terms, conditions and requirements as outlined in the rebate offer letter and upon customer completion of attestation documents required by the Public Utilities Commission of Ohio.
- 4. Duke Energy Ohio, Inc will issue a Self Direct Custom Rebate check, based on the approved rebate amount for each ECM, upon receiving approval from the Public Utilities Commission of Ohio. Duke Energy Ohio, Inc does not guarantee PUCO approval.
- 5. With the application, the customer must provide a list of all sites where the ECMs were installed. Duke Energy Ohio, Inc requests that sites of similar size, hours of operation and energy consuming characteristics be grouped together in one application for the determination of the rebate amount. The application should identify the site where each unique ECM was installed.
- 6. Based on the information submitted with the application and the information gathered both before and after the initial installation of the ECM, *Duke Energy Ohio, Inc* will calculate the rebate amount for each ECM.
- 7. Duke Energy Ohio, Inc may conduct random site inspections of a sample of the locations where the ECMs are installed to verify installation and operability of the ECMs and to obtain information needed to calculate the Approved Incentive Amount.
- 8. Customers are encouraged to retain copies of all forms, invoices and supporting documentation for their records.
- 9. Approved rebates are valid for 6 months from the date communicated to the customer by *Duke Energy Ohio, Inc,* subject to the expiration of measure eligibility based on project completion dates and application submission deadlines as defined by PUCO. Customers are encouraged to execute their rebate offer contracts and PUCO-required affidavits promptly to ensure eligibility is not forfeited.
- 10. *Duke Energy Ohio, Inc* reserves the right to recover all unrecoverable costs associated with the project approval if the customer decides not to execute the rebate contract, after the project is approved by *Duke Energy Ohio, Inc.*
- 11. Projects financially supported by other funding sources will be evaluated on a case-by-case basis for potential partial funding from *Duke Energy Ohio*, *Inc*.
- 12. Participants must be *Duke Energy Ohio, Inc* nonresidential, mercantile customers with the project sites in the *Duke Energy Ohio, Inc* service territory.

Page 6 Rev 7/11



- 13. Customers or trade allies may not use any Duke Energy logo without prior written permission.
- 14. Only trade allies registered with *Duke Energy* are eligible to participate.
- 15. All equipment must be new. Used or rebuilt equipment is not eligible for incentives. All old existing equipment must be removed on retrofit projects.
- 16. Disclaimers: Duke Energy Ohio, Inc.
 - a. does not endorse any particular manufacturer, product or system design within the program;
 - b. will not be responsible for any tax liability imposed on the customer as a result of the payment of incentives;
 - c. does not expressly or implicitly warrant the performance of installed equipment. (Contact your contractor for details regarding equipment warranties.);
 - d. is not responsible for the proper disposal/recycling of any waste generated or obsolete or old equipment as a result of this project;
 - e. is not liable for any damage caused by the installation of the equipment nor for any damage caused by the malfunction of the installed equipment; and
 - f. reserves the right to change or discontinue this program at any time. The acceptance of program applications is determined solely by *Duke Energy Ohio, Inc.*

Page 7 Rev 7/11

Mercantile Self Direct

Wercantile Self Direct

Nonresidential Custom Incentive Application

GENERAL CUSTOM APPLICATIONS WORKSHEET - CUSTOM GENERAL APPLICATION PART 2

Page 1 of 3 Rev 7/11



The General Worksheet is part 2 of the application. Do not submit this file without submitting a completed Part1 Custom Application document file, which can be found at www.duke-energy.com. This worksheet is for all projects that are not easily submitted through one of the other worksheets

Before you complete this application, please note the following important criteria:

- · Submitting this application does not guarantee an incentive will be approved.
- · Incentive already decided to proceed.
- · Electric demand and/or energy reductions must be well documented with auditable calculations.
- · Incomplete applications will not be reviewed; all fields are required.

Refer to the complete list of Instructions and Disclaimers, found in the Mercantile Self Direct Custom Application Part 1 document.

Please enter your information and data into the cells that are shaded.
Cells in white are locked and cannot be written over.

Duke Energy Customer Contact Information (Match the information in Application Part 1):

Name Don Elbe

Company Cincinnati Public Schools

Equipment Vendor / Project Engineer Contact Information

Name

Lucas Dixon

Company

Plug Smart

Before proceeding with the custom application, please verify that your project is not on the Self-Direct Prescriptive application.

The prescriptive incentive applications can be found at:

http://www.duke-energy.com/ohio-large-business/smart-saver/mercantile-self-direct.asp

Prescriptive rebate amounts are pre-approved.

Hartwell.Custom.Gen.xls Input Data 1 of 3

Page 2 of 3
Rev 7/11

Energy

List of Sites (Required)

Provide a list of sites addressed by this custom incentive application

| App No. | |
|---------|--|
| Rev. | |

| Site ID | Duke Energy Electric Account Number(s) (see note 2) | Facility Address | List of Proposed Projects at each site | Annual Hours of Operation | Gross Square Footage | Conditioned Square Footage | Facility Age (years) |
|---------|---|--|--|---------------------------------|----------------------------|----------------------------------|----------------------------|
| 225 | 12345678 01 | Example: 123 Main Street, Anywhere USA 12345 | Project Name(s) | 5,840 | 42,000 | 38,000 | 12 |
| | 0250-2096-01 | 8320 Vine St Cincinnati OH 45216 | Heat Recovery Wheels | 1,225 | 70,209 | 70,209 | |
| | | | , | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

1 Site ID

Can be a store number, building name or other way to identify the location. If there is only one site involved in this application, then a Site ID is not necessary.

2 Account Numbers

Must match the facility of the proposed project(s). If there are multiple meters at a site, only include the meters that pertain to the project(s).

Hartwell.Custom.Gen.xls Input Data 2 of 3

Mercantile Self Direct

Page 3 of 3

Nonresidential Custom Incentive Application

GENERAL CUSTOM APPLICATIONS WORKSHEET - CUSTOM GENERAL APPLICATION PART 2

Rev 7/11

0

For each project, answer the following questions (use one worksheet per project) oN aaA Project Name: **Heat Recovery Units** Rev.

How would you classify this project? (Place an x in all boxes that apply.)

| Lighting | Heating/Cooling | X | Air Compressor | Energy Management System | |
|----------|-----------------|---|--------------------------|---------------------------------|--|
| VFD | Motors/Pumps | | Process Equipment | Other, describe below: | |
| | | | | | |

Brief Project Description

| Describe the Baseline (see note 3) Equipment/System Describe the Proposed High Efficiency Project | | | | | | |
|---|---|--|--|--|--|--|
| No heat recovery units installed on air handlers Heat recovery units installed on air handlers. | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| If Existing Equipment is the Baseline, how many years of useful life | e remain or how many years until scheduled replacement? | | | | | |

Detailed Project Description Attached? Yes (Required)

Operating Hours (see note 4)

| ſ | | | | | | | | Weeks of | |
|---|--------|------------|----------|------------|----------|------------|----------|--------------|--------------|
| ı | | Weekday | | Saturday | | Sunday | | Use in Year | Total Annual |
| | 24 x 7 | Start Hour | End Hour | Start Hour | End Hour | Start Hour | End Hour | (see note 5) | Hours of Use |
| | | 7:00 AM | 3:00 PM | | | | | 29 | 1,225 |

Energy Savings

| Liter by Savings | | | | |
|------------------------|-----------------------|----------|------------|---|
| | Baseline (see Note 3) | Proposed | Savings | |
| | | - | | Describe how energy numbers were calculated |
| Annual Electric Energy | 51,980 kWh | 0 kWh | 51,980 kWh | |
| Electric Demand | 0 kW | 0 kW | 0 kW | |
| Calculations attached | Yes | Yes | (Required) | fore, baseline is listed as the savings with proposed at 0 kWh. See attached Covedale.H |

Simple Payback

| Simple I ayback | | | | | _ |
|--|-----------------|-------------------------|--|-------------|---|
| Average electric rate (\$/kWh) on the applicab | \$0.10 | | | | |
| Estimated annual electric savings | \$5,198 | | | | |
| Other annual savings in addition to electric sa | | | | | |
| Incremental cost to implement the project (ed | quipment & inst | :allation) (see note 7) | | \$16,000.00 | |
| Copy of vendor proposal is attached (see note 8) | Yes | | | | |
| Simple Electric Payback in years (see note 9) | | 3.078106964 | | | |

з Baseline

Retrofit projects: the existing equipment is the baseline.

New construction projects: the baseline is the standard option in today's market, taking into account any applicable organizational, local, state or federal codes or standards currently in effect.

4 Operating Hours

Describe when the equipment is typically used. If the project is proposed for more than one site, provide any variations in operating hours between the sites on a separate sheet.

5 Weeks of Use in Year

If the equipment is not in use 52 weeks during the year (for example, during holiday or summer break), provide an explanation of when usage is not expected and why: Savings only calculated for summer hours, gas heating systems are used during the winter.

6 Average electric rate (\$/kWh)

If you do not know your average electric rate, use \$0.10/kWh.

7 Incremental cost to implement the project

Costs exclude self installation costs. Retrofit projects, incremental cost is the total cost of the proposed project. New construction or where the existing equipment must be replaced anyway, then incremental cost is the premium of the proposed high efficiency project over baseline.

8 Copy of vendor invoice is attached

Vendor invoices detailing costs of the project are always required.

New construction projects or where the existing equipment must be replaced anyway, vendor proposal of baseline must also be attached.

9 Simple Electric Payback

If the simple electric payback is less than 1 year, the rebate structure is affected. Double check average electric rate for correct payback.

Hartwell.Custom.Gen.xls Input Data 3 of 3 CUSTOM LIGHTING APPLICATION PART 2

Rev 5/11



The Lighting Worksheet is part 2 of the application. Do not submit this file without submitting a completed Part1 Custom Application document file, which can be found at www.duke-energy.com.

Before you complete this application, please note the following important criteria:

- · Incentive approval is required PRIOR to equipment purchase, or any other activity which would indicate that the Duke Energy customer has already decided to proceed.
- · Submitting this application does not guarantee an incentive will be approved.
- · Incentives are based on electricity conservation only.
- · Electric demand and/or energy reductions must be well documented with auditable calculations.
- · Simple payback without incentive must be greater than 1 year.
- · Incomplete applications will not be reviewed; all fields are required.

Refer to the complete list of Instructions and Disclaimers, found in the Custom Application Part 1 document.

Please enter your information and data into the cells that are shaded.
Cells in white are locked and cannot be written over.

Duke Energy Customer Contact Information (Match the information in Application Part 1):

Name Don Elbe

Company Cincinnati Public Schools

Equipment Vendor / Project Engineer Contact Information

Name Lucas Dixon
Company Plug Smart

Before proceeding with the custom application, please verify that your project is not on the prescriptive incentive application.

The prescriptive incentive applications can be found at:

KY http://www.duke-energy.com/kentucky-business/energy-management/energy-efficiency-incentives.asp

Kentucky only: custom incentives only available to K-12 school facilities; prescriptive incentives available for those not on rate TT.

OH http://www.duke-energy.com/ohio-business/energy-management/energy-efficiency-incentives.asp

NC http://www.duke-energy.com/north-carolina-business/energy-management/energy-efficiency-incentives.asp

SC http://www.duke-energy.com/south-carolina-business/energy-management/energy-efficiency-incentives.asp

Prescriptive incentives are already pre-approved and the application is submitted after project implementation.

Take note of the equipment eligibility on the prescriptive application before planning to utilize the prescriptive application.



Please enter your information and data into the cells that are shaded. Cells in white are locked and cannot be written over.

List of Sites (Required)

| Project/ Site | | Electric Account Number(s) (see | | Area | Location within | | Indoor or |
|---------------|---------------------|---------------------------------|--|---------|-----------------|---------------|-----------|
| (see note 1) | Site Name | note 2) | Site Address | (sq ft) | Facility | Location Type | Outdoor? |
| Example | Distribution Center | 12345678 01 | Example: 123 Main Street, Anywhere USA 12345 | 1000 | Warehouse | Industrial | Indoor |
| 1 | Hartwell | 0250-2096-01 | 8320 Vine St Cincinnati OH 45216 | 70,209 | Classroom | K-12 | Indoor |
| 2 | | | | | | | |
| 3 | | | | | | | |
| 4 | | | | | | | |
| 5 | | | | | | | |
| 6 | | | | | | | |
| 7 | | | | | | | |
| 8 | | | | | | | |
| 9 | | | | | | | |
| 10 | | | | | | | |
| 11 | | | | | | | |
| 12 | | | | | | | |
| 13 | | | | | | | |
| 14 | | | | | | | |
| 15 | | | | | | | |
| 16 | | | | | | | |
| 17 | | | | | | | |
| 18 | | | | | | | |
| 19 | | | | | | | |
| 20 | | | | | | | |

| If your application involves more than 20 lighting projects, please check here and use multiple worksheets. | |
|---|--|
|---|--|

1 Project/Site

You can write over the default project/site number with a store #, building identifier, or other reference that distinguishes one project/location from another.

2 Electric Account Number(s)

If there are multiple meters at a site, only include the Duke Energy account numbers that pertain to the project.

Currently active account number(s) are required for an existing facility. For new construction, write in "new construction."

Rev 5/11



| | | | | | Hours of Use | (see note 3) | | Controls (see note 5) | | | | | e note 5) |
|----------|--------|------------|------------|------------|--------------|--------------|----------|-----------------------|--------------|---------|-----------|-----------|-------------------------------------|
| | | | | | | | | Weeks of Use | | Exis | iting | Proposed | |
| Project/ | | Weel | | Satu | | Sun | | in Year (see | Total Annual | Type of | Hours | Type of | |
| Site | 24 x 7 | Start Hour | End Hour | Start Hour | End Hour | Start Hour | End Hour | note 4) | Hours of Use | Control | Reduction | Control | Description |
| Example | No | 8:00 AM | 7:00 PM | 10:00 AM | 6:00 PM | 1:00 PM | 6:00 PM | 52 | 3,536 | None | 0% | Occupancy | Applying for Prescriptive Incentive |
| 1 | No | 7:00:00 AM | 3:00:00 PM | | | | | 52 | 2,080 | None | | Occupancy | Applying for Prescriptive Incentive |
| 2 | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | |
| 16 | | | | | | | | | | | | | |
| 17 | | | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | |
| 19 | | | | | | | | | | | | | |
| 20 | | | | | | | | | | | | | |

3 Hours of Use

For unoccupied times, leave applicable cells blank.

4 Weeks of Use in Year

If the lighting fixtures are not in use 52 weeks during the year (for example, during holiday or summer break), provide an explanation of when they are not expected to be in use and why:

Majority not being used for holiady or summer break, or spring break, due to school not being in session. Janitorial/Maintenance and some office work expected to continue, however.

5 Controls

Please attach more description of existing and/or proposed controls if more space is needed. If sufficient description is not provided, then controls portion of project will not be evaluated. Attach assumptions and calculations to support estimated reduction in hours that result from the controls.

New occupancy sensors should be applied for through the prescriptive application unless ineligible for prescriptive.

New or upgraded EMS/building controls require a separate application part 2. Without the separate application, EMS portion of the project will not be evaluated for an incentive.

Rev 5/11



| | | | | xisting Fixture(s |) | | | | |
|------------------|---|------------------------|-----------------------------------|---|-------------------------|-----------------|--|-----|-------------------------|
| Project/ Site | Existing Fixture Installation Year (see note 6) | Fixture Type | Fixture Manufacturer (see note 6) | Fixture Model Number (see note 6) | Lamps per Fixture | Fixture Size | Fixture Input Power (watts) (see note 7) | of | Total Demand (kW) |
| Example | 1995 | High Pressure Sodium | Manufacturer | Model # | 1 | | 190 | 175 | 33 |
| 1 | 2010 | Other (enter by typing | Comcheck | Code Specs | | | 84,250 | 1 | 84 |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |
| 11 | | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |

Application Total 1 84

6 Information on Existing Fixture(s)

Optional - please provide as much information as you can.

For new construction projects, provide information on the light fixture(s) that would meet the building code in your location.

7 Fixture Input Power (watts)

Provide actual input power (in watts), not nominal power rating. For example, a 400 watt (nominal) metal halide fixture has a typical input power of approximately 459 watts.

Rev 5/11



| _ | Proposed Fixture(s) | | | | | | | | | | Projected Savings | | | |
|-------------------------------------|---------------------|--------------|--|-------------------------|---------|---------------|----------|--------|-----------------|--------|-------------------|--------|-----------------|---------------------|
| | | Fixture | Fixture Model | Warranty of Proposed | Lamps | Fixture Input | Quantity | Total | Lumen Output | | | Annual | Other Annual | Incremental |
| Project/ | | Manufacturer | Number (see | Fixtures | per | Power (watts) | of | Demand | per | Lumen/ | Demand | Energy | Savings \$ (see | Project Cost |
| Site | Fixture Type | (see note 8) | note 8) | (years) | Fixture | | Fixtures | (kW) | Fixture | Sq Ft | (kW) | | note 10) | \$ (see note 11) |
| Example | T8 Fluorescent | Manufacturer | Model # | 5.0 | 1.0 | 78 | 225 | 18 | | 0 | | 55,515 | \$1,265 | \$29,215 |
| 1 | Comcheck | Proposed | | | | 76,366 | 1 | 76 | | 0 | 8 | 16,399 | | \$108,964 |
| 2 | | | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | |
| 7 | ' | | | | | | | | | | | | | |
| 8 | 3 | | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | | | |
| 14 | | | | | | | | | | | | | | |
| 15 | | | | | | | | | | | | | | |
| 16 | | | | | | | | | | | | | | |
| 17 | | | | | | | | | | | | | | |
| 18 | | | | | | | | | | | | | | |
| 19 | | | | | | | | | | | | | | |
| 20 | | | | | | | | | | | | | | |
| Application Total 1 76 8 16,399 \$0 | | | | | | | | | | | \$108,964 | | | |
| Average El | ectric Rate \$/kWh | \$0.10 | \$0.10 Project Simple Electric Payback (see note 12) years | | | | | | | | | | | |

8 Fixture Manufacturer and Model Number

Attach a scanned copy of a spec sheet for each fixture that includes the input power (watts), lumen output and other relevant information. For eligible LED fixtures, refer to the FAQs for Custom Incentives found at www.duke-energy.com and attach required documents if necessary.

9 Fixture Input Power (watts)

Provide actual input power (in watts), not nominal power rating. For example, a 400 watt (nominal) metal halide fixture has a typical input power of approximately 459 watts.

10 Other Annual Savings \$

Optional. Estimate other annual savings in addition to electric (for example operations/maintenance savings).

11 Incremental Project Cost \$

Attach a copy of a formal proposal with the projected project costs.

For new construction projects, a formal proposal is also required with the projected costs for the light fixture(s) that would meet the building code in your location.

12 Project Simple Electric Payback

If the simple payback on the project is less than 1 year, then the project is not eligible for a custom incentive. Please check that the electric rate is accurate based on history.



To whom it may concern:

This letter is to confirm for the **custom** rebate application, the lighting project and heat recovery wheels; and for the **prescriptive** rebate application, the occupancy sensors, premium efficiency motors, and a chiller were installed with a minimum unit cost listed below.

| Postal Code | 45216 |
|---------------------------------|----------------|
| State Code | OH |
| City Code | CINCINNATI |
| Address 1 | 8320 Vine St |
| Building Code | 427 |
| Annual of Colors Colored Colors | Hartwell (New) |

| Custom Rebate Items | Quantity | Price/Fixture | Cost to Replace |
|--|------------------------------|--|--------------------|
| 427-LGHT-A1 - Prismatic Lamp info: T8 32W 4100K 75 CRI (Min); qty | 62 | 77.00 | 4,774.00 |
| 2 | | | |
| 427-LGHT-A1X- Prismatic Lamp info: T8 32W 4100K 75 CRI (Min); qty | 6 | 175.00 | 1,050.00 |
| 2 427-LGHT-A2 - Prismatic Lamp info: T8 32W 4100K 75 CRI (Min); qty 2 | | 77.00 | 2 207 00 |
| THE STATE OF THE S | 31 6 | 4 - 44/44 - 4 (COMMAND) | 2,387.00 |
| 427-LGHT-A2X- Prismatic Lamp info: T8 32W 4100K 75 CRI (Min); qty | 0 | 175.00 | 1,050.00 |
| 427-LGHT-A31- Prismatic Lamp info: T8 32W 4100K 75 CRI (Min); qty | 11 | 77.00 | 847.00 |
| 3 | | | |
| 427-LGHT-B34- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); | 4 | 77.00 | 308.00 |
| qty 3 | alisa di sedal d a si | | |
| 427-LGHT-B38- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); qty 3 | 7 | 77.00 | 539.00 |
| 427-LGHT-C31- Parabolic Lamp: T8 32W 4100K 75 CRI (MIN); qty 3 | 15 | 77.00 | 1,155.00 |
| 427-LGHT-C32- Parabolic Master-Satellite Lamp:T8 32W 4100K, qty 3 | 24 | 77.00 | 1,848.00 |
| 427-LGHT-D5 - Wall Bracket Lamp: T8 32W 4100K 75 CRI (MIN); qty 2 | 12 | 77.00 | 924.00 |
| 427-LGHT-D5X- Wall Bracket Lamp: T8 32W 4100K 75 CRI (MIN); qty 2 | 1 | 175.00 | 175.00 |
| 427-LGHT-D7 - Wraparound Lamp: T8 32W 4100K 75 CRI (MIN); qty 2 | 15 | 77.00 | 1,155.00 |
| 427-LGHT-DA - Wall Mount Lamp: CFTR 42W 4100K 82 CRI; qty 2 | 8 | 77.00 | 616.00 |
| 427-LGHT-EX - Exit Sign - AC Only Lamp: LED; qty 1 | 53 | 77.00 | 4,081.00 |
| 427-LGHT-G3 - Prismatic Sealed Lamp T8 32W 4100K 75 CRI (MIN); | 11 | 77.00 | 847.00 |
| qty 3 | | | |
| 427-LGHT-G3X- Prismatic Sealed Lamp T8 32W 4100K 75 CRI (MIN); | 2 | 175. 0 0 | 350.00 |
| qty 3 | ann a chean a ile ach | en la companya da ser la company | |
| 427-LGHT-J31- Recessed Indirect Lamp: T8 32W 4100K 75 CRI (MIN) | 42 | 77.0 0 | 3,234.00 |
| 427-LGHT-J32- Rec. Ind. Master-SAT, Lamp: T8 32W 4100K 75; qty 3 | 6 | 77.00 | 462.00 |
| 427-LGHT-K - Industrial Closed Lamp: T8 32W 4100K 75 CRI (MIN); qty 2 | 20 | 77.00 | 1,540.00 |
| 427-LGHT-K4 - Heavy Industrial Lamp: T8 32W 4100K 75 CRI (MIN); | 18 | 77.00 | 1,386.00 |



| Custom Rebate Items | Quantity | Price/Fixture | Cost to Replace |
|---|--------------------|-----------------|--------------------|
| qty 2 | 2 | 77.00 | 1.54.00 |
| 427-LGHT-K4E- Heavy Industrial 120V Lamp: T8 32W 4100K; qty 2 427-LGHT-K4X- Heavy Industrial Lamp: T8 32W 4100K 75 CRI (MIN); | 5 | 77.00 175.00 | 154.00 875.00 |
| qty 2 | J | 113.00 | 0.0.00 |
| ., 427-LGHT-K8 - Heavy Industrial Lamp: T8 32W 4100K 75 CRI (MIN); qty 2 | 26 | 77.00 | 2,002.00 |
| 427-LGHT-K8X- Heavy Industrial Lamp: T8 32W 4100K 75 CRI (MIN); qty 2 | 13 | 175.00 | 2,275.00 |
| 427-LGHT-KX - Industrial Closed Lamp: T8 32W 4100K 75 CRI (MIN); | 1 | 175.00 | 175.00 |
| qty 2 427-LGHT-L14- Performance Cove Lamp: T8 32W 4100K 75 CRI (MIN); | 12 | 77.00 | 924.00 |
| qty 1 427-LGHT-PS1- Decorative Pendant Lamp: CFL 50W 4100K 82 CRI; qty 8 | 25 | 77.00 | 1,925.00 |
| 427-LGHT-PS2- Corner Mount Lamp: T8 32W 4100K 75 CRI (MIN); qty | 18 | 77.00 | 1,386.00 |
| 427-LGHT-PS3- Decorative Pendant Lamp: CFDT 26W 4100K 82 CRI; qty 4 | 9 | 77.00 | 693.00 |
| 427-LGHT-PS4- Decorative Sconce Lamp: Incandescent 60W; qty 1 | 6 | 77.00 | 462.00 |
| 427-LGHT-PS5- Track Lightning, Lamp: CFL 18W 4100K 82 CRI; qty 2 | 9 | 77.00 | 693.00 |
| 427-LGHT-S1 - Fluorescent Downlight, Lamp: CFTR 32W 4100K 82 CRI; qty 1 | 2 | 77.0 0 | 154.00 |
| 427-LGHT-S4 - Fluorescent Shower Light Lamp; CFTR 32W 4100K 82 CRI; qty 1 | 3 | 77.0 0 | 231.00 |
| 427-LGHT-SL2- Wall Mounted Area Light Lamp: PSMH 150W E17 65 CRI; qty 1 | 1 | 77.00 | 77.00 |
| 427-LGHT-SL3- Exterior Decorative Pendant Lamp: PSMH 100W 65 CRI; qty 1 | 3 | 77.00 | 231.00 |
| 427-LGHT-SL4- Ext Decorative Bracket Mount Lamp: PSMH 70W 65 | 10 | 77.00 | 770.00 |
| CRI; qty 1 427-LGHT-Y1 - Attic light fixture | 40 | 77.00 | 3,080.00 |
| 427-LGT-A31X- Prismatic Lamp info: T8 32W 4100K 75 CRI (Min); qty | 5 | 175.00 | 875.00 |
| 427-LGT-B24D- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); qty 2 | 1 | 77.00 | 77 .00 |
| 427-LGT-B28 - LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); qty | 6 | 77.00 | 462.00 |
| 427-LGT-B34D- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); | 17 | 77.00 | 1,309.00 |
| qty 3 427-LGT-B38D- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); | 116 | 77.00 | 8,932.00 |
| qty 3 427-LGT-B38X- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); | weether 2 . | 175.00 | 350.00 |



Invoice Letter Page 3 of 3 September 10, 2012

| Custom Rebate Items | Quantity | Price/Fixture | Cost to Replace |
|--|----------|---------------|--------------------|
| qty 3 | | | |
| 427-LGT-C31X- Parabolic Lamp: T8 32W 4100K 75 CRI (MIN); qty 3 | 6 | 175.00 | 1,050.00 |
| 427-LGT-J31X- Recessed Indirect Lamp: T8 32W 4100K 75 CRI (MIN) | 41 | 175.00 | 7,175.00 |
| 427-LGT-PS1X- Decorative Pendant Lamp: CFL 50W 4100K 82 CRI; qty 8 | 6 | 175.00 | 1,050.00 |
| 427-LGT-X8-A- Fluorescent Highbay Lamp: CFTR 42W 4100K 82 CRI: qty 8 | 18 | 575.00 | 10,350.00 |
| 427-LGTB24DX- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); qty 2 | 1 | 175.00 | 175.00 |
| 427-LGTB28D - LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); qty 2 | 35 | 77.00 | 2,695.00 |
| 427-LGTB28DX- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); | 12 | 175.00 | 2,100.00 |
| qty 2 427-LGTB34DX- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); qty 3 | 1 | 175.00 | 175.00 |
| 427-LGTB38DX- LF Pendant Lamp info: T8 32W 4100K 75 CRI (Min); qty 3 | 19 | 175.00 | 3,325.00 |
| 427-LGTX8-AX- Fluorescent Highbay Lamp: CFTR 42W 4100K 82 CRI: qty 8 | 5 | 575.00 | 2,875.00 |

| | Rebate Items Total 87,810.00 | |
|--|--------------------------------|--|
| | | |
| | | |

| Prescriptive Rebate Items | Quantity | Price/Fixture | Cost to Replace |
|--|----------|---------------|-----------------|
| 427-CH-1 - Water Cooled Screw Chiller - 175.3 Tons | 1 | 150,000.00 | 150,000.00 |

Prescriptive Rebate Items Total | 150,000.00

Thank you for your attention to this matter,

9-19-12

Don Elle

Report Prepared by GBBN Architects, on behalf of

Don Elbe

Utility Management Coordinator



October 29, 2010

Angie Tolle Cincinnati Public Schools 2315 Iowa Avenue Cincinnati, OH 45206

Dear Angie:

Attached are Pay Applications for the Hartwell School, please process payment for the November 19, 2010 check distribution.

| Contractor BP#6B United | Application # | M | onthly Billing | Total Billing To Date | Contract Amount to Date |
|-------------------------|---------------|----|----------------|--------------------------|-------------------------|
| BP#6B United | #17 | \$ | 32,219,60 | \$ 1,646,161.40 | \$1,681,770.50 |

Please call if you have any questions.

Sincerely,

TURNER/DAG/TYS

Kimberly Metz Asst. Accountant

Attachments

cc:

Vince Terry – Moody/Nolan Darris Storms – Turner/DAG/TYS

File 0025 - 14591MF

T:PROJECTS/Hartwell/00250 Pay Application/2010-10-29 United Pay App. Lttr. Doc

APPLICATION AND CERTIFICATE FOR PAYMENT

TO OWNER: HARTWELL ELEMENTARY SCHOOL PROJECT: PERIOD TO: HARTWELL ELEMENTARY 9.30.2010 PROJECT NOS: 125 W. NORTH BEND ROAD Bid Package 6B CINCINNATI OHIO 45206 CONTRACT DATE: VIA CONSTRUCTION MANAGER: TURNER/DAG FROM CONTRACTOR: UNITED ELECTRIC **when at 75% close out documents must be submitted MOODY NOLAN ARCHITECT: CONTRACT FOR: BID PACKAGE 6B - ELECTRICAL/TECHNOLOGY The Contractor certified that the work covered by this pay request has been CONTRACTOR'S APPLICATION FOR PAYMENT completed in accordance with the Contract Documents and that all progress payments previously paid by the State have been applied by the Contractor to discharge in full all of Contractor's obligations incurred in connection with the work covered by all prior pay requests. Application is made for payment as shown below, in connection with the Contract Continuation sheet is attached. UNITED ELECTRIC CO., INC. 9.24.2010 Contractor 1,568,000.00 1. ORIGINAL CONTRACT SUM.....\$ 2. Net Change by Change Orders.....\$ 113,770.50 3. CONTRACT SUM TO DATE.....\$ 1,681,770.50 4. TOTAL COMPLETED & STORED TO DATE.....\$ 1,646,161.40 Based upon on-site observations, the firm affirms that the work has progressed to the percentage of completeness indicated on the pay request. 5. RETAINAGE a. 8% Labor to 50% total Contract.....\$ 31,462,40 b. 8% of Stored Material.....\$ 0.00 Total Retainage.....\$ 31,462.40 6. TOTAL EARNED LESS RETAINAGE.....\$ 1,614,699.00 7. LESS PREVIOUS CERTIFICATES FOR PAYMENT\$ 1,582,479.40 8. CURRENT PAYMENT DUE......\$ 32,219.60 67,071.50 Construction Manager 9. BALANCE TO FINISH, INCLUDING RETAINAGE......\$ **ADDITIONS DEDUCTIONS** Change Order/Contract Approved: 113770.50 Total Changes approved in Previous months by Owner 0.00 Total approved this month School District Treasurer Date **TOTALS** 113770.50 0.00

APPLICATION No:

17

113770.50

NET CHANGES by Change Order

The Ohio School Facilities Commission

88 East Broad Street Suite 1400 Columbus, Ohio 43215

Contractor's Name:

Address:

Project Name:

UNITED ELECTRIC CO., INC.

1309 ETHAN AVENUE, CINCINNATI OHIO 45225

HARTWELL ELEMENTARY

Contractor Pay Application Summary

Ohio School Facilities Commission

Comments:

| tract | | BID PACKAGE 6B ELEC | TRICAL/TECHNOL | -OGY |
|-------|---|---------------------|----------------|------|
| 1 | Original Contract Amount | \$ | 1,568,000.00 | |
| 2 | Net Changes to Date | \$ | 113,770.50 | |
| 3 | Current Contract Amount | \$ | 1,681,770.50 | |
| 4 | Labor Completed to Date | \$ | 763,245.90 | |
| 5 | Material Completed to Date | \$ | 882,915.50 | |
| 6 | Total Work Completed to Date | \$ | 1,646,161.40 | |
| 7 | Store Material to Date | \$ | 0.00 | 0.00 |
| 8 | Less Retained to Date | \$ | 31,462.40 | |
| 9 | Total Amount Due | \$ | 1,614,699.00 | |
| 10 | Less Previous Payments | \$ | 1,582,479.40 | |
| 11 | Less Amount Retained to Cover Lien | \$ | 0.00 | |
| 12 | Less Amount Retained for Liquidated Damages | \$ | 0.00 | |
| 13 | Less Other Amounts Withheld | \$ | 0.00 | |
| 14 | Current Due | \$ | 32,219.60 | |
| | Balance to Complete | \$ | 67,071.50 | |

Form OSFC-163A

payappcover.xls

Phone 614-466-6290 Fax 614-466-7749

Date

ARCHITECT: Moody Nolan

CONSTRUCTION MANAGER: TURNER/DAG CONTRACTOR: UNITED ELECTRIC INC.

SUBMITTAL DATE: PAY APPLIACTION NO:

9.24.10 17.00

| | | | 7 | WORK (| COMPLETED | MATERIALS | TOTAL COMPLETED | | | |
|--|--|----------|---|------------|-----------|-----------|-----------------------|----------|-------------|-----------|
| ITEM | | 1 1 | SCHEDULED | PREVIOUS | THIS | PRESENTLY | & STORED | . 1 | BALANCE | |
| NUMBER | DESCRIPTION OF WORK | 1 | VALUE | APPS. | PERIOD | STORED | TO DATE | % | TO FINISH | RETAINAGE |
| | ELEMENTARY SCHOOL | 1 | *************************************** | 7 11 7 21 | , 2 | 0.01125 | | | 10 (11.011 | |
| - CONTRACTOR OF THE PARTY OF TH | BOND / PERMITS / INSURANCE | MATERIAL | 30,000.00 | 30,000,00 | 0.00 | 0.00 | 30,000.00 | 100.00% | 0.00 | 0,00 |
| | SUPERINTENDENT | LABOR | 15,000.00 | 14,250.00 | 750.00 | 0.00 | 15,000.00 | 100.00% | 0.00 | 0.00 |
| | MOBILIZATION | LABOR | 5,000.00 | 5,000.00 | 0.00 | 0.00 | 5,000.00 | 100.00% | 0.00 | 0,00 |
| | DE-MOBILIZATION | LABOR | 3,500.00 | 0.00 | 1,750.00 | 0.00 | 1,750.00 | 50.00% | 1,750.00 | 140.00 |
| | FINAL CLEANING | LABOR | 1,000,00 | 0,00 | 700.00 | 0.00 | 700.00 | 70.00% | 300.00 | 56.00 |
| | DAILY CLEANING | LABOR | 10,000.00 | 8,500.00 | 1,000.00 | 0.00 | 9,500.00 | 95.00% | 500.00 | 0.00 |
| | SAFETY | LABOR | 5,500.00 | 4,950.00 | 550.00 | 0.00 | 5,500.00 | 100.00% | 0.00 | 0.00 |
| | MEP CORDINATION | LABOR | 10,000.00 | 10,000.00 | 0.00 | 0.00 | 10,000.00 | 100.00% | 0.00 | 0.00 |
| | PROJECT CLOSEOUT | MATERIAL | 25,000.00 | 10,000.00 | 2,500.00 | 0.00 | 12,500.00 | 50.00% | 12,500.00 | 1,000.00 |
| | TEMPORARY | LABOR | 25,000.00 | 25,000.00 | 0.00 | 0.00 | 25,000.00 | 100.00% | 0.00 | 0.00 |
| | TRAINING / COMMISIONING | LABOR | 2,500.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00% | 2,500,00 | 0.00 |
| | SUBMITTALS | LABOR | 7,500.00 | 7,500.00 | 0.00 | 0,00 | 7,500.00 | 100.00% | 0.00 | 0.00 |
| | PUNCH LIST | LABOR | 10.000.00 | 0.00 | 2,500.00 | 0.00 | 2,500.00 | 25.00% | 7,500.00 | 0.00 |
| | PROGRESS MEETINGS | LABOR | 15,000.00 | 14,250.00 | 750.00 | 0.00 | 15,000.00 | 100.00% | 0.00 | 0.00 |
| 15 | PROGRESS WEETINGS | LABOR | 13,000.00 | 14,230.00 | 730.00 | 0.00 | 13,000.00 | 100.0076 | 0.00 | 0.00 |
| | LIGHTING CONDUIT BASEMENT FL. | LABOR | 9,900,00 | 9,900.00 | 0.00 | 0.00 | 9,900.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING CONDUIT BASEMENT FL. | MATERIAL | 6.500.00 | 6,500.00 | 0.00 | 0.00 | 6,500,00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING CONDOTT BASEMENT FL. | LABOR | 2,310.00 | 2,310.00 | 0.00 | 0.00 | 2,310.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING WIRE BASEMENT FL. | MATERIAL | 1,500.00 | 1,500.00 | 0.00 | 0.00 | 1,500,00 | 100.00% | 0.00 | 0.00 |
| | | | · · · · · · · · · · · · · · · · · · · | | 0.00 | 0.00 | 3,815.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING FIXTRES BASEMENT FL. | LABOR | 3,815.00 | 3,815.00 | 0.00 | 0.00 | 10,000.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING FIXTRES BASEMENT FL. | MATERIAL | 10,000.00 | 10,000.00 | | | 420,00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING DEVICES DEVICES BASEMENT FL. | LABOR | 420.00 | 420.00 | 0.00 | 0.00 | 650.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING DEVICES DEVICES BASEMENT FL. | MATERIAL | 650.00 | 650.00 | 0.00 | 0.00 | 17,500.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING CONDUIT 1ST FL. | LABOR | 17,500.00 | 17,500.00 | 0.00 | 0.00 | 15,500.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING CONDUIT 1ST FL. | MATERIAL | 15,500.00 | 15,500.00 | 0.00 | 0.00 | | 100.00% | 0.00 | 0.00 |
| | LIGHTING WIRE 1ST FL. | LABOR | 4,500.00 | 4,500.00 | | 0.00 | 4,500.00 | | 0.00 | 0.00 |
| | LIGHTING WIRE 1ST FL. | MATERIAL | 5,500.00 | 5,500.00 | 0.00 | 0.00 | 5,500.00 16,000.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING FIXTRES 1ST FL. | LABOR | 16,000.00 | 12,800.00 | 3,200.00 | | | | | |
| | LIGHTING FIXTRES 1ST FL. | MATERIAL | 38,500.00 | 38,500.00 | 0.00 | 0.00 | 38,500.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING DEVICES 1ST FL. | LABOR | 5,000.00 | 5,000.00 | 0.00 | 0.00 | 5,000.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING DEVICES 1ST FL. | MATERIAL | 9,000.00 | 9,000.00 | 0.00 | 0.00 | 9,000.00 | 100.00% | 0.00 | 0.00 |
| | LIGHTING CONDUIT 2ND FLOOR | LABOR | 14,000.00 | 14,000.00 | 0.00 | 0.00 | 14,000.00 | 100.00% | 0.00 | |
| | LIGHTING CONDUIT 2ND FLOOR | MATERIAL | 11,500.00 | 11,500.00 | 0.00 | 0.00 | 11,500,00 | 100.00% | 0.00 | 0.00 |
| 34 | LIGHTING WIRE 2ND FL. | LABOR | 3,290.00 | 3,290.00 | 0.00 | 0.00 | 3,290.00 | 100.00% | 0.00 | 263.20 |
| 35 | LIGHTING WIRE 2ND FL. | MATERIAL | 4,500.00 | 4,500.00 | 0.00 | 0.00 | 4,500.00 | 100.00% | 0.00 | 0.00 |
| 36 | LIGHTING FIXTRES 2ND FL. | LABOR | 12,000.00 | 12,000.00 | 0.00 | 0.00 | 12,000.00 | 100.00% | 0.00 | 960.00 |
| 37 | LIGHTING FIXTURES 2ND FL. | MATERIAL | 36,000.00 | 36,000.00 | 0.00 | 0.00 | 36,000.00 | 100.00% | 0.00 | 0.00 |
| 38 | LIGHTING DEVICES 2ND FL. | LABOR | 5,500.00 | 5,500.00 | 0.00 | 0,00 | 5,500.00 | 100.00% | 0.00 | 440.00 |
| 39 | LIGHTING DEVICES 2ND FL. | MATERIAL | 12,000.00 | 12,000.00 | 0.00 | 0.00 | 12,000.00 | 100.00% | 0.00 | 0.00 |
| 40 | · | | | | | | | 100 000 | | |
| | DEMOLITION BASEMENT | LABOR | 18,500.00 | 18,500.00 | 0.00 | 0.00 | 18,500.00 | 100.00% | 0.00 | 0.00 |
| | DEMOLITION 1ST FLOOR | LABOR | 15,000.00 | 15,000.00 | 0.00 | 0.00 | 15,000.00 | 100.00% | 0.00 | 0.00 |
| 43 | DEMOLITION 2ND FLOOR | LABOR | 15,000.00 | 15,000.00 | 0.00 | 0.00 | 15,000.00 | 100.00% | 0.00 | 0.00 |
| 44 | | | | | | w | | | 0.00 | |
| 45 | | | | | | | | | | |
| | | | | | | | | | | 0.00 |
| | and the state of t | LABOR | 252,735.00 | 228,985.00 | 11,200.00 | 0.00 | 240,185.00 | 95.03% | 12,550.00 | 10,109.40 |
| ł | | MATERIAL | 206,150.00 | 191,150.00 | 2,500.00 | 0.00 | 193,650.00 | 93.94% | 12,500.00 | 0.00 |
| | HARTWELL ELEMENTARY | | 458,885.00 | 420,135.00 | 13,700.00 | 0.00 | 433,835.00 | 94.54% | 25,050.00 | 10,109.40 |
| | | <u> </u> | | <u></u> | ., | | | | | |

GRAND TO

GRAND TO

GRAND TO

CONSTRUCTION MANAGER: TURNER/DAG CONTRACTOR: UNITED ELECTRIC INC.

SUBMITTAL DATE: PAY APPLICATOIN NUMBER:

9,24,10 17,00

| | | | | | COMPLETED | | TOTAL COMPLETED | | | |
|----------|---|-------------------|------------------------|------------------------|-----------|-----------|---|---------|-----------|-----------|
| ITEM | | | SCHEDULED | PREVIOUS | THIS | PRESENTLY | & STORED | | BALANCE | |
| UMBER | DESCRIPTION OF WORK | | VALUE | APPS. | PERIOD | STORED | TO DATE | % | TO FINISH | RETAINAGE |
| | BRANCH POWER | | | | | | | | | |
| | DRANGH FOWER | | | | | | *************************************** | | | ······ |
| 1 | POWER CONDUIT GYM ADDITION | LABOR | 5,000.00 | 5,000.00 | 0.00 | 0.00 | 5,000.00 | 100.00% | 0.00 | 0.0 |
| 2 | POWER CONDUIT GYM ADDITION | MATERIAL | 4,900.00 | 4,900.00 | 0.00 | 0.00 | 4,900.00 | 100.00% | 0.00 | 0.0 |
| 3 | POWER WIRE GYM ADDITION | LABOR | 4,500.00 | 4,500.00 | 0.00 | 0.00 | 4,500.00 | 100.00% | 0.00 | 360.0 |
| 4 | POWER WIRE GYM ADDITION | MATERIAL | 3,000.00 | 3,000.00 | 0.00 | 0.00 | 3,000.00 | 100.00% | 0.00 | 0.0 |
| 5 | POWER DEVICES GYM ADDITION | LABOR | 1,120.00 | 896.00 | 224.00 | 0.00 | 1,120.00 | 100.00% | 0.00 | 89.6 |
| 6 | POWER DEVICES GYM ADDITION | MATERIAL | 932.00 | 932.00 | 0.00 | 0.00 | 932.00 | 100.00% | 0.00 | 0.0 |
| 7 | FIRE ALARM | | | | | | | | | |
| 8 | | | | | | | | | | |
| 9 | FIRE ALARM CONDUIT | LABOR | 14,500.00 | 14,500.00 | 0.00 | 0.00 | 14,500.00 | 100.00% | 0.00 | 0.0 |
| 10 | FIRE ALARM CONDUIT | MATERIAL | 11,500.00 | 11,500.00 | 0.00 | 0.00 | 11,500.00 | 100.00% | 0.00 | 0.0 |
| 11 | FIRE ALARM WIRE | LABOR | 4,795.00 | 4,795.00 | 0.00 | 0.00 | 4,795.00 | 100.00% | 0.00 | 0.0 |
| 12 | FIRE ALARM WIRE | MATERIAL | 2,000.00 | 2,000.00 | 0.00 | 0.00 | 2,000.00 | 100.00% | 0.00 | 0.0 |
| 13 | FIRE ALARM DEVICES | LABOR | 8,085.00 | 8,085.00 | 0.00 | 0.00 | 8,085.00 | 100.00% | 0.00 | 0.0 |
| 14 | FIRE ALARM DEVICES | MATERIAL | 3,500.00 | 3,500.00 | 0.00 | 0.00 | 3,500.00 | 100.00% | 0.00 | 0.0 |
| 15 | | | | | | | | | | |
| 16 | | | | | | | | | | |
| 17 | | | | | | | | | | |
| 18 | | | | | | | | | | |
| | | | | | | | | | | |
| | DISTRIBUTION POWER | | | | | | | | | |
| 19 | DISTRIBUTION CONDUIT LABOR | LABOR | 24,000.00 | 24,000.00 | 0.00 | 0.00 | 24,000.00 | | 0.00 | 0.0 |
| 20 | DISTRIBUTION CONDUIT MATERIAL | MATERIAL | 22,500.00 | 22,500.00 | 0.00 | 0.00 | 22,500.00 | 100.00% | 0.00 | 0.0 |
| 21 | DISTRIBUTION WIRE LABOR | LABOR | 15,500.00 | 15,500.00 | 0.00 | 0.00 | 15,500.00 | 100.00% | 0.00 | 0.0 |
| 22 | DISTRIBUTION WIRE MATERIAL | MATERIAL | 14,500.00 | 14,500.00 | 0.00 | 0.00 | 14,500.00 | 100.00% | 0.00 | 0.0 |
| 23 | DISTRIBUTION EQUIPMENT LABOR | LABOR | 22,000.00 | 22,000.00 | 0.00 | 0.00 | 22,000.00 | 100.00% | 0.00 | 0.0 |
| 24 | DISTRIBUTION EQUIPMENT MATERIAL | MATERIAL | 18,000.00 | 18,000.00 | 0.00 | 0.00 | 18,000.00 | 100.00% | 0.00 | 0.0 |
| 25 | GENERATOR LABOR | LABOR | 7,500.00 | 7,500.00 | 0.00 | 0.00 | 7,500.00 | 100.00% | 0.00 | 0.0 |
| 26 | GENERATOR MATERIAL | MATERIAL | 10,500.00 | 10,500.00 | 0.00 | 0.00 | 10,500.00 | 100.00% | 0.00 | 0.0 |
| 27 | | | | | | | | | | |
| 28 | SITE | | 00 500 00 | 00.500.00 | 0.00 | 0.00 | 22,500.00 | 100.00% | 0,00 | 0.0 |
| 29 | SITE SERVICE CONDUIT LABOR | LABOR | 22,500.00 | 22,500.00 22,000.00 | 0.00 | 0.00 | 22,000.00 | 100.00% | 0.00 | 0.0 |
| 30 | SITE SERVICE CONDUIT MATERIAL | MATERIAL | 22,000.00 | 12,500.00 | 0.00 | 0.00 | 12,500.00 | 100.00% | 0.00 | 0.0 |
| 31 | SITE SERVICE WIRE LABOR | LABOR MATERIAL | 12,500.00 22,000.00 | 22,000.00 | 0.00 | 0.00 | 22,000.00 | 100.00% | 0.00 | 0.0 |
| 32 33 | SITE SERVICE WIRE MATERIAL SITE FIXTURE CONDUIT LABOR | LABOR | 8,600.00 | 8,600.00 | 0.00 | 0.00 | 8,600,00 | 100.00% | 0.00 | 0.0 |
| 34 | SITE FIXTURE CONDUIT MATERIAL | MATERIAL | 6,500.00 | 6,500.00 | 0.00 | 0.00 | 6,500.00 | 100.00% | 0.00 | 0.0 |
| 35 | SITE FIXTURE WIRE LABOR | LABOR | 2,950.00 | 2,950.00 | 0.00 | 0.00 | 2,950.00 | 100.00% | 0.00 | 236.0 |
| 36 | SITE FIXTURE WIRE MATERIAL | MATERIAL | 3,500.00 | 3,500.00 | 0.00 | 0.00 | 3,500.00 | 100.00% | 0.00 | 0.0 |
| 35 | SITE FIXTURES LABOR | LABOR | 3,100.00 | 3,300.00 | 0.00 | 0.00 | 3,300.00 | 100.00% | 0.00 | 0.0 |
| 38 | SITE FIXTURES MATERIAL | MATERIAL | 9,000.00 | 9,000.00 | 0.00 | 0.00 | 9,000.00 | 100.00% | 0.00 | 0.0 |
| 39 | EXCAVATION LABOR | LABOR | 7,500.00 | 7,500.00 | 0.00 | 0.00 | 7,500.00 | 100.00% | 0.00 | 0.0 |
| 40 | EXCAVATION MATERIAL | MATERIAL | 11,500.00 | 11,500.00 | 0.00 | 0.00 | 11,500.00 | 100.00% | 0.00 | 0.0 |
| 70 | CASAVATION WATERIAGE | 160 (121(0)) | | ,000.00 | | | | | | |
| | | | | | | | | | | |
| | | LABOR | 164,150.00 | 163,926.00 | 224.00 | 0.00 | | 16.00 | 0.00 | 6,566. |
| | | MATERIAL | 165,832.00 | 165,832.00 | 0.00 | 0.00 | 165,832.00 | 15.00 | 6,500.00 | 0,0 |
| | HARTWELL ELEM | | 329,982.00 | 329,758.00 | 224,00 | 0.00 | 329,982.00 | 100.00% | 6,500.00 | 6,566.0 |

PROJECT NAME: HARTWELL ELEM

ARCHITECT: Moody Noian
CONSTRUCTION MANAGER: TURNER/DAG
CONTRACTOR: UNITED ELECTRIC INC.

0.00

SUBMITTAL DATE: PAY APPLICATION NUMBER:

9.24.10 17.00

| | | | | WORK | COMPLETED | MATERIALS | TOTAL COMPLETED | | T. | |
|----------|---|-------------------|------------------------|---|----------------|-----------|-----------------|--------------|--------------|-------------|
| ITEM | | | SCHEDULED | PREVIOUS | THIS | PRESENTLY | & STORED | | BALANCE | ı |
| NUMBER | DESCRIPTION OF WORK | | VALUE | APPS. | PERIOD | STORED | TO DATE | % | TO FINISH | RETAINAGE |
| ARTWELL | ELEMENTARY | | | | | **** | | | | |
| | LIGHTING CONT. | | | | | | | | | |
| | | | | | | | | | | |
| 1 | LIGHTING CONDUIT GYM ADDITION | LABOR | 6,500.00 | 6,500.00 | 0.00 | 0.00 | 6,500.00 | 100,00% | 0.00 | 0.00 |
| 2 | LIGHTING CONDUIT GYM ADDITION | MATERIAL | 4,500.00 | 4,500.00 | 0.00 | 0.00 | 4,500.00 | 100.00% | 0.00 | 0.0 |
| 3 | LIGHTING WIRE GYM ADDITON | LABOR | 800,00 | 800.00 | 0.00 | 0.00 | 800.00 | 100.00% | 0.00 | 64.0 |
| 4 | LIGHTING WIRE GYM ADDITON | MATERIAL | 400.00 | 400.00 | 0.00 | 0.00 | 400.00 | 100.00% | 0.00 | 0.0 |
| 5 | LIGHTING FIXTRES GYM ADDITION | LABOR | 6,000.00 | 6,000.00 | 0.00 | 0.00 | 6,000.00 | 100.00% | 0.00 | 480.0 |
| | LIGHTING FIXTRES GYM ADDITION | MATERIAL | 3,500.00 | 3,500.00 | 0.00 | 0.00 | 3,500.00 | 100.00% | 0.00 | 0.0 |
| | LIGHTING DEVICES GYM ADDITION | LABOR | 2,000.00 | 1,500.00 | 500.00 | 0.00 | 1,500.00 | 75.00% | 500.00 | 0.0 |
| 8 | LIGHTING DEVICES GYM ADDITION | MATERIAL | 2,300.00 | 2,300.00 | 0.00 | 0.00 | 2,300.00 | 100.00% | 0.00 | 0,0 |
| | | | | | | | - | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | <u> </u> |
| | | | | | | | | <u> </u> | | |
| | | | | | | | <u></u> | | | |
| | | | | | | | | ļ | | r |
| | | | | | | | | ļi | | |
| | DOANGU DOWED | | | | | ***** | <u> </u> | | | |
| | BRANCH POWER | LABOR | 40.000.00 | 40.000.00 | 0.00 | 0.00 | 12,000.00 | 100.00% | 0.00 | 0.0 |
| | POWER CONDUIT BASEMENT | LABOR MATERIAL | 12,000.00 8,500.00 | 12,000.00 8,500.00 | 0.00 | 0.00 | | 100.00% | 0.00 | 0.0 |
| 18 | POWER CONDUIT BASEMENT | LABOR | | 3,500.00 | 0.00 | 0.00 | , | 100.00% | 0.00 | 0.0 |
| | POWER WIRE BASEMENT | | 3,500.00 | | 0.00 | 0.00 | <u> </u> | 100.00% | 0.00 | 0.0 |
| | POWER WIRE BASEMENT | MATERIAL | 1,100.00 | 1,100.00 | 0.00 | 0.00 | | 100.00% | 0.00 | 0.0 |
| 21 | POWER DEVICES BASEMENT | LABOR | 420.00 | 420.00 | | 0.00 | | 100.00% | 0.00 | 0.0 |
| 22 | POWER DEVICES BASEMENT | MATERIAL | 350.00 | 350.00 | 0.00 | 0.00 | 28,000.00 | 100.00% | 0.00 | 0.0 |
| 23 | POWER CONDUIT 1ST FL. | LABOR MATERIAL | 28,000.00 20,000.00 | 28,000.00 20,000.00 | 0.00 | 0.00 | | 100.00% | 0.00 | 0.0 |
| 24 | POWER CONDUIT 1ST FL. | | | 12,000.00 | 0.00 | 0.00 | | 100.00% | 0.00 | 0.0 |
| 25 | POWER WIRE 1ST FL. | LABOR | 12,000.00 | | 0.00 | 0.00 | | 100.00% | 0.00 | 0.0 |
| 26 | POWER WIRE 1ST FL. | MATERIAL | 8,500.00 | 8,500.00 | | 0.00 | 2,870,00 | 100.00% | 0.00 | 0.0 |
| 27 | POWER DEVICES 1ST FL. | LABOR | 2,870.00 | 2,296.00 1,918,00 | 574.00 0.00 | 0.00 | 1 ' | 100.00% | 0.00 | 0.0 |
| 28 | POWER DEVICES 1ST FL. | MATERIAL LABOR | 1,918.00 26,500.00 | 26,500,00 | 0.00 | 0.00 | 1 | 100.00% | 0.00 | 0.0 |
| 29 | POWER CONDUIT 2ND FL | MATERIAL | 20,000.00 | 20,000.00 | 0.00 | 0.00 | 20,000.00 | 100.00% | 0.00 | 0.0 |
| 30 | POWER CONDUIT 2ND FL. POWER WIRE AREA 2ND FL. | LABOR | 10,000.00 | 10,000.00 | 0.00 | 0.00 | | 100.00% | 0.00 | 0.0 |
| 31 32 | POWER WIRE AREA 2ND FL. | MATERIAL | 8,500.00 | 8,500.00 | 0.00 | 0.00 | 8,500.00 | 100.00% | 0.00 | 0.0 |
| 33 | POWER DEVICES 2ND FL. | LABOR | 1,575.00 | 1,575.00 | 0.00 | 0.00 | 1,575.00 | 100.00% | 0.00 | 0.0 |
| 34 | POWER DEVICES 2ND FL. | MATERIAL | 1,400.00 | 1,400.00 | 0.00 | 0.00 | | 100.00% | 0.00 | 0.0 |
| 34 | POWER DEVICES ZND FL. | IVIATERIAL | 1,400.00 | 1,400.00 | 0.00 | 0.00 | 1,400,00 | 100,0076 | 3.00 | 0.0 |
| | | | | | | | | | | |
| | | | | | | | | <u> </u> | , | |
| | | - | | | | | | | | |
| | | | | *************************************** | | | | - | | |
| | | | <u></u> | | | | | 1 | | |
| | | | | | | | · | - | i | <u></u> |
| | | | | | | | | - | | |
| | | | | | | ····· | | | | |
| | | LABOR | 112,165.00 | 111,091.00 | 1.074.00 | 0.00 | 111,665.00 | 99.55% | 500.00 | 4,486.6 |
| | | MATERIAL | 80,968.00 | 80,968,00 | 0.00 | 0.00 | | | 0.00 | 0.0 |
| | HARTWELL | | 193,133.00 | 192,059.00 | 1,074.00 | 0.00 | | | 500.00 | 4,486.6 |
| | 1 | | | | · | \ | • | · | , | |

ARCHITECT: Moody Nolan
CONSTRUCTION MANAGER: TURNER/DAG
CONTRACTOR: UNITED ELECTRIC INC.

SUBMITTAL DATE: PAY APPLICATION NUMBER:

9.24.2010 17.00

| | | | | WORK (| COMPLETED | MATERIALS | TOTAL COMPLETED | | | |
|----------|---|-------------------|-----------------------|-----------------------|----------------|-----------|------------------------|------------------|--------------------|-----------|
| ITEM | | - | SCHEDULED | PREVIOUS | THIS | PRESENTLY | & STORED |] | BALANCE | |
| NUMBER | DESCRIPTION OF WORK | | VALUE | APPS. | PERIOD | STORED | TO DATE | % | TO FINISH | RETAINAGE |
| HARTWELL | ELEM SCHOOL | | | | | | | | | |
| | | - | | | | | | | | |
| | | | | | | | | | | |
| 1 2 | | | | | | | | | | |
| 3 | TELE/ DATA CONDUIT LABOR | LABOR | 13,500.00 | 13,500,00 | 0.00 | 0.00 | 13,500.00 | 100.00% | 0.00 | 0.00 |
| | | MATERIAL | 9,500.00 | 9,500.00 | 0.00 | 0.00 | 9,500.00 | 100.00% | 0,00 | 0.00 |
| | | LABOR | 40,000.00 | 40,000.00 | 0.00 | 0.00 | 40,000.00 | 100.00% | 0.00 | 0.00 |
| | | MATERIAL | 60,675.00 | 60,675.00 | 0.00 | 0.00 | 60,675.00 | 100.00% | 0.00 | 0.00 |
| 7 | | LABOR | 3,000.00 | 3,000.00 | 0.00 | 0.00 | 3,000.00 | 100.00% | 0.00 | 0.00 |
| 8 | | MATERIAL | 5,000.00 | 5,000.00 | 0.00 | 0.00 | 5,000.00 | 100.00% | 0.00 | 0.00 |
| | | LABOR | 14,000.00 | 14,000.00 | 0.00 | 0.00 | 14,000.00 | 100.00% | 0.00 | 0.00 |
| | | MATERIAL | 11,000.00 | 11,000.00 | 0.00 | 0.00 | 11,000.00 | 100.00% | 0.00 | 0.00 |
| | | LABOR | 14,740.00 | 12,529.00 | 737.00 | 0.00 | 13,266.00 | 90.00% | 1,474.00 | 0.00 |
| | 101101111111111111111111111111111111111 | MATERIAL | 19,945.00 | 16,953,25 | 997.25 | 0.00 | 17,950.50 5,066.00 | 90.00% 85.00% | 1,994.50 894.00 | 0.00 |
| | | LABOR | 5,960.00 61,000.00 | 2,384.00 61,000.00 | 2,682.00 | 0.00 | 61,000.00 | 100.00% | 0.00 | 0.00 |
| | | MATERIAL LABOR | 10,500.00 | 10,500.00 | 0.00 | 0.00 | 10,500.00 | 100.00% | 0.00 | 0.00 |
| 16 | | MATERIAL | 8,500.00 | 8,500.00 | 0.00 | 0.00 | 8,500.00 | 100.00% | 0.00 | 0.00 |
| 17 | | LABOR | 28,094.00 | 22,475.20 | 4,214.10 | 0.00 | 26,689.30 | 95.00% | 1,404.70 | 0.00 |
| 18 | | MATERIAL | 56,000.00 | 56,000.00 | 0.00 | 0.00 | 56,000.00 | 100.00% | 0.00 | 0.00 |
| 19 | | LABOR | 7,500.00 | 7,500.00 | 0.00 | 0.00 | 7,500.00 | 100.00% | 0.00 | 0.00 |
| 20 | ACCESS CONTROL CONDUIT MATERIAL | MATERIAL | 5,500.00 | 5,500.00 | 0.00 | 0.00 | 5,500.00 | 100.00% | 0.00 | 0.00 |
| 21 | | LA80R | 18,482.00 | 14,785.60 | 1,848.20 | 0.00 | 16,633.80 | 90.00% | 1,848.20 | 0.00 |
| 22 | | MATERIAL | 11,602.00 | 11,602.00 | 0.00 | 0.00 | 11,602.00 | 100.00% | 0.00 | 0.00 |
| 23 | | LABOR | 5,500.00 | 5,500.00 | 0.00 | 0.00 | 5,500.00 | 100.00% | 0.00 | 0.00 |
| 24 | | MATERIAL | 4,000,00 | 4,000.00 | 0.00 | 0.00 | 4,000.00 | 100,00% | 0.00 | 0.00 |
| 25 | | LABOR | 18,817.00 | 14,112.75 | 2,822.55 | 0.00 | 16,935.30 18,225.00 | 90.00% | 1,881.70 0.00 | 0.00 |
| 26 | | MATERIAL | 18,225.00 | 18,225.00 602.50 | 0.00 602.50 | 0.00 | 1,205.00 | 100.00% | 0.00 | 0.00 |
| 27 | NETWORK ELECTRONICS LABOR NETWORK ELECTRONICS MATERIAL | LABOR MATERIAL | 1,205.00 68,700.00 | 68,700.00 | 0.00 | 0.00 | 68,700.00 | | 0.00 | 0.00 |
| 29 | EQUIPMENT ROOM BULD. LABOR | LABOR | 2,000.00 | 1,000.00 | 800.00 | 0.00 | 1,800.00 | 90.00% | 200.00 | 0.00 |
| 30 | EQUIPMENT ROOM BULD, MATERIAL | MATERIAL | 10,000.00 | 10,000.00 | 0.00 | 0.00 | 10,000.00 | | 0.00 | 0.00 |
| 31 | GYM AV CONDUIT LABOR | LABOR | 2,500.00 | 2,500.00 | 0.00 | 00,0 | 2,500.00 | 100.00% | 0.00 | 0,00 |
| 32 | GYM AV CONDUIT MATERIAL | MATERIAL | 2,000.00 | 2,000.00 | 0.00 | 0.00 | 2,000.00 | 100.00% | 0.00 | 0,00 |
| 33 | GYM A/V CABLING EQUIP. LABOR | LABOR | 6,295.00 | 3,147.50 | 2,518.00 | 0.00 | 5,665.50 | 90.00% | 629.50 | 0.00 |
| 34 | GYM AV CABLING EQUIP. MATERIAL | MATERIAL | 25,964.00 | 25,964.00 | 0.00 | 0.00 | 25,964.00 | | 0.00 | 0.00 |
| 35 | BATTERY CLOCK LABOR | LABOR | 2,432.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00% | 2,432.00 | 0.00 |
| 36 | BATTERY CLOCK MATERIAL | MATERIAL | 3,864.00 | 3,864.00 | 0.00 | 0.00 | 3,864.00 | 100.00% | 0.00 | 0.00 |
| 37 | | | | | | | | <u> </u> | | 0.00 |
| 38 | ALL OWANGE | 1.4808 | 5 000 00 | 6,000,00 | 0.00 | 0.00 | 5,000.00 | 100.00% | 0.00 | 0.00 |
| 39 40 | ALLOWANCE ALLOWANCE | LABOR MATERIAL | 5,000.00 5,000.00 | 5,000.00 5,000.00 | 0.00 | 0.00 | 5,000.00 | | 0.00 | 0.00 |
| 42 | change order 001 FWO 113 | LABOR | 2,462.50 | 2,462.50 | 0.00 | 0.00 | 2,462.50 | | 0.00 | 0.00 |
| 43 | change order 001 FWO 113 | MATERIAL | 2,462.50 | 2,462.50 | 0.00 | 0.00 | 2,462.50 | | 0,00 | 0.00 |
| 44 | | LABOR | 8,513.50 | 8,513.50 | 0.00 | 0.00 | 8,513.50 | | 0.00 | 0.00 |
| 45 | change order 002 BP 06 - PCO 066 Items 1 & 2 mat | MATERIAL | 8,513.50 | 8,513.50 | 0.00 | 0.00 | 8,513.50 | | 0.00 | 0.00 |
| 46 | change order 003 COP 12 and 23 | LABOR | 1,878.00 | 1,878.00 | 0.00 | 0.00 | 1,878.00 | 100.00% | 0.00 | 0.00 |
| 47 | change order 003 COP 12 and 23 | MATERIAL | 1,878.00 | 1,878.00 | 0.00 | 0.00 | 1,878.00 | | 0.00 | 0.00 |
| 48 | change order 004 PCO 158 | LABOR | 4,239.50 | 4,239.50 | 0.00 | 0.00 | 4,239.50 | | 0.00 | 0.00 |
| 49 | change order 004 PCO 158 | MATERIAL | 4,239.50 | 4,239.50 | 0.00 | 0.00 | 4,239.50 | | 0.00 | 0.00 |
| 50 | 1 0 | LABOR | 2,379.50 | 2,379.50 | 0.00 | 0.00 | | 100.00% | | 0.00 |
| 51 | change order 005 PCO 227 | MATERIAL | 2,379.50 | 2,379.50 | 0,00 | 0.00 | 2,379.50 | | | 0.00 |
| 52 | change order 006 PCO 203, 205 | LABOR | 3,481.00 | 3,481.00 3,481.00 | 0.00 | 0,00 | 3,481.00 3,481.00 | | | 0.00 |
| 53 | change order 006 PCO 203, 205 change order 007 PCO 220 | MATERIAL LABOR | 3,481.00 1,102.00 | 1,102.00 | 0.00 | 0.00 | 1,102.00 | | | 0.00 |
| 54 55 | | MATERIAL | 1,102.00 | 1,102.00 | 0.00 | 0.00 | 1,102.00 | | | 0.00 |
| 56 | J | LABOR | 1,493.50 | 1,493.50 | 0.00 | 0.00 | 1,493.50 | | | 0.00 |
| 57 | | MATERIAL | 1,493.50 | 1,493.50 | 0.00 | 0.00 | 1,493.50 | | | 0.00 |
| 58 | change order 009 PCO 135, 237 | LABOR | 709.50 | 709.50 | 0.00 | 0.00 | 709.50 | | | 0.00 |
| 59 | change order 009 PCO 135, 237 | MATERIAL | 709.50 | 709.50 | 0.00 | | | | | 0.00 |

PROJECT NAME: HARTWELL ELEM

ARCHITECT: Moody Noian

CONSTRUCTION MANAGER: TURNER/DAG CONTRACTOR: UNITED ELECTRIC INC.

SUBMITTAL DATE: PAY APPLICATION NUMBER:

9.24.2010 17.00

| | | | | WORK C | OMPLETED | MATERIALS | TOTAL COMPLETED | | | |
|----------|-------------------------------|----------|--------------|--------------|-----------|-----------|-----------------|---------|-----------|-----------|
| ITEM | | | SCHEDULED | PREVIOUS | THIS | PRESENTLY | & STORED | | BALANCE | |
| NUMBER | DESCRIPTION OF WORK | | VALUE | APPS. | PERIOD | STORED | TO DATE | % | TO FINISH | RETAINAGE |
| 60 | change order 010 PCO 0445 | LABOR | 6,927.50 | 6,927.50 | 0.00 | 0.00 | 6,927.50 | 100.00% | 0.00 | 0.00 |
| 61 | change order 010 PCO 0445 | MATERIAL | 6,927.50 | 6,927.50 | 0.00 | 0.00 | 6,927.50 | 100.00% | 0.00 | 0.00 |
| 62 | change order 011 PCO 210 | LABOR | 6,035.00 | 6,035.00 | 0.00 | 0.00 | 6,035.00 | 100.00% | 0.00 | 0.00 |
| 63 | change order 011 PCO 210 | MATERIAL | 6,035.00 | 6,035.00 | 0.00 | 0.00 | 6,035.00 | 100.00% | 0.00 | 0.00 |
| 64 | change order 012 PCO 167 | LABOR | 7,683.50 | 7,683.50 | 0.00 | 0.00 | 7,683.50 | 100.00% | 0.00 | 0.00 |
| 65 | change order 012 PCO 167 | MATERIAL | 7,683.50 | 7,683.50 | 0.00 | 0.00 | 7,683.50 | 100.00% | 0.00 | 0.00 |
| 66 | change order 013 PCO 207 | LABOR | 8,880.50 | 8,880.50 | 0.00 | 0.00 | 8,880.50 | 100.00% | 0.00 | 0.00 |
| 67 | change order 013 PCO 207 | MATERIAL | 8,880.50 | 8,880.50 | 0.00 | 0.00 | 8,880.50 | 100.00% | 0.00 | 0.00 |
| 68 | change order 014 PCO 256 | LABOR | 719.00 | 719.00 | 0.00 | 0.00 | 719.00 | 100.00% | 0.00 | 0.00 |
| 69 | change order 014 PCO 256 | MATERIAL | 719.00 | 719.00 | 0.00 | 0.00 | 719.00 | 100.00% | 0.00 | 0.00 |
| 70 | change order 015 PCO 183, 266 | LABOR | 1,480.50 | 1,480.50 | 0.00 | 0.00 | 1,480.50 | 100.00% | 0.00 | 0.00 |
| 71 | change order 015 PCO 183, 266 | MATERIAL | 1,480.50 | 1,480.50 | 0.00 | 0.00 | 1,480.50 | 100.00% | 0.00 | 0.00 |
| | | | | | | | | | | |
| | | LABOR | 257,510.00 | 230,521.55 | 16,224.35 | 0.00 | 246,745.90 | 95.82% | 10,764.10 | 10,300.40 |
| | | MATERIAL | 444,460.00 | 441,468.25 | 997.25 | 0.00 | 442,465.50 | 99.55% | | 0,00 |
| | HARTWELL ELEM | | 701,970.00 | 671,989.80 | 17,221.60 | 0.00 | 689,211,40 | 98,18% | 12,758.60 | 10,300,40 |
| GRAND TO | OTAL JOB | | | | | | | | | |
| | 1 | LABOR | 786,560.00 | 734,523.55 | 28,722.35 | 0.00 | 763,245.90 | 97.04% | 23,314.10 | 31,462.40 |
| | TOTAL MATERIAL | MATERIAL | 895,210.50 | 879,418.25 | 3,497.25 | 0.00 | 882,915.50 | 98.63% | 12,295.00 | 0.00 |
| GRAND TO | TAL HARTWELL ELEM PAGE FOUR | | 1,681,770.50 | 1,613,941.80 | 32,219.60 | 0.00 | 1,646,161.40 | 97.88% | 35,609.10 | 31,462.40 |

| | labor | material | stored material |
|------------|-----------|-----------|-----------------|
| page one | 240185.00 | 193650.00 | 0.00 |
| page two | 111655.00 | 80968.00 | 0.00 |
| page tivee | 154150.00 | 165832.00 | 0.00 |
| page four | 246745.90 | 442465.50 | 0.00 |
| | 762745.90 | 882915.50 | 0.00 |

0.00

31462.40 retainage on labor 0.00 retainage on stored material

31462.40 total retainage

1614699.00

1646161.40

1582479.40 less previous application

| page one | LABOR | | PREVIOUS APPS. 228985.00 | 32219.60 THIS PERIOD 11200.00 | PRESENTLY | & STORED TO DATE 240185.00 | BALA 0.00 TO F 0.95 | NCE INISH RET | TAINAGE 0.00 |
|------------|--|------------------------|--------------------------------|--|--------------|----------------------------------|---------------------------|-----------------------|------------------|
| page one | MATERIAL | 206150,00 | 191150.00 | 2500,00 | 0.00 | 193650,00 | 0,94 | 12500.00 | 0.00 |
| page two | LABOR | 112185.00 | 111091.00 | 1074.00 | 0.00 | 112165,00 | 1,00 | 0.00 | 0.00 |
| page two | MATERIAL | 80968.00 | 00.89608 | 0.00 | 0.00 | 00,8908 | 1.00 | 0.00 | 0.00 |
| page tivee | LABOR | 154150.00 | 163926,00 | 224.00 | 0.00 | 164150,00 | 1,00 | 0.00 | 0.00 |
| page three | MATERIAL | 165832.00 | 165832.00 | 0.00 | 0.00 | 165832.00 | 1,00 | 0.00 | 0.00 |
| page four | LABOR | 257510.00 | 230521.55 | 16224.35 | 0.00 | 246745.90 | 0.96 | 10764.10 0.00 | 0.00 00.0 |
| page four | MATERIAL | 442260.50 | 441468.25 | 997. 2 5 | 0.00 | 442465.50 | 1.00 | ~205.00 | 0.00 |
| | | 1581770.50 | 1613941.80 | 32219.50 | 0.00 | 1646161.40 | 89.0 | 23059.10 | 0.00 |
| | 45885.00 193133.00 LABOR 329982.00 MATERIAL 699770.50 | 786560.00 896210.50 | 734523.55 879418.25 | 28722.35 3497.25 | 0.00 0.00 | 763245.90 440450.00 | 0.97 0.49 | 23314,10 454760.50 | 31462.40 0.00 |
| | | 1681770.50 | 1613941.80 | 32219.60 | 0.00 | 1203695.90 | 0.72 | 478074.60 | 31452.40 |



Ohio School Facilities Commission 88 East Broad Street, Suite 1400 Columbus, OH 43215

| <u>~_~</u> | | | | | | | | |
|----------------------|-----|---|----|----|----------------------|---------------|------|---------------|
| roject / Contract #: | mm- | - | ╗╗ | ΠГ | $\neg \sqcap \sqcap$ | $I \square I$ | 7-M | Contract Name |

Certification of Material Stored At Site

| 1 | | 1 | Γ | T . | | New | Mat. Installed | |
|-----------|-----------|--------------|-------------------|---------------------------|-------------|------------------|--------------------|-----------------|
| Line Item | | Pay | | | Previous | Materials Stored | This Period | Total Materials |
| | Invoice # | Request # | Material Supplier | Description | Amount | (Add) | (Deduct) | Stored at Site |
| Reference | HIVOICE # | 5 | Material Supplier | WIRE | \$6,775.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | CONDUIT | \$4,600.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | DEVICES | \$650.00 | \$0.00 | \$0.00 | \$0.00 |
| | | 1 | | DIST. CONDUIT EQUIP | \$16,875.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | FIXTURES | \$8,000.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | RICHARDS | LTG CONDUIT | \$1,725.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | RICHARDS | DIST EQUIP MAT'L | \$6,300.00 | \$0,00 | \$0.00 | \$0.00 |
| | | 8 | RICHARDS | DIST EQUIP MAT'L | \$11,600.00 | \$0.00 | \$0.00 | \$0.00 |
| | | 8 | RIGHTREO | SITE SERVICE WIRE MAT | \$22,000.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | Itg devices 1st floor | \$9,000.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | RICHARDS | Itg conduit 2nd floor | \$5,750.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | FDL | Ita fixtures 2nd floor | \$9,000.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | RICHARDS | Itg wire 2nd Ifoor | \$2,250.00 | \$0.00 | \$0.00 | \$0.00 |
| | | - | 1,00,0,00 | Itg devices 2nd floor | \$12,000.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | Itg conduit gym addition | \$3,825.00 | \$0.00 | \$0.00 | \$0.00 |
| | | <u> </u> | | power conduit gym add. | \$3,185.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | fire alarm devices | \$3,500.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | DIST EQUIP MAT'L | \$3,600.00 | \$0.00 | \$0.00 | \$0.00 |
| | | † | | Itg wire 2nd Ifoor | | \$0.00 | \$90.00 | \$0.00 |
| pg 1 -29 | | 11 | | Ltg Fixts 1st floor | \$38,500.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 1-36 | | 11 | | Itg wire 2nd Ifoor | \$2,160.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 2-4 | | 11 | | Ltg Wire Gym addition | \$400.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 2-20 | | 11 | | Power Wire- basement | \$1,100.00 | \$0,00 | \$0.00 | \$0.00 |
| pg 2-22 | | 11 | | Power devices - bsmnt | \$350.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 2-28 | | 11 | | Power devices-1st flr | \$1,918.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 2-32 | | 11 | | Power wire-2nd floor | \$8,500.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 2-34 | | 11 | | Power devices-2nd flor | \$1,400.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 3-4 | | 11 | | Power wire gym add | \$3,000.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 3-6 | | 11 | | Power devices gym add | \$932.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 3-12 | | 11 | | Fire Alarm wire | \$2,000.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 4-14 | | 11 | | A/V material | \$10,980.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 1 - 37 | | 13 | | Itg fixtures 2nd floor | \$36,000.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 2 - 6 | | 13 | | ltg fixtures gym addition | \$3,500.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 2-8 | | 13 | | Itg fixtures gym addition | \$2,300.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 4-14 | | 13 | | AV material | \$15,250.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 4-34 | | 14 | | GYM a/v cabling equip | \$12,982.00 | \$0.00 | \$0.00 | \$0.00 |
| pg 4-36 | | 14 | | Battery clock material | \$3,864.00 | \$0.00 | \$0.00 | \$0.00 |
| | | | | | | | | |
| | | | | | | | | \$0.00 |
| | | | | | | | Total | \$0.00 |
| | | | | | | | Less 8% Retainage | \$0.00 |
| | | | | | | To | tal Stored at Site | \$0.00 |

| | | Total Stored at Site | \$0.00 |
|---|-----------|----------------------|--------|
| The undersigned have visited, reviewed, and approved the place | Approved: | | |
| for storage of the fabricated materials for which the Contractor is | | | |
| requesting payment. The fabricated materials are in conformity | | | |
| with the Specifications and have been tagged with the Project | Architect | Date | |
| name and number for delivery to the Project. | | | |
| UNITED ELECTRIC COA INC. | | | |
| 7 Mary 6 / M 09/24/10 | | | |
| Contractor Date | | | |

OSFC-120c

PHONE (614) 466-6290 FAX (614)466-7749

1/13/1999



Ohio School Facilities Commission 88 East Broad Street, Suite 1400 Columbus, OH 43215

| Project / Contract #: | -ПГ | $\Box\Box\Box$ | - | ПП | Contract Name |
|-----------------------|-----|----------------|---|----|---------------|

| | Certification | of Material | Stored | Off Site |
|--|---------------|-------------|--------|----------|
|--|---------------|-------------|--------|----------|

| | Certification of Material Stored Off Site | | | | | | | | | |
|-----------|---|-----------|--------------------|---------------------------|-------------|------------------|----------------|-----------------|--|--|
| | | | | | | New | Mat. Installed | | | |
| Line Item | | Pay | | | Previous | Materials Stored | This Period | Total Materials | | |
| Reference | Invoice # | Request # | Material Supplier | Description | Amount | (Add) | (Deduct) | Stored off site | | |
| | | 8 | Structured Cabling | Hoirzonatl Cabling Mat'l | \$6,067.50 | \$0.00 | | \$0.00 | | |
| | | 8 | Structured Cabling | Fiber Copper Backbone m | \$1,500.00 | \$0.00 | | \$0.00 | | |
| | | 8 | Structured Cabling | Classroom Sound mat'l | \$9,972.50 | \$0.00 | | \$0.00 | | |
| | | 8 | Structured Cabling | A/V Material | \$30,500.00 | \$0.00 | | \$0.00 | | |
| | | 8 | Structured Cabling | CCTV Cabling Equip Mat | \$22,400.00 | \$0.00 | | \$0.00 | | |
| | | 8 | Structured Cabling | Access Ctrl Conduit mat'l | \$1,100.00 | \$0.00 | | \$0.00 | | |
| | | 8 | Structured Cablin | Paging Cabling equip/mat | \$1,822.50 | \$0.00 | | \$0.00 | | |
| | | 9 | Structured Cablin | Tele Data conduit mat | \$2,375.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 9 | Structured Cablin | horz. Cabling mat'l | \$45,506.25 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 9 | Structured Cablin | Fiber Copper Backbone m | \$3,000.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 9 | Structured Cablin | A/V Condut material | \$4,400.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 9 | Structured Cablin | CCTV Conduit mat'l | \$3,400.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 9 | Structured Cablin | Access Ctrl Conduit mat'l | \$2,750.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 9 | Structured Cablin | paging conduit mat'l | \$1,000.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 9 | Structured Cablin | Gym A/V conduit mat'l | \$800.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 10 | Structured Cablin | Classroom Sound mat'l | \$398.90 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 10 | Structured Cablin | A/V Material | \$1,220.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 10 | 1 | CCTV Cabling Equip Mat | . , | \$0.00 | \$0.00 | \$0.00 | | |
| | | 10 | Structured Cablin | Paging, cabling equip mat | \$911.25 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 11 | Structured Cablin | Access Ctrl Cabling/Equip | \$6,961.20 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 11 | Structured Cablin | Paging/cabling equip mat | \$10,935.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 11 | Structured Cablin | Network electronics mat'l | \$68,700.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 11 | Structured Cablin | Equip Rm bldg mat'l | \$9,000.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 12 | Structured Cablin | Classroom Sound mat'l | \$997.25 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 12 | Structured Cablin | A/V Material | \$3,050.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | 12 | Structued Cabling | CCTV Cabling Equip Mat | \$1,680.00 | \$0.00 | \$0.00 | \$0.00 | | |
| | | |] | | | | | | | |
| | | | | | | | - | | | |
| | | | | | | | | | | |
| | | | | | | | Total | \$0.00 | | |

Total \$0.00 \$0.00 Less 8% Retainage Total Stored at Site \$0.00

| The und | ersigned have visited, reviewed, and approved the place |
|-----------|---|
| for stora | ge of the fabricated materials for which the Contractor i |
| requestir | ag payment. The fabricated materials are in conformity |
| with the | Specifications and have been tagged with the Project |
| name an | d number for delivery to the Project. |
| UNITE | ED ELECTRIC CO. INC. |

Contractor

Approved:

Architect

Date

| ł. | | | | 1 |
|-------------------|--------------------------|---|------------------|---|
| | RIGINAL OR SUBCONTRACTO | OR No. 44 | • | |
| (R.C. 1311.04 Eff | | | | |
| State of Ohi | | | Ohio | 9.24 2010 |
| | Hamilton | | , Ohio | |
| THOMAS G | 6. MURRAY | , being first duly sworn, says the | it (s)ne is (1) | ACCOUNTING |
| of (2) | UNITED ELECTRIC | CO., INC. | | |
| contractor h | naving a contract with | (2) CPS FACILITIES | S/OHIO SCHO | OOL COMMISSION |
| the (3) | OWNER | for (4) | | |
| а | SCHOOL | | situated | on or around or in front of the following property, |
| (5) in | Hamilton | County, Ohio, vi | z: | HARTWELL ELEMENTARY SCHOOL |
| LOCATED | AT 125 W. NORTH I | BEND ROAD, CINCINNATI OHIO | 45216 | |
| whereof (2) | CPS FACILITIES/C | HIO SCHOOL BD. COMMISSION | | was the Onwer, Part-Owner or Lessee: |
| | | | | |
| | | SUB-CONTR | ACTORS | |
| | Affiant further says tha | at the following shows the names and a | dresses of ever | y sub-contractor in the employ of said |
| (2) | | | | due, or about to become due, to them, or any |
| of them, for v | vork done, or machinery | , material or fuel furnished to date here | of, under said o | contracts. |
| | | | | week of the subsentington |
| | | companied by a similar sworn state | ment signea o | y each or the subcontractors |
| listed below | • | | | |
| NAME | | ADDRESS | TRADE | AMOUNT |
| NAME | | VDDIVEOO | TIVAUL | \$0.00 |
| | | MATERIA | M=N | 1 40.00 |
| | B. M. Marit Callerina | MATERIA | | of overer person furnishing machinery |

Said affiant further says that the following shows the names and addresses of every person furnishing machinery, material or fuel to (2) giving the amount, if any, which is due, or to become due, to them, or to any of them, for machinery, material or fuel furnished to date hereof, under the said contracts.

| NAME | ADDRESS | TRADE | AMOUNT |
|--------------------|---------|-------|------------|
| F.D. LAWRENCE | | | \$3,676.30 |
| ELEX INC. | | | \$1,167.03 |
| WESCO DISTRIBUTION | | | \$529.71 |
| | | | |
| | | | 4 |
| | | | |
| | | | • |
| | | | - |
| | | | - |

NOTE: The above must be accompanied by "Certificate of Materialman" in lieu of such certificates, there may be furnished a Waiver of Lien, a written release or receipt.

LABOR

Said affiant further says that the following shows the names and addresses of every unpaid laborer in the employ of (2) furnishing labor under said contract, giving the amount, if any which is due or to become due, for albor done to date hereof.

NOTE: If the fact is that every laborer has been paid in full, then recite: "Every laborer has been paid in full." If not, then give each unpaid laborer's name and address and the amount due or to become due.

| NAME ADDRESS | HOURS AMOUNT DUE |
|--|--|
| ALL LABORERS HAVE BEEN PAID IN FULL. | |
| | TIES/OHIO SCHOOL BOARD COMMISSION to date 19.60 (Owner or Contractor) |
| are fully and correctly set forth opposite their names, respectively, in by certificates of every person furnishing machinery, material or fuel | |
| has not employeed or purchased or procured machinery, material or corporation, other than those mentioned, and owes for no labor p said contracts, other than above set forth. | |
| SWORN TO BEFORE ME AND SUBSTRIBED IN MY PRESENCE September 2010 Daniel Leesman Notary Public, State of Ohio My Commission Expires 04-08-2014 | CINCINNATI , Ohio MM L TV M NOTARY PUBLIC, COUNTY, OHIO |
| Secy., Treas, one of riem or agent, as cause may be | "Constructing, altering or repairing a boat, vessel or other watercraft," or |
| 2. Name and address | "erecting, altering repairing or removing a house, mill, manaufactory or any |
| 3. "Owner," "Part Owner," or "Lessee," or "authorized agent of the owner, | furnace, or furnace material therein, or other building appurtenance, |
| part owner or lessee," or "original" or "principal contractor under a | fixture, bridge or other structure," or "digging," "drilling, broing, operating, |
| contract with the owner, part owner or lessee," as the case may be. | completing and repairing any gas well, oil well, or other well," or "altering, |
| | repairing or constructing any oil derrick, oil tank, oil or gas pipe line," or |
| | "furnishing tile for the drainage of any lot or land," as the case may be. |
| | 5. Accurate description of property |
| | Contractor or subcontractor executing affidavit. |
| | FFIDAVIT |
| | OF |
| | SUB-CONTRACTOR |
| | TIES/OHIO SCHOOL BD. COMMISSION |
| HEAD CONTRACTOR: UNITED EL | ECTRIC CO., INC. |
| SUB-CONTRACTOR: | |
| DATE: | |

Statement of Compliance

| Date: SEPTEMBER 24, 2010 | | 911 | Contract Number: BID PACKAGE 6B |
|--|--|--|--|
| I, TOM MURRAY, PAYROLL DEPARTMENT do hereby state: | | 177 | |
| (1) That I pay or supervise the payment of the persons employed by United Electr SEPTEMBER, 2010, all persons employed on said project have been paid the full we earned by any person and that no deductions have been made either directly or indire under the Copeland Act, as amended (48 Stat. 948.63 Stat. 108, 72 Stat. 967; 76 Stat. | eckly wages earned, that no rebates have been or will be made either di- ectly from the full wages earned by any person, other than permissible d | rectly or indirectly to or on behalf of said | United Electric Co., Inc. from the full weekly wages |
| (2) That any payrolls otherwise under this contract required to be submitted for th determination incorporated into the contract; that the classifications set forth therein to | he above period are correct and complete; that the wage rates for labore for each laborer or mechanic conform with the work he performed. | ers or mechanics contained therein are no | ot less than the applicable wage rates contained in any wage |
| (3) That any apprentices employed in the above period are duly registered in a box Labor, or if no such recognized agency exists in a State, are registered with the Burea | ona fide apprenticeship program registered with a State apprenticeship a au of Apprenticeship and Training, United States Department of Labor. | agency recognized by the Bureau of Appr | renticeship and Training, United States Department of |
| (4) That: | | | |
| (a) WHERE FRINGE BENEFITS ARE PAID TO APPROVED PLANS, FU | UNDS, OR PROGRAMS | | |
| In addition to the basic hourly wage rates paid to each laborer or for the benefit of such employees, except as noted in Section 4(c) | r mechanic listed in the above referenced payroll, payments of fringe b below. | enefits as listed in the contract have bee | n or will be made to appropriate programs |
| (b) WHERE FRINGE BENEFITS ARE PAID IN CASH | | | |
| Each laborer or mechanic listed in the above referenced payroll has as listed in the contract, except as noted in Section 4(c) below. | has been paid as indicated on the payroll, an amount not less than the su | m of the applicable basic hourly wage ra | te plus the amount of the required fringe benefits |
| (c) EXCEPTIONS | | | |
| EXCEPTION (Craft) | - 1 | EXPLANATION | |
| | | | |
| REMARKS | | | |
| NAME AND TITLE | SIGNATURE | 1 | 1 |

The willful falsification of any of the above statements may subject the contractor or subcontractor to civil or criminal prosecution. See Section 1001 of Title 18 and Section 231 of Title 31 of the United States Code.

TOM MURRAY, PAYROLL DEPARTMENT

United Electric Co., Inc. 4333 Robards Lane

Pay Period Date: Week Ending: Payroli No:

09/19/10 09/19/10 75

Certified Payroll Report

Contract #: Job No: Job Name:

BID PACKAGE 6B

09-16024

HARTWELL ELEMENTARY

Louisville, KY 40218 502 459-5242

| | # Exemptions | | | | Hours | | | | | (| Other Job Pay | FICA | Local | Tot Ded |
|-------------------------|---|-----------------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|-------------------------------------|--------------------------------|-------------------------------------|------------------------------------|
| | Social Security Work Class | MON 13 | TUE 14 | WED 15 | THU 16 | FRI 17 | SAT 18 | SUN 19 | Total | Rate | Job Gross Total Gross | Fed W/H State | Union | Benefits |
| RATZ, JOSEPH MICHAEL | Ex: S-01 C M O ***_**_4824 S 49% APPRENTICE | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 13.84 | | 42.36 <i>50.85</i> 18.17 | 11.63 31.70 25.00 Check #; | 179.71 0.00 373.89 181205 |
| REDDING, RAMON D | Ex: S-01 B M O ***-**-2885 S 58% PERCENT | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 15.14 | 0.00 605.60 605.60 | 46.32 58.65 15.82 | 12,72 34,30 0.00 Check #: | 167.81 0.00 437.79 181206 |
| SCHRAND, RAYMOND PIERCE | , Ex: M-00 C M O ***-**-2 <i>014</i> S JOURNEYMAN 1ST S | 0.00 8.00 SHIFT | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 28.72 | 0.00 <i>1,148.80</i> 1,148.80 | 87.88 122.32 37.92 | 61.45 | 333.69 0.00 815.11 |

Check #:

181214

Statement of Compliance

Date: SEPTEMBER 8, 2010 Contract Number: BID PACKAGE 6B

1, TOM MURRAY, PAYROLL DEPARTMENT do hereby state:

(1) That I pay or supervise the payment of the persons employed by United Electric Co., Inc. on the HARTWELL ELEMENTARY, that during the payroil period commencing on the 16 day of AUGUST, 2010 and ending the 22 day of AUGUST, 2010, all persons employed on said project have been paid the full weekly wages earned, that no rebates have been or will be made either directly or indirectly to or on behalf of said United Electric Co., Inc. from the full weekly wages earned by any person and that no deductions have been made either directly or indirectly from the full wages earned by any person, other than permissible deductions as defined in Regulations, Part 3 (29 CFR Subtitle A), issued by the Secretary of Labor under the Copeland Act, as amended (48 Stat. 948.63 Stat. 108, 72 Stat. 967; 76 Stat. 357; 40 U.S.C. 3145), and described below:

- (2) That any payrolls otherwise under this contract required to be submitted for the above period are correct and complete; that the wage rates for laborers or mechanics contained therein are not less than the applicable wage rates contained in any wage determination incorporated into the contract: that the classifications set forth therein for each laborer or mechanic conform with the work he performed.
- (3) That any apprentices employed in the above period are duly registered in a bona fide apprenticeship program registered with a State apprenticeship agency recognized by the Bureau of Apprenticeship and Training, United States Department of Labor, or if no such recognized agency exists in a State, are registered with the Bureau of Apprenticeship and Training, United States Department of Labor.
- (4) That;
 - (a) WHERE FRINGE BENEFITS ARE PAID TO APPROVED PLANS, FUNDS, OR PROGRAMS
 - In addition to the basic hourly wage rates paid to each laborer or mechanic listed in the above referenced payroll, payments of fringe benefits as listed in the contract have been or will be made to appropriate programs for the benefit of such employees, except as noted in Section 4(c) below.
 - (b) WHERE FRINGE BENEFITS ARE PAID IN CASH
 - Each laborer or mechanic listed in the above referenced payroll has been paid as indicated on the payroll, an amount not less than the sum of the applicable basic hourly wage rate plus the amount of the required fringe benefits as listed in the contract, except as noted in Section 4(c) below.
 - (c) EXCEPTIONS

| EXCEPTION (Craft) | EXPLANATION | | | | | |
|--------------------------------|-----------------------|--|--|--|--|--|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| REMARKS | | | | | | |
| NAME AND TITLE | SIGNATURE TURNAS Muum | | | | | |
| TOM MURRAY, PAYROLL DEPARTMENT | (VVQTW (1/100 - | | | | | |

United Electric Co., Inc. 4333 Robards Lane

Pay Period Date: Week Ending: Payroll No:

08/22/10

Certified Payroll Report

Contract #: Job No: Job Name: BID PACKAGE 6B 09-16024

HARTWELL ELEMENTARY

Louisville, KY 40218 502 459-5242

| | # Exemptions _ | | | | Hours | | | | | | Other Job Pay | FICA | Local | Tot Ded |
|-----------------------------|--|--------------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|----------------------------------|--------------------------|-------------------------------------|---|
| Employee | Social Security Work Class | MON 16 | TUE 17 | WED 18 | THU 19 | FRI 20 | SAT 21 | SUN 22 | Total | Rate | Job Gross Total Gross | Fed W/H State | Union Oth Ded | Benefits Net Chk |
| HOWELL, MARCIA R | Ex: S-02 B F O | 0.00 | 0,00 8.00 | 0,00 6.50 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 30.50 | 0.00 19.06 | 0.00 <i>581.3</i> 3 581.33 | 44.47 44.48 13.93 | 12.21 32.11 75.00 Check #: | 222.20 0.00 359,13 180457 |
| LOCKARD, JAY H | Ex: M-04 C M O | 0.00 0.00 FT | 0.00 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 24.00 | 0.00 26.11 | 0.00 626.64 626.64 | 47.95 8.14 15.19 | 13.16 82.65 33.00 Check #: | 200.09 0.00 426.55 180465 |
| MILLER, MICHAEL J | Ex: M-04 C M O 9249 S JOURNEYMAN | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 26.11 | 0.00 1,044.40 1,044.40 | 79.90 64.54 31.91 | 21.93 139.75 0.00 Check #: | 338.03 <i>0.00</i> 706.37 180469 |
| RATZ, JOSEPH MICHAEL | Ex: S-01 C M O4824 S 49% APPRENTICE | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 13.84 | 0.00 553.60 553.60 | 42,35 50.85 18.17 | 11.63 31.70 25.00 Check #: | 179.70 <i>0.00</i> 373.90 180474 |
| REDDING, RAMON D | Ex: S-01 B M O2885 S 58% PERCENT | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 00,0 | 0.00 00,0 | 0.00 40.00 | 0.00 15.14 | 0.00 605.60 605.60 | 46.32 58.65 15.82 | 12.72 34.30 0.00 Check #: | 167,81 0.00 437,79 180475 |
| SCHRAND, RAYMOND PIERCE, JR | Ex: M-00 C M O 2014 S JOURNEYMAN 1ST SHI | 0.00 8.00 FT | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0,00 00,0 | 0.00 0.00 | 0.00 40.00 | 0.00 28.72 | 0.00 1,148.80 1,148.80 | 87.89 122.32 37.92 | 24.12 61.45 -8.99 Check #: | 324.71 0,00 824.09 180484 |

Statement of Compliance

Date: SEPTEMBER 9, 2010 Contract Number: BID PACKAGE 6B

I, TOM MURRAY, PAYROLL DEPARTMENT do hereby state:

(1) That I pay or supervise the payment of the persons employed by United Electric Co., Inc. on the HARTWELL ELEMENTARY, that during the payroll period commencing on the 23 day of AUGUST, 2010 and ending the 29 day of AUGUST, 2010, all persons employed on said project have been paid the full weekly wages earned, that no rebates have been or will be made either directly or indirectly to or on behalf of said United Electric Co., Inc. from the full weekly wages earned by any person and that no deductions have been made either directly or indirectly from the full wages earned by any person, other than permissible deductions as defined in Regulations, Part 3 (29 CFR Subtitle A), issued by the Secretary of Labor under the Copeland Act, as amended (48 Stat, 948.63 Stat, 108, 72 Stat, 967; 76 Stat, 357; 40 U.S.C. 3145), and described below:

- (2) That any payrolls otherwise under this contract required to be submitted for the above period are correct and complete; that the wage rates for laborers or mechanics contained therein are not less than the applicable wage rates contained in any wage determination incorporated into the contract; that the classifications set forth therein for each laborer or mechanic conform with the work he performed.
- (3) That any apprentices employed in the above period are duly registered in a bona fide apprenticeship program registered with a State apprenticeship agency recognized by the Bureau of Apprenticeship and Training, United States Department of Labor, or if no such recognized agency exists in a State, are registered with the Bureau of Apprenticeship and Training, United States Department of Labor.
- (4) That:
 - (a) WHERE FRINGE BENEFITS ARE PAID TO APPROVED PLANS, FUNDS, OR PROGRAMS
 - () In addition to the basic hourly wage rates paid to each laborer or mechanic listed in the above referenced payroll, payments of fringe benefits as listed in the contract have been or will be made to appropriate programs for the benefit of such employees, except as noted in Section 4(c) below.
 - (b) WHERE FRINGE BENEFITS ARE PAID IN CASH
 - Each laborer or mechanic listed in the above referenced payroll has been paid as indicated on the payroll, an amount not less than the sum of the applicable basic hourly wage rate plus the amount of the required fringe benefits as listed in the contract, except as noted in Section 4(c) below.

(c) EXCEPTIONS

| EXCEPΠΟΝ (Craft) | EXPLANATION |
|-------------------------------|------------------------|
| | |
| | |
| | |
| EMARKS | |
| AME AND TITLE | SIGNATURE 1.4 |
| OM MURRAY, PAYROLL DEPARTMENT | SIGNATURE / Worns Munz |

United Electric Co., Inc. 4333 Robards Lane

Pay Period Date: Week Ending: Payroll No:

08/29/10

Certified Payroll Report

Contract #: Job No: Job Name: BID PACKAGE 6B

09-16024 HARTWELL ELEMENTARY

Louisville, KY 40218 502 459-5242

| | # Exemptions | | | | Hours | | | | | | Other Job Pay | FICA | Local | Tot Ded |
|-----------------------------|---|----------------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|---------------|-------------------------------------|--------------------------------|--|------------------------------------|
| Employee | Social Security Work Class | MON 23 | TUE 24 | WED 25 | THU 26 | FRI 27 | SAT 28 | SUN 29 | Total | Rate | Job Gross Total Gross | Fed W/H State | Union Oth Ded | Benefits Net Chk |
| HOWELL, MARCIA R | Ex: S-02 B F 0 | 0.00 8.00 EA | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 19.06 | 0,00 <i>762.40</i> 762.40 | 58.32 71.64 20.87 | 16,01 <i>42,10</i> 75,00 Check #: | 283.94 0.00 478.46 180655 |
| MAINS, JASON EARL | Ex: S-00 C M O ***-**-7668 S 40% APP W/COPE | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 13.84 | 0.00 553.60 553.60 | 42.36 61.38 26.23 | 11.63 31.70 0.00 Check #: | 173.30 0.00 380.30 180664 |
| MILLER, MICHAEL J | Ex: M-04 C M O S JOURNEYMAN | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.08 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 26.11 | 0.00 1,044.40 1,044.40 | 79.89 <i>64.54</i> 31.91 | 21.93 139.75 0.00 Check #: | 338.02 0.00 706.38 180667 |
| RATZ, JOSEPH MICHAEL | Ex: S-01 C M O4824 S 49% APPRENTICE | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 5.00 | 0.00 0.00 | 0.00 0.00 | 0.00 37.00 | 0.00 13.84 | 0.00 <i>512.08</i> 512.08 | 39.18 <i>44.62</i> 16.76 | 10.75 29.32 25.00 Check #: | 165.63 0.00 346.45 180672 |
| REDDING, RAMON D | Ex: S-01 B M O2885 S 58% PERCENT | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 00.8 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 40.00 | 0.00 15.14 | 0.00 <i>605.60</i> 605.60 | 46.33 58.65 15.82 | 12,72 34,30 0,00 Check #: | 167.82 0.00 437.78 180673 |
| REED, MARK DELBERT | Ex: M-00 C M O | 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 32.00 | 0.00 26,11 | 0.00 835. <i>5</i> 2 835.52 | 63.91 75.33 25.05 | 17.55 111.80 175.00 Check #: | 468.64 0.00 366.88 180674 |
| SCHRAND, RAYMOND PIERCE, JR | Ex: M-00 C M O | 0.00 8.00 ⊣IFT | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0,00 40.00 | 0.00 28.72 | 0,00 <i>1,148.80</i> 1,148.80 | 87.88 122.32 37.92 | 24.12 <i>61.4</i> 5 0.00 Check #: | 333.69 0.00 815.11 180682 |

Statement of Compliance

Date: SEPTEMBER 15, 2010 Contract Number: BID PACKAGE 6B

I, TOM MURRAY, PAYROLL DEPARTMENT do hereby state:

(1) That I pay or supervise the payment of the persons employed by United Electric Co., Inc. on the HARTWELL ELEMENTARY, that during the payroll period commencing on the 30 day of AUGUST, 2010 and ending the 5 day of SEPTEMBER, 2010, all persons employed on said project have been paid the full weekly wages earned, that no rebates have been or will be made either directly or indirectly to or on behalf of said United Electric Co., Inc. from the full weekly wages earned by any person and that no deductions have been made either directly or indirectly from the full wages earned by any person, other than permissible deductions as defined in Regulations, Part 3 (29 CFR Subtitle A), issued by the Secretary of Labor under the Copeland Act, as amended (48 Stat. 948.63 Stat. 108, 72 Stat. 967; 76 Stat. 357; 40 U.S.C. 3145), and described below:

- (2) That any payrolls otherwise under this contract required to be submitted for the above period are correct and complete; that the wage rates for laborers or mechanics contained therein are not less than the applicable wage rates contained in any wage determination incorporated into the contract: that the classifications set forth therein for each laborer or mechanic conform with the work he performed.
- (3) That any apprentices employed in the above period are duly registered in a bona fide apprenticeship program registered with a State apprenticeship agency recognized by the Bureau of Apprenticeship and Training, United States Department of Labor, or if no such recognized agency exists in a State, are registered with the Bureau of Apprenticeship and Training, United States Department of Labor.

(4) That:

- (a) WHERE FRINGE BENEFITS ARE PAID TO APPROVED PLANS, FUNDS, OR PROGRAMS
- In addition to the basic hourly wage rates paid to each laborer or mechanic listed in the above referenced payroll, payments of fringe benefits as listed in the contract have been or will be made to appropriate programs for the benefit of such employees, except as noted in Section 4(c) below.
- (b) WHERE FRINGE BENEFITS ARE PAID IN CASH
- Each laborer or mechanic listed in the above referenced payroll has been paid as indicated on the payroll, an amount not less than the sum of the applicable basic hourly wage rate plus the amount of the required fringe benefits as listed in the contract, except as noted in Section 4(c) below.

(c) EXCEPTIONS

| EXCEPTION (Cmft) | EXPLANATION |
|--------------------------------|-----------------------|
| | |
| | |
| | |
| REMARKS | |
| NAME AND TITLE | SIGNATURE 77 |
| FOM MURRAY, PAYROLL DEPARTMENT | SIGNATURE Thomas Muny |

United Electric Co., Inc. 4333 Robards Lane

Pay Period Date: Week Ending: Payroll No:

09/05/10

Certified Payroll Report

Contract #: Job No: BID PACKAGE 68 09-16024

Job No: 09-16024

Job Name: HARTWELL ELEMENTARY

Louisville, KY 40218 502 459-5242

Hours # Exemptions Other Job Pay FICA Local Tot Ded Social Security MON TUE WED THU FRI Fed W/H SAT SUN Job Gross Union Benefits Employee Work Class 30 31 01 02 03 04 05 Total Rate Total Gross State Oth Ded Net Chk HOWELL, MARCIA R Ex: \$-02 B F 0 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 58.33 16.01 283.95 ***--*-4929 S 8.00 8.00 8.00 8.00 8.00 0.00 0.00 40.00 19.06 762.40 71.54 42.10 0.00 53% W/COPE - 4TH YEA 75.00 478.45 762.40 20.87 Check #: 180827 LAYMON, WILLIAM EDWARD Ex: M-04 C M 0 0.00 0.00 0.00 0,00 0.00 0.00 0.00 0.00 0.00 0.00 70.31 19.30 360,68 ***- ***- 6765 s 8.00 8.00 8.00 8.00 0.00 0.00 0.00 32.00 28.72 919.04 45.74 122,68 0.00 JOURNEYMAN 1ST SHIFT 919.04 27,65 75.00 558.36 180833 Check #: MAINS, JASON EARL Ex: S-00_C M 0 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 42.34 11.63 173.28 ***- 7668 s 8.00 8.00 8.00 8.00 8.00 0.00 0.00 40.00 13.84 553,60 61.38 31.70 0.00 40% APP W/COPE 553.60 26,23 0.00 380.32 180836 Check #: MILLER, MICHAEL J Ex: M-04 C M 0 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 79.90 21.93 338.03 ***-**-9249 s 8.00 8.00 8.00 8.00 8.00 0.00 0.00 40.00 26.11 1.044.40 64.54 139.75 0.00 JOURNEYMAN. 1,044,40 31.91 0.00 706.37 Check #: 180839 RATZ, JOSEPH MICHAEL 0 0.00 Ex: S-01 C M 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 42.35 11.63 179.70 ***-**-4824 s 8.00 8.00 8.00 8.00 8.00 0.00 0.00 40,00 13.84 553.60 50.85 31.70 0.00 49% APPRENTICE 553.60 18.17 25.00 373.90 180844 Check #: REDDING, RAMON D 0 Ex: S-01 B M 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 46.34 12.72 167.83 ***-**-2885 s 8.00 8.00 8.00 8.00 8.00 0.00 0.00 40.00 15.14 605.60 58,65 34.30 0.00 58% PERCENT 605,60 15.82 0.00 437.77 Check #: 180845 REED, MARK DELBERT Ex: M-00 C M 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 95.89 26.32 646,60 ***-**-0941 8.00 8.00 8.00 0.00 0.00 0.00 0.00 26.11 626.64 24.00 137.99 167.70 0.00 JOURNEYMAN 1,253,28 43.70 175.00 606.68 Check #: 180846 SCHRAND, RAYMOND PIERCE, JR Ex: M-00 C M 0 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.00 87,88 24.12 296.54 ***-**-2014 8.00 8,00 8.00 8.00 8.00 0.00 0.00 40.00 28.72 1,148.80 122.32 61.45 0.00 JOURNEYMAN 1ST SHIFT 852,26 1,148.80 37.92 -37.15 Check #: 180854

Statement of Compliance

Date: SEPTEMBER 17, 2010

I, TOM MURRAY, PAYROLL DEPARTMENT do hereby state:

(1) That I pay or supervise the payment of the persons employed by United Electric Co., Inc. on the HARTWELL ELEMENTARY, that during the payroll period commencing on the 6 day of SEPTEMBER, 2010 and ending the 12 day of

Contract Number: BID PACKAGE 6B

under the Copeland Act, as amended (48 Stat. 948.63 Stat. 108, 72 Stat. 967; 76 Stat. 357; 40 U.S.C. 3145), and described below:

SEPTEMBER, 2010, all persons employed on said project have been paid the full weekly wages earned, that no rebates have been or will be made either directly or indirectly to or on behalf of said United Electric Co., Inc. from the full weekly wages earned by any person and that no deductions have been made either directly or indirectly from the full wages earned by any person, other than permissible deductions as defined in Regulations, Part 3 (29 CFR Subtitle A), issued by the Secretary of Labor

- (2) That any payrolls otherwise under this contract required to be submitted for the above period are correct and complete, that the wage rates for laborers or mechanics contained therein are not less than the applicable wage rates contained in any wage determination incorporated into the contract; that the classifications set forth therein for each laborer or mechanic conform with the work he performed.
- (3) That any apprentices employed in the above period are duly registered in a bona fide apprenticeship program registered with a State apprenticeship agency recognized by the Bureau of Apprenticeship and Training, United States Department of Labor, or if no such recognized agency exists in a State, are registered with the Bureau of Apprenticeship and Training, United States Department of Labor.
- (4) That:
 - (a) WHERE FRINGE BENEFITS ARE PAID TO APPROVED PLANS, FUNDS, OR PROGRAMS
 - In addition to the basic hourly wage rates paid to each laborer or mechanic listed in the above referenced payroll, payments of fringe benefits as listed in the contract have been or will be made to appropriate programs for the benefit of such employees, except as noted in Section 4(c) below.
 - (b) WHERE FRINGE BENEFITS ARE PAID IN CASH
 - Each laborer or mechanic listed in the above referenced payroll has been paid as indicated on the payroll, an amount not less than the sum of the applicable basic hourly wage rate plus the amount of the required fringe benefits as listed in the contract, except as noted in Section 4(c) below.
 - (c) EXCEPTIONS

| EXCEPTION (Craft) | EXPLANATION |
|--------------------------------|---------------------|
| | |
| | |
| | |
| REMARKS | |
| NAME AND TITLE | SIGNATURE 04 |
| TOM MURRAY, PAYROLL DEPARTMENT | SIGNATURE Thomas Mu |

United Electric Co., Inc. 4333 Robards Lane

Pay Period Date: Week Ending: Payroll No:

09/12/10

Certified Payroll Report

Contract #: Job No: Job Name:

BID PACKAGE 6B

09-16024 HARTWELL ELEMENTARY

Louisville, KY 40218 502 459-5242

09/12/10 74

| | # Exemptions | | | | Hours | | | | | c | Other Job Pay | FICA | Local | Tot Ded |
|--------------------------|--|---------------------|--------------|--------------|--------------|--------------|--------------|--------------|---------------|----------------|-----------------------------------|---------------------------------|---|------------------------------------|
| Employee | Social Security Work Class | MON 06 | TUE 07 | WED 08 | THU 09 | FRI 10 | SAT 11 | SUN 12 | Total | Rate | Job Gross Total Gross | Fed W/H State | Union Oth Ded | Benefits Net Chk |
| HOWELL, MARCIA R | Ex: S-02 B F O ***-**-4929 S 53% W/COPE - 4TH YE | 0.00 0.00 A | 0.00 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 24.00 | 0.00 19.06 | 0.00 457.44 457.44 | 34.99 25. <i>90</i> 9.19 | 9.61 25.26 75.00 Check #: | 179.95 0.00 277.49 181013 |
| LAYMON, WILLIAM EDWARD | Ex: M-04 C M 0 ***-**-6765 S JOURNEYMAN 1ST SH | 0.00 0.00 IFT | 0.00 3.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 27.00 | 0.00 28.72 | 0.00 <i>775.44</i> 919.04 | 70.30 45.74 27.65 | 18.43 122.68 75.00 Check #: | 359.80 0.00 559.24 181019 |
| MAINS, JASON EARL | Ex: S-00 C M O ***-**-7668 S 40% APP W/COPE | 0.00 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 32.00 | 0.00 13.84 | 0.00 <i>442.88</i> 608.96 | 46.59 69.69 29.44 | 9.30 <i>34.46</i> 0.00 Check #: | 189.48 0.00 419.48 181022 |
| MILLER, MICHAEL J | Ex: M-04 C M O ***-**-9249 S JOURNEYMAN | 0.00 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 32.00 | 0.00 26.11 | 0.00 835.52 835.52 | 63.92 33. <i>21</i> 24.81 | 17.55 111.80 0.00 Check #: | 251,29 0.00 584,23 181025 |
| RATZ, JOSEPH MICHAEL | Ex: S-01 C M O ***-*-4824 S 49% APPRENTICE | 0.00 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 32.00 | 0.00 13.84 | 0.00 <i>442.88</i> 442.88 | 33.87 <i>34.24</i> 14.40 | 9.30 25.36 25.00 Check #: | 142.17 0.00 300.71 181030 |
| REDDING, RAMON D | Ex: S-01 B M O ***-*-2885 S 58% PERCENT | 0.00 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 | 0.00 32.00 | 0.00 15.14 | 0.00 <i>484.48</i> 484.48 | 37.06 <i>40.48</i> 11.18 | 10.17 27.44 0.00 Check #: | 126.33 0.00 358.15 181031 |
| REED, MARK DELBERT | Ex: M-00 C M O | 0.00 0.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.00 0.00 | 0.00 0.00 | 0.00 32.00 | 0.00 26.11 | 0.00 <i>835.52</i> 1,148.88 | 87.89 122.33 39.04 | 17.55 153.34 175.00 Check #: | 595.15 0.00 553.73 181032 |
| SCHRAND, RAYMOND PIERCE, | Ex: M-00 C M O ***-**-2014 S JOURNEYMAN 1ST SHI | 0.00 0.00 FT | 0.00 8.00 | 0.00 8.00 | 0.00 8.00 | 0.50 8.00 | 0.00 0.00 | 0.00 0.00 | 0.50 32.00 | 43.08 28.72 | 0.00 <i>940.58</i> 940.58 | 71.96 91.09 28.62 | 19.75 <i>50.30</i> 0.00 Check #: | 261.72 0.00 678.86 181040 |





March 28, 2011

Angie Tolle Cincinnati Public Schools 2315 Iowa Avenue Cincinnati, OH 45206

Dear Angie:

Attached are Pay Applications for the Hartwell School, please process payment for the April 22, 2011 check distribution.

| Contractor | Application # | Monthly Billing | Total Billing To Date | Contract Amount to Date |
|---------------------|---------------|-----------------|--------------------------|-------------------------|
| BP#5B- Blau | #22 | \$ 8,220.48 | \$ 1,421,993.00 | \$1,421,993.00 |
| BP#5B- Blau | #23 | \$37,725.67 | \$ 1,421,993.00 | \$1,421,993.00 |
| BP#3B-Triton | #18 | \$29,059.52 | \$ 594,336.00 | \$ 594,336.00 |
| BP#3B-Triton | #17 | \$ 113.00 | \$ 594,336.00 | \$ 594,336.00 |

Please call if you have any questions.

Sincerely,

TURNER/DAG/TYS

Kimberly Metz

Accountant

Attachments

cc:

Vince Terry – Moody/Nolan

Darris Storms - Turner/DAG/TYS

File 0025 - 14591MF

T:PROJECTS/Hartwell/00250 Pay Application/2011-03-28BlauPay App. Lttr. Doc

The Ohio School Facilities Commission

10 West Broad Street Suite 1400 Columbus, Ohio 43215

Contractor's Name: Blau Mechanical Inc Address: 1532 Russell Street Covington, Ky 41011

| | Contractor Pay Application Summary | 138122 |
|----|--|--------------------|
| | ame Hartwell PK-8 Elementary School age No. 5B HVAC | 14-Mar-11 |
| 1 | Original Contract Amount | \$ 1,212,000.00 |
| 2 | Net Changes to Date | \$ 209,993.00 |
| 3 | Current Contract Amount | \$ 1,421,993.00 |
| 4 | | \$ |
| 5 | Completed to Date | \$ 1,421,993.00 |
| 6 | Total Work Completed to Date | \$ 1,421,993.00 |
| 7 | Store Material to Date | \$ - |
| 8 | Less Retained to Date | \$ 37,725.67 |
| 9 | Total Amount Due | \$ 1,384,267.33 |
| 10 | Less Previous Payments | \$ 1,376,046.85 |
| 11 | Less Amount Retained to Cover Lien | \$ |
| 12 | Less Amount Retained for Liquidated Damages | \$ - |
| 13 | Less Other Amounts Withheld | \$ |
| 14 | Current Due | \$ 8,220.48 |
| 15 | Balance to Complete | \$ 37,725.67 |
| | | |

| OSFC approval required for the following cont 1. Assessment of liquidated damages 2. Other amounts withheld | ract adjustments: | |
|---|-------------------|--|
| Ohio School Facilities Commission | Date | |
| Comments: | | |
| | | |
| | | |

Form OSFC-163A

payappcover.xls

Phone 614-466-6290 Fax 614-466-7749

APPLICATION AND CERTIFICATE FOR PAYMENT

TOTALS

NET CHANGES by Change Order

ostc-165ss

138122 PROJECT: Hartwell PK-8 Elementary School APPLICATION No: TO OWNER: CINCINNATI PUBLIC SCHOOLS 14-Mar-11 PERIOD TO: 2315 IOWA AVENUE PROJECT NOS: CINCINNATI, OHIO 45206 CONTRACT DATE: VIA ARCHITECT: Moody Nolan Inc FROM CONTRACTOR: BLAU MECHANICAL INC 1532 RUSSELL ST COVINGTON, KY 41011 BP 5B - HVAC CONTRACT FOR: The Contractor certified that the work covered by this pay request has been CONTRACTOR'S APPLICATION FOR PAYMENT completed in accordance with the Contract Documents and that all progress payments previously paid by the State have been applied by the Contractor to discharge in full all of Contractor's obligations incurred in connection with the work covered by all prior pay requests. Application is made for payment as shown below, in connection with the Contract Continuation sheet is attached. 15-Mar-11 Date Blau Mechanical Inc. 1.212.000.00 1. ORIGINAL CONTRACT SUM.....\$ 209,993.00 2. Net Change by Change Orders.....\$ Vicente Salazar, President 3. CONTRACT SUM TO DATE.....\$ 1,421,993.00 Based upon on-site observations, the firm affirms that the work has progressed to the 4. TOTAL COMPLETED & STORED TO DATE.....\$ 1,421,993.00 percentage of completeness indicated on the pay request. 5. RETAINAGE 37725.67 a. 8-50% of Completed Labor.....\$ b. 8% of Stored Material.....\$ Total Retainage.....\$ 37,725.67 1,384,267.33 6. TOTAL EARNED LESS RETAINAGE.....\$ 1,376,046.85 7. LESS PREVIOUS CERTIFICATES FOR PAYMENT\$ 8. CURRENT PAYMENT DUE......\$ 8.220.48 37,725.67 9. BALANCE TO FINISH, INCLUDING RETAINAGE.......\$ DEDUCTIONS **ADDITIONS** Change Order/Contract Approved: Total Changes approved in 209993.00 Previous months by Owner Total approved this month Date School District Treasurer

8/25/99

0.00

209993.00

| E | 8P#7a HVAC | | | OMPLETED | MATERIALS | TOTAL COMPLETED | | -017/20/2009 | 401 |
|------|--|------------|----------------------|------------|-----------|--|---|--------------|------------|
| EM | | SCHEDULED | PREVIOUS | · THIS | PRESENTLY | & STORED | | BALANCE | 4% |
| MBER | DESCRIPTION OF WORK | VALUE | APPS. | PERIOD | STORED | TO DATE | % | TO FINISH | RETAINAGE |
| | HVAC | | | | | | | | |
| | | 19,900.00 | 19,900.00 | | | 19,900.00 | 100% | 0.00 | 796. |
| 1- | ond Insurance Permits Tests | | 10,000.00 | | | 10,000.00 | 100% | 0.00 | 400. |
| 100 | Nobilization & Submittals | 10,000.00 | | | | 8,500.00 | 100% | 0.00 | 340.0 |
| J | ob Meetings | 8,500.00 | 8,500.00 | | | 3,000.00 | 100% | 0.00 | 120. |
| C | Cleanup - daily | 3,000.00 | 3,000.00 | | | | 2000 0 100 | 0.00 | 80.0 |
| C | Cleanup - final | 2,000.00 | 2,000.00 | | | 2,000.00 | 100% | 30.0550 | 120. |
| F | unch List | 3,000.00 | 3,000.00 | | | 3,000.00 | 100% | 0.00 | 60. |
| T | raining & Demostration | 1,500.00 | 1,500.00 | | | 1,500.00 | 100% | 0.00 | 60. |
| | Commissioning | 2,500.00 | 2,500.00 | | | 2,500.00 | ~ 100% | 0.00 | |
| | Close Out | 25,000.00 | 25,000.00 | | | 25,000.00 | 100% | 0.00 | 600. 0. |
| | | | | | | 0.00 | | | 0. |
| | DuctWork | | | | | 0.00 | | 0.00 | |
| 116 | Submittals | 1,500.00 | 1,500.00 | V . | | 1,500.00 | 100% | 0.00 | 60.0 |
| | Drafting | 33,333.00 | 33,333.00 | | | 33,333.00 | 100% | 0.00 | 1,333. |
| | Mobilization | 2,637.00 | 2,637.00 | | | 2,637.00 | 100% | 0.00 | 105.4 |
| | | 2,007.00 | -1 | | | 0.00 | 1 | 0.00 | 0.0 |
| | HV101 Basement A | 5 000 00 | 5,000.00 | | | 5,000.00 | 100% | 0.00 | 200.0 |
| | Labor | 5,000.00 | |). C | | 2,000.00 | 100% | 0.00 | 0.0 |
| | Materials | 2,000.00 | 2,000.00 | V | | 0.00 | 10070 | 0.00 | 0.0 |
| - 10 | HV102 Basement B | 1 | of research | | | | | 0.00 | 532.0 |
| | Labor | 13,300.00 | 13,300.00 | | | 13,300.00 | 100% | 2752775b. | 0.0 |
| | Materials | 6,000.00 | 6,000.00 | _ | | 6,000.00 | 100% | 0.00 | 0.0 |
| | HV111 1st fl A | 100000 | | | | 0.00 | | 0.00 | |
| | Labor | 25,300.00 | 25,300.00 | | | 25,300.00 | 100% | 0.00 | 1,012.0 |
| | Materials | 10,208.00 | 10,208.00 | | | 10,208.00 | 100% | 0.00 | 0.0 |
| | HV112 1st fl B | | | | | 0.00 | | 0.00 | 0.0 |
| | LAbor | 27,500.00 | 27,500.00 | | | 27,500.00 | 100% | 0.00 | 1,100.0 |
| | Materials | 12,000.00 | 12,000.00 | | | 12,000.00 | 100% | 0.00 | 0.0 |
| | A SAN CONTRACTOR AND | 12,000.00 | 12,000.00 | | | 0.00 | 2500 | 0.00 | 0.0 |
| | HV113 1st FI C | 45 500 00 | 45,500.00 | | | 45,500.00 | 100% | 0.00 | 1,820.0 |
| | Labor | 45,500.00 | | | | 13,000.00 | 100% | 0.00 | 0.0 |
| | Materials | 13,000.00 | 13,000.00 | | | 0.00 | 100% | 0.00 | 0.0 |
| | HV121 2nd fl A | | 45 S. J. J. J. S. W. | | | | 3220 | 0.00 | 880.0 |
| - 4 | Labor | 22,000.00 | 22,000.00 | | | 22,000.00 | 100% | 0.00 | 0.0 |
| - 11 | Materials | 9,000.00 | 9,000.00 | | | 9,000.00 | 100% | | 0.0 |
| - 4 | HV122 2nd FI B (no Gym) | | | | | 0.00 | | 0.00 | |
| | Labor | 20,000.00 | 20,000.00 | | | 20,000.00 | 100% | 0.00 | 800.0 |
| | Materials | 8,000.00 | 8,000.00 | | | 8,000.00 | 100% | 0.00 | 0.0 |
| - 11 | HV123 2nd FI C | | | | | 0.00 | | 0.00 | 0.0 |
| | Labor | 22,000.00 | 22,000.00 | | | 22,000.00 | 100% | 0.00 | 880.0 |
| | 777 A 2 C C C C C C C C C C C C C C C C C C | 7,100.00 | 7,100.00 | | | 7,100.00 | 100% | 0.00 | 0.0 |
| | Materials | 7,100.00 | 7,100.00 | | | 0.00 | 111111111111111111111111111111111111111 | 0.00 | 0. |
| | HV131 Attic A | 22.052.22 | 22,000.00 | 1 | | 22,000.00 | 100% | 0.00 | 880. |
| | Labor | 22,000.00 | | | | 12,750.00 | 100% | 0.00 | 0. |
| | Materials | 12,750.00 | 12,750.00 | | | 0.00 | 100.76 | 0.00 | 0. |
| | HV132 Attic B | | 7,070,00 | la II | | The second secon | 222.1 | 0.00 | 248. |
| | Labor | 6,200.00 | 6,200.00 | | | 6,200.00 | 100% | | 0. |
| | Materials | 2,200.00 | 2,200.00 | | | 2,200.00 | 100% | 0.00 | |
| 1 | A TOTAL OF THE STATE OF THE STA | 2000 | | | | 0.00 | | 0.00 | 0. |
| 1 | | | | | | 0.00 | | 0.00 | 0. |
| | | | | -11- | | | | | |
| 1 | FOTAL, page 3 | 403,928.00 | 403,928.00 | 0.00 | 0.00 | 403,928.00 | 100% | 0.00 | 12,426 |

| | BP#7a HVAC | | WORK COMPLETED | | MATERIALS | TOTAL COMPLETED | | | |
|---------------|---------------------|-----------------|-------------------|----------------|---------------------|---------------------|-------|----------------------|-----------------|
| ITEM UMBER | DESCRIPTION OF WORK | SCHEDULED VALUE | PREVIOUS APPS. | THIS PERIOD | PRESENTLY STORED | & STORED TO DATE | % | BALANCE TO FINISH | 4% RETAINAGE |
| | HVAC | 771202 | 1.11.0. | . 2.1.02 | CIGILES | 100,112 | - | | |
| | HV133 Attic C | | | | | 0.00 | | 0.00 | 0.0 |
| | Labor | 17,500.00 | 17,500.00 | | | 17,500.00 | 100% | 0.00 | 700.0 |
| | Materials | 8,600.00 | 8,600.00 | | | 8,600.00 | 100% | 0.00 | 0.0 |
| | HV401 Boiler Room | 8,600.00 | 0,000.00 | | | 0.00 | 100% | 0.00 | 0.0 |
| | Labor | 15,500.00 | 15,500.00 | | | 15,500.00 | 100% | 0.00 | 620.0 |
| | Materials | 6,200.00 | 6,200.00 | | | 6,200.00 | 100% | 0.00 | 0.0 |
| | HV122 Gym/ Addition | 6,200.00 | 0,200.00 | | | 0.00 | 100% | 0.00 | 0. |
| - 0.4 | Labor | 9,000.00 | 9,000.00 | | | 9,000.00 | 100% | 0.00 | 360. |
| | Materials | 3,300.00 | 3,300.00 | | | 3,300.00 | 100% | 0.00 | 0. |
| | Alt M1 Big Fans | 18,900.00 | 18,900.00 | | | 18,900.00 | 100% | 0.00 | 756. |
| | Equipment | 38,600.00 | 38,600.00 | | | 38,600.00 | 100% | 0.00 | 1,544. |
| | Duct Cleaning | 16,250.00 | 16,250.00 | Y | | 16,250.00 | 100% | 0.00 | 650. |
| | Balance | 10,000.00 | 10,000.00 | 1 1 | | 10,000.00 | 100% | 0.00 | 400, |
| | Punchlist | 1,000.00 | 1,000.00 | 1 3 | | 1,000.00 | 100% | 0.00 | 40. |
| | Fulldhist | 1,000.00 | 1,000.00 | | | 0.00 | 10078 | 0.00 | 0.0 |
| | | | | | | 0.00 | | 0.00 | 0. |
| | | | 1 | - 1 | | 0.00 | | 0.00 | 0. |
| | | 31 | | | | 0.00 | | 0.00 | 0.0 |
| | | | | | | 0.00 | - 18 | 0.00 | 0. |
| | 1 1 | -1 | 1.0 | | | 0.00 | | 0.00 | 0. |
| | | | | | | 0.00 | | 0.00 | 0.0 |
| | | 1 | | 3.1 | | 0.00 | | 0.00 | 0. |
| | | | | | | 0.00 | | 0.00 | 0.0 |
| | | | | 1 1 | | 0.00 | | 0.00 | 0.0 |
| | | 1 1 | 1 | | | 0.00 | | 0.00 | 0.0 |
| 7, (| Insulation | 1 1 | | | | 0.00 | | 0.00 | 0.0 |
| | HV101 Basement A | | | | | 0.00 | | 0.00 | 0.0 |
| | Materials | 4,200.00 | 4,200.00 | 71 | | 4,200.00 | 100% | 0.00 | 0.0 |
| | Labor | 2,800.00 | 2,800.00 | 0 (3) | | 2,800.00 | 100% | 0.00 | 112.0 |
| | HV102 Basement B | 2,000.00 | 2,000.00 | | | 0.00 | 10070 | 0.00 | 0.0 |
| | Materials | 4,200.00 | 4,200.00 | | | 4,200.00 | 100% | 0.00 | 0.0 |
| | Labor | 2,800.00 | 2,800.00 | | | 2,800.00 | 100% | 0.00 | 112.0 |
| 1 (| HV111 1st fl A | 2,000.00 | 2,000.00 | | | 0.00 | 10070 | 0.00 | 0.0 |
| | Materials | 6,000.00 | 6,000.00 | | | 6,000.00 | 100% | 0.00 | 0.0 |
| | Labor | 4,000.00 | 4,000.00 | | | 4,000.00 | 100% | 0.00 | 160.0 |
| | HV112 1st fl B | 4,000.00 | 4,000.00 | 1 | | 0.00 | 10074 | 0.00 | 0.0 |
| - 11 | Materials | 600.00 | 600.00 | 1 | | 600.00 | 100% | 0.00 | 0.0 |
| 100 | Labor | 400.00 | 400.00 | | | 400.00 | 100% | 0.00 | 16.0 |
| | HV113 1st FI C | 450.00 | 400.00 | 1 | | 0.00 | 10074 | 0.00 | 0.0 |
| | Materials | 12,000.00 | 12,000.00 | | | 12,000.00 | 100% | 0.00 | 0.0 |
| 4 | Labor | 8,000.00 | 8,000.00 | | | 8,000.00 | 100% | 0.00 | 320.0 |
| | Labor | 8,000.00 | 8,000.00 | | | 0.00 | 100 % | 0.00 | 0.0 |
| | | | | | | | | | |
| | Total Page 4 | 189,850.00 | 189,850.00 | 0.00 | 0.00 | 189,850.00 | 100% | 0.00 | 5,790.0 |

| | BP#7a HVAC | | | OMPLETED | MATERIALS | TOTAL COMPLETED | | DALANCE | 4% |
|------|--|---|-------------|----------|-----------|-----------------|-------|----------------------|-----------|
| TEM | | SCHEDULED | PREVIOUS | THIS | PRESENTLY | & STORED | 2.0 | BALANCE TO FINISH | RETAINAGE |
| MBER | DESCRIPTION OF WORK | VALUE | APPS. | PERIOD | STORED | TO DATE | % | TOPINION | KLIAMAGE |
| | HVAC | | | | | | | | |
| | HV121 2nd fl A | | 2,222,22 | | 1 | 3.000.00 | 100% | 0.00 | 0.0 |
| | Materials | 3,000.00 | 3,000.00 | | | 2,000.00 | 100% | 0.00 | 80.0 |
| | Labor | 2,000.00 | 2,000.00 | | | 0.00 | 10076 | 0.00 | 0.0 |
| | HV122 2nd Fl B (no Gym) | 1.000 | | | | 4.800.00 | 100% | 0.00 | 0.0 |
| | Materials | 4,800.00 | 4,800.00 | | | 3,200.00 | 100% | 0.00 | 128.0 |
| | Labor | 3,200.00 | 3,200.00 | | | 0.00 | ,00,0 | 0.00 | 0.0 |
| | HV123 2nd FI C | 7 | 4 500 00 | | | 4,800.00 | 100% | 0.00 | 0.0 |
| | Materials | 4,800.00 | 4,800.00 | 13 | | 3,200.00 | 100% | 0.00 | 128.0 |
| - 1 | Labor | 3,200.00 | 3,200.00 | | | 0.00 | 100.0 | 0.00 | 0.0 |
| | HV131 Attic A | | 0.000.00 | | 1 | 3,000.00 | 100% | 0.00 | 0.0 |
| 1 | Materials | 3,000.00 | 3,000.00 | | | 2,000.00 | 100% | 0.00 | 80.0 |
| | Labor | 2,000.00 | 2,000.00 | | | 0.00 | 10070 | 0.00 | 0.0 |
| | HV132 Attic B | 0.000 | 0.000.00 | 1 | | 3,000.00 | 100% | 0.00 | 0.0 |
| | Materials | 3,000.00 | 3,000.00 | 9 | | 2,000.00 | 100% | 0.00 | 80.0 |
| - 13 | Labor | 2,000.00 | 2,000.00 | 11 | | 0.00 | 100% | 0.00 | 0.0 |
| | HV133 Attic C | | -200 | | | 7,800.00 | 100% | 0.00 | 0.0 |
| | Materials | 7,800.00 | 7,800.00 | 13 | | 5,200.00 | 100% | 0.00 | 208.0 |
| | Labor | 5,200.00 | 5,200.00 | | | 0.00 | 100% | 0.00 | 0.0 |
| | HV401 Boiler Room | | 47.73.74 | | | 12,000.00 | 100% | 0.00 | 0.0 |
| | Materials | 12,000.00 | 12,000.00 | | | 8,000.00 | 100% | 0.00 | 320. |
| | Labor | 8,000.00 | 8,000.00 | | | 0.00 | 10076 | 0.00 | 0.0 |
| | HV122 Gym | | 0.222.52 | | | 4.800.00 | 100% | 0.00 | 0.0 |
| | Materials | 4,800.00 | 4,800.00 | | | 3,200.00 | 100% | 0.00 | 128.0 |
| | Labor | 3,200.00 | 3,200.00 | | | 0.00 | 10075 | 0.00 | 0.0 |
| | | | | | | 0.00 | | 0.00 | . 0.0 |
| | Temperature Controls | 100000000000000000000000000000000000000 | 72 32-22 | | | 13,485.00 | 100% | 0.00 | 0.0 |
| | Materials | 13,485.00 | 13,485.00 | | [| 76,415.00 | 100% | 0.00 | 3,056.6 |
| | Labor | 76,415.00 | 76,415.00 | | h I I I I | 0.00 | 10070 | 0.00 | 0.0 |
| | Mechanical - Materials | 1000000 | 44.000.00 | b 1/4 | 1,1 | 11,326.00 | 100% | 0.00 | 0.0 |
| | Pumps & Hydronic Accessories | 11,326.00 | 11,326.00 | | | 10,100.00 | 100% | 0.00 | 0.0 |
| | Water Treatment & Glycol | 10,100.00 | 10,100.00 | | | 22,400.00 | 100% | 0.00 | 0.0 |
| | Ductless Splits Systems | 22,400.00 | 22,400.00 | | } | 10,500.00 | 100% | 0.00 | 0.0 |
| | Terminal Units (BB,UH.FC) | 10,500.00 | 10,500.00 | | | 5,490.00 | 100% | 0.00 | 0.0 |
| | Pipe Valves Fittings HP101 | 5,490.00 | 5,490.00 | | 6 | 16,900.00 | 100% | 0.00 | 0.0 |
| | Pipe Valves Fittings HP102 | 16,900.00 | 16,900.00 | | (5) | 25,500.00 | 100% | 0.00 | 0.0 |
| | Pipe Valves Fittings HP103 | 25,500.00 | 25,500.00 | | | 10,800.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP111 | 10,800.00 | 10,800.00 | | | 23,300.00 | 100% | 0.00 | 0.0 |
| | Pipe Valves Fittings HP112 | 23,300.00 | 23,300.00 | | | 31,012.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP113 | 31,012.00 | 31,012.00 | | | 6,600.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP121 | 6,600.00 | 6,600.00 | | | 11,600.00 | 100% | 0.00 | 0.0 |
| | Pipe Valves Fittings HP122 | 11,600.00 | 11,600.00 | | | 6,700.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP123 | 6,700.00 | 6,700.00 | 1 | | 8,300.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP131 | 8,300.00 | 8,300.00 | | | 11,900.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP132 | 11,900.00 | 11,900.00 | | | 8,700.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP133 | 8,700.00 | 8,700.00 | | | 38,194.00 | 100% | 0.00 | 0. |
| | Pipe Valves Fittings HP401 | 38,194.00 | 38,194.00 | | | 00,101.00 | | | · w |
| _ | The state of the s | | 20.00.00.00 | A1341 | | 404 000 00 | ***** | 0.00 | 4,208. |
| | Total , Page 5 | 421,222.00 | 421,222.00 | 0.00 | 0.00 | 421,222.00 | 100% | 0.00 | 7,200. |

| | BP#7a HVAC | Toronto de la Cal | | OMPLETED | MATERIALS PRESENTLY | TOTAL COMPLETED & STORED | | BALANCE | 4% |
|------|---|-------------------|-----------------------|----------------|------------------------|--------------------------|-----------|-----------|-----------|
| TEM | Administration of Constitution | SCHEDULED | PREVIOUS APPS. | THIS PERIOD | STORED | TO DATE | % | TO FINISH | RETAINAGE |
| MBER | DESCRIPTION OF WORK | VALUE | APPS. | PERIOD | STORED | 100 | | | |
| | HVAC | | | | | | | | |
| | Mechanical - Labor | 2 200 00 | 6,600.00 | | | 6,600.00 | 100% | 0.00 | 264.0 |
| | Pumps & Hydronic Accessories | 6,600.00 | 1,100.00 | | | 1,100.00 | 100% | 0.00 | 44.0 |
| | Water Treatment | 1,100.00 | 5,500.00 | | | 5,500.00 | 100% | 0.00 | 220.0 |
| | Ductless Splits Systems | 5,500.00 | | | | 6,800.00 | 100% | 0.00 | 272.0 |
| | Terminal Units (BB,UH.FC) | 6,800.00 | 6,800.00 3,300.00 | | | 3,300.00 | 100% | 0.00 | 132.0 |
| | Pipe Valves Fittings HP101 | 3,300.00 | 6,800.00 | | | 6,800.00 | 100% | 0.00 | 272.0 |
| | Pipe Valves Fittings HP102 | 6,800.00 | 8,800.00 | | | 8,800.00 | 100% | 0.00 | 352.0 |
| | Pipe Valves Fittings HP103 | 8,800.00 | 5,500.00 | | | 5,500.00 | 100% | 0.00 | 220.0 |
| | Pipe Valves Fittings HP111 | 5,500.00 | 9,800.00 | | | 9,800.00 | 100% | 0.00 | 392.0 |
| | Pipe Valves Fittings HP112 | 9,800.00 | | | | 11,500.00 | 100% | 0.00 | 460.0 |
| | Pipe Valves Fittings HP113 | 11,500.00 | 11,500.00 | | | 6,600.00 | 100% | 0.00 | 264.0 |
| | Pipe Valves Fittings HP121 | 6,600.00 | 6,600.00 | | | 4,400.00 | 100% | 0.00 | 176.0 |
| | Pipe Valves Fittings HP122 | 4,400.00 | 4,400.00 | | | 4,400.00 | 100% | 0.00 | 176.0 |
| | Pipe Valves Fittings HP123 | 4,400.00 | 4,400.00 | 1 | | 6,600.00 | 100% | 0.00 | 264.0 |
| | Pipe Valves Fittings HP131 | 6,600.00 | 6,600.00 | | | 8,800.00 | 100% | 0.00 | 352.0 |
| | Pipe Valves Fittings HP132 | 8,800.00 | 8,800.00 | 1 | | 6,600.00 | 100% | 0.00 | 264.0 |
| | Pipe Valves Fittings HP133 | 6,600.00 | 6,600.00 19,400.00 | | | 19,400.00 | 100% | 0.00 | 776.0 |
| | Pipe Valves Fittings HP401 | 19,400.00 | | | | 27,500.00 | 100% | 0.00 | 120.5 |
| | Demolition | 27,500.00 | 27,500.00 | | | 12,000.00 | 100% | 0.00 | 480.0 |
| | Install Owner Furnished Equipment | 12,000.00 | 12,000.00 | | | 0.00 | | 0.00 | 0.0 |
| | Allowances | 40,000,00 | 40,000,00 | | | 10,000.00 | 100% | 0.00 | 400.0 |
| | General Allowance | 10,000.00 | 10,000.00 | 25,000.00 | | 25,000.00 | 100% | 0.00 | 1,000.0 |
| | Dehimidification Allowance | 25,000.00 | | 25,000.00 | | 0.00 | 155.0 | 0.00 | 0.0 |
| | Change Orders: | | 405 000 00 | 1.5 | | 195,289.00 | 100% | 0.00 | 7,811.56 |
| | 001, dated 09/03/09 thru 18 various dates | 195,289.00 | 195,289.00 | | | 150,200.00 | 100.0 | 0.00 | 0.00 |
| | | 0.070.00 | 3,872.00 | | | 3,872.00 | 100% | 0.00 | 154.88 |
| | 019, dated 09/29/10 | 3,872.00 | 649.00 | | | 649.00 | 100% | 0.00 | 25.96 |
| | 020, dated 11/4/10 | 649.00 | 4,292.00 | Y. 1 | | 4,292.00 | 100% | 0.00 | 171.6 |
| | 021, dated 11/17/10 | 4,292.00 | 8,343.00 | 1 | | 8,343.00 | 100% | 0.00 | 333.7 |
| | 022, dated 11/17/10 | 8,343.00 | 8,343.00 | | | 0.00 | #DIV/0! | 0.00 | 0.0 |
| | | | | 5,064.00 | | 5,064.00 | 100% | 0.00 | 202.5 |
| | 023, dated 12/13/10 | 5,064.00 | 1 | 2,297.00 | | 2,297.00 | 100% | 0.00 | 91.8 |
| | 024, dated 12/13/10 | 2,297.00 | | 1,017.00 | | 1,017.00 | 100% | 0.00 | 40.6 |
| | 025, dated 01/13/11 | 1,017.00 | | 2,900.00 | | 2,900.00 | 100% | 0.00 | 116.0 |
| | 026, dated 01/13/11 | 2,900.00 | | 2,707.00 | | 2,707.00 | 100% | 0.00 | 108.2 |
| | 027, dated 01/13/11 | 2,707.00 | | (25,000.00) | | (25,000.00) | 100% | 0.00 | (1,000.0 |
| | 028, dated 01/13/11 | (25,000.00) | | 725.00 | | 725.00 | 100% | 0.00 | 29.0 |
| | 029, dated 03/03/11 | 725.00 | | 2,421.00 | | 2,421.00 | 100% | 0.00 | 96.8 |
| | 030, dated 03/03/11 | 2,421.00 | | 5,417.00 | | 5,417.00 | 100% | 0.00 | 216.6 |
| | 031, dated 03/03/11 | 5,417.00 | | 3,417.00 | | 3.00 | 1 100,000 | 0.00 | 0.0 |
| | | | | | | | | 0.00 | 0.0 |
| | | | | | | | | 0.00 | 0.0 |
| | | 1 | | | | | | 0.00 | 0.0 |
| | | 1 | | | | | | 0.00 | 0.0 |
| | | | | | | | | 0.00 | 0.0 |
| | | | | | | | | | AF 000 5 |
| | total page 6 | 406,993.00 | 384,445.00 | 22,548.00 | 0.00 | 406,993.00 | | 0.00 | 15,300.2 |
| | GRAND TOTAL | 1,421,993.00 | 1,399,445.00 | 22,548.00 | 0.00 | 1,421,993.00 | 100% | 0.00 | 37,725.6 |

State of Kentucky

County of Kenton

ss Covington, Kentucky

March 15, 2011

Invoice #138122

VICENTE SALAZAR, being first duly sworn, says that he is PRESIDENT of Blau Mechanical, Inc. the contractor having a contract with, the owner Cincinnati Public Schools, for HVAC work at Hartwell Elementary School, a project situated on or around or in front of the following described property, in Hamilton County, Ohio via:

8320 Vine Street

Cincinnati, Ohio 45216

whereof Cincinnati Public Schools was the owner.

Sub-Contractors

Affiant further says that the following shows the name and addresses of every sub-contractor in the employ of said **BLAU MECHANICAL**, **INC** giving the amount, if any, which is due, or to become due, to them, or any of them, for work done, or machinery, material or fuel furnished to date hereof, under said contracts.

| Name | Address | Trade | Amount | | |
|-------------------------|----------------|------------|--------|------|--|
| Jacobs Mechanical | Cincinnati, OH | Duct Work | \$ | 0.00 | |
| Habegger Corporation | Cincinnati, OH | Controls | \$ | 0.00 | |
| Priority III Insulation | Cincinnati, OH | Insulation | \$ | 0.00 | |

Material Men

Said affiant further says that the following shows the names and address of every person furnishing machinery, material or fuel to **BLAU MECHANICAL INC**, giving the amount, if any, which is due, to them, or any of them for machinery, material or fuel furnished to date hereof, under said contracts.

Name

Address

Material

Amount

NONE

Labor

..... EVERY LABORER HAS BEEN PAI D IN FULL

Said affiant further says that the following shows the names and addresses of every unpaid laborer in the employ of **BLAU MECHANICAL.INC**. furnishing labor under said contract, giving the amount, if any, which is due, or become due, for labor to date hereof.

Amount

Affiant further states that there is due or to become due to BLAU MECHANICAL, INC. for work performed or machinery, material or fuel furnished to Cincinnati Public Schools to date hereof under said contracts, the sum of \$8,220.48.

That the amounts due or to become due to said sub-contractor, material-men and laborers, for work done or machinery, material or fuel furnished to the date hereof to **BLAU MECHANICAL**, **INC**. are fully and correctly set forth opposite their names, respectively, in the aforesaid statements, and further evidenced by certificates of every person furnishing machinery, material or fuel, hereto attached, and made a part hereof.

Affiant further says that **BLAU MECHANICAL**, **INC**. has not employed or procured machinery, material or fuel from, or sub-contracted with any person ,firm or corporation, other than those above mentioned, and owes for no labor performed, or machinery, material or fuel furnished, under said contracts, other that above set forth.

VICENTE SALAZAR, PRESIDENT

SWORN TO BEFORE ME AND SUBSCRIBED IN MY PRESCENCE, AT COVINGTON, KY

THIS 15 DAY OF MARCH, 2011 .

Notary Public

KIMBERLY ANN BRUNGS Notary Public, Kentucky State at Large My Commission Expires July 21, 2012

Form44

HEAT RECOVERY WHEEL SAVINGS SUMMARY

| | AHU-1 | AHU-2 | TOTAL |
|----------|-------------|-------------|-------------|
| kWh: | 26,945.5 | 25,034.6 | 51,980.0 |
| Dollars: | \$ 2,155.64 | \$ 2,002.76 | \$ 4,158.40 |
| 75% | \$ 1,616.73 | \$ 1,502.07 | \$ 3,118.80 |



90.1 (2004) Standard

Section 1: Project Information

Project Type: New Construction

Project Title:

Construction Site: Owner/Agent: Designer/Contractor:

Section 2: Interior Lighting and Power Calculation

| | Α | B Floor Area | C Allowed Watts / ft2 | D Allowed Watts |
|-------------------|---|-----------------|-----------------------------|--------------------|
| School/University | | 70209 | 1.2 | 84251 |
| | | Tot | al Allowed Watts = | 84251 |

Section 3: Interior Lighting Fixture Schedule

| A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast | B Lamps/ Fixture | C # of Fixtures | D Fixture Watt. | (C X D) |
|--|------------------------|-----------------------|-----------------------|---------|
| School/University (70209 sq.ft.) | | | | |
| Linear Fluorescent 1: A1: 48" T8 32W (Super T8) / Electronic | 2 | 68 | 59 | 4012 |
| Linear Fluorescent 2: A2: 48" T8 32W (Super T8) / Electronic | 2 | 37 | 58 | 2146 |
| Linear Fluorescent 3: A31: 48" T8 32W / Electronic | 3 | 17 | 84 | 1428 |
| Linear Fluorescent 4: B24: 48" T8 32W / Electronic | 2 | 4 | 63 | 252 |
| Linear Fluorescent 5: B28: 48" T8 32W / Electronic | 2 | 55 | 126 | 6930 |
| Linear Fluorescent 6: B34: 48" T8 32W / Electronic | 3 | 18 | 97 | 1746 |
| Linear Fluorescent 7: B38: 48" T8 32W / Electronic | 3 | 150 | 194 | 29100 |
| Linear Fluorescent 8: C31: 48" T8 32W / Electronic | 3 | 22 | 91 | 2002 |
| Linear Fluorescent 9: C32: 48" T8 32W / Electronic | 3 | 20 | 91 | 1820 |
| Linear Fluorescent 10: D5: 48" T8 32W / Electronic | 2 | 13 | 63 | 819 |
| Linear Fluorescent 11: D7: 48" T8 32W / Electronic | 2 | 7 | 63 | 441 |
| Linear Fluorescent 12: G3: 48" T8 32W / Electronic | 3 | 13 | 87 | 1131 |
| Linear Fluorescent 13: J31: 48" T8 32W / Electronic | 3 | 82 | 91 | 7462 |
| Linear Fluorescent 14: J32: 48" T8 32W / Electronic | 3 | 6 | 91 | 546 |
| Linear Fluorescent 15: K: 48" T8 32W / Electronic | 2 | 21 | 63 | 1323 |
| Linear Fluorescent 16: K4: 48" T8 32W / Electronic | 2 | 22 | 74 | 1628 |
| Linear Fluorescent 17: K8: 48" T8 32W / Electronic | 2 | 39 | 74 | 2886 |
| Linear Fluorescent 18: L14: 48" T8 32W / Electronic | 1 | 10 | 34 | 340 |
| Compact Fluorescent 1: PS2: Triple 4-pin 32W / Electronic | 2 | 18 | 64 | 1152 |
| Compact Fluorescent 2: PS3: Twin Tube 24/26/27W / Electronic | 4 | 10 | 100 | 1000 |
| Compact Fluorescent 3: S1: Triple 4-pin 32W / Electronic | 1 | 2 | 36 | 72 |
| Compact Fluorescent 4: XBA: Triple 4-pin 42W / Electronic | 8 | 23 | 372 | 8556 |

Total Proposed Watts = 76792

Section 4: Requirements Checklist

Lighting Wattage:

■ 1. Total proposed watts must be less than or equal to total allowed watts.


Project Title: Report date: 05/17/12

| _ 0 Fuit sings | Allowed Watts 84251 | Proposed Watts 76792 | Complies YES | | |
|-------------------|--|-------------------------|--|--|-------|
| 2. Exit signs | s 5 Watts or less per s | ign. | | | |
| Controls, | Switching, and | Wiring: | | | |
| _ | | | or each space (remote switch meeting rooms, and employe | with indicator allowed for safety or security). ee lunch and break rooms. | |
| Exception | ns: | | | | |
| | | | · | preschool through 12th grade classrooms. occupant sensor, or other automatic control. | |
| Exception | ns: | | | | |
| - | | | re auto shutoff would endang | ger safety or security. | |
| _ | witch at entry to hotel/i control device for disp | | se lighting, task lighting, nonv | visual lighting, lighting for sale, and demonstra | ation |
| 3. Tandem | wired one-lamp and th | ree-lamp ballasted lum | inaires (No single-lamp balla | sts). | |
| Exception | ns: | | | | |
| ☐ Electr | onic high-frequency b | allasts. | | | |
| Lumir | naires not on same sw | itch. | | | |
| ☐ Reces | ssed luminaires 10 ft. | apart or surface/pendar | nt not continuous. | | |
| Lumir | naires on emergency o | ircuits. | | | |
| _ | onductors have been | | m voltage drop of 2 percent. | reent | |
| _ | | | aximum voltage drop of 3 pe | rcent. | |
| Interior Lightin | g PASSES: Design 9 ^o | % better than code. | | | İ |
| Section 5: | Compliance | Statement | | | |
| other calculation | ns submitted with this | permit application. The | proposed lighting system has | nsistent with the building plans, specifications is been designed to meet the 90.1 (2004) Stars in the Requirements Checklist. | |
| Name - Title | | | Signature | | |
| Section 5: | Post Constru | ıction Complia | nce Statement | | |
| Record D | rawings and Ope | erating and Maint | enance Manuals: | | |
| 1. Construc | tion documents with re | ecord drawings and ope | erating and maintenance mar | nuals provided to the owner. | |
| Lighting Design | ner or Contractor Nam | е | Signature | Date | |

Project Title: Report date: 05/17/12 Data filename: C:\Dropbox\Rebate Projects\Cinci Public\7. 09 and 10 new schools\Hartwell\Submission\Support\Hartwell.COMCheck.cck Page



WI-200 Passive Infrared Wall Switch Sensor



Product Overview

Description

The WI-200 is a passive infrared wall switch that turns lighting systems on and off based on occupancy and ambient light levels. The WI-200 replaces an existing wall switch with a quick and easy installation and operates at 120 or 277 VAC.

Operation

The WI-200 uses advanced passive infrared technology to detect occupancy. The sensors detect the difference between the infrared energy from a human body in motion and the background space. For manual-ON, occupants press the auto/OFF button on the face of the unit. Once the space is vacated and the user-set time delay elapses, lights turn off. A reset delay allows the sensor 30 seconds to detect occupancy and turn lights back on automatically. With auto-ON set, lights automatically turn on when occupants enter the controlled area. Once the space is vacated and the user-set time delay elapses, lights automatically turn off.

Features

- ASIC technology reduces components and enhances reliability
- Pulse Count Processing eliminates false offs without reducing sensitivity
- Detection Signature Analysis eliminates false triggers; provides immunity to RFI and EMI
- Zero crossing circuitry reduces stress on the relay and results in increased sensor life
- Choice of Manual-ON or Auto-ON operation for increased flexibility

Light Level Sensing

A built-in light level sensor provides increased energy savings in areas with abundant natural light. This feature holds lighting OFF if a user-specified level of ambient light already exists. A user can simply bypass this feature by placing his hand over the sensor for a second.

Applications

The WI-200's great coverage, ease of installation, and full-featured options ranging from ON mode operation to built-in light level sensing add up to great energy savings and return on investment. Its convenience and reliability provide satisfaction at all levels – especially to the occupants. These sensors work well in many enclosed building spaces including offices, utility rooms, and small conference rooms.

- Time delay adjustment from 15 seconds to 30 minutes
- DIP switch adjustments for ON-mode operation, time delay, sensitivity, and light level control
- Four-level patented Fresnel lens provides superior desktop detection
- Patented voltage drop protection
- For safety, there is no leakage to load in the OFF mode and sensor is safety grounded
- Units are tamper resistant
- LED indicates occupancy detection




S

Specifications


- Dual 120/277 VAC
- Coverage of 180 degrees, maximum 1000 ft² (92.9 m²), 500 ft² (46.5 m²) for desktop activity
- Digital time delay adjustable from 15 seconds to 30 minutes
- Built-in light level sensor, works from 10 to 150 footcandles (107 to 1,614 lux)
- Compatible with all electronic ballasts and PL lamp ballast systems
- Dimensions: 2.8" x 4.8" x 1.5"
 [71.1mm x 121.9mm x 38.1mm]
- UL and CUL listed; 5 year warranty

Controls & Installation

Product Controls




Installation




Wiring

Single Level Wiring




Manual Bi-level Lighting



Coverage & Settings

Coverage



DIP Switch Settings

| DIP Switch # | 1 | 2 | 3 | 4 | | | # | 5 | 6 | 7 |
|--------------|---|---|---|---|---|----|-------------|------|---|----|
| Time Delays | | | | | | | Light Level | | | |
| 15 seconds | Χ | Χ | Χ | Χ | | | _ow (-10FC) | 0 | 0 | 0 |
| 2 minutes | Χ | Χ | Χ | 0 | | | ium (-50FC) | X | 0 | 0 |
| 4 minutes | Χ | Χ | 0 | Χ | | Hi | | X Z | X | 0 |
| 6 minutes | Χ | Χ | 0 | 0 | | | Override | X . | X | X |
| 8 minutes | Χ | 0 | Χ | Χ | | | | | # | 8 |
| 10 minutes | Х | 0 | Х | 0 | | | Sensit | ivit | y | |
| 12 minutes | Χ | 0 | 0 | Χ | | L | H | ligh | | Χ |
| 14 minutes | Χ | 0 | 0 | 0 | | L | l | _OW | 1 | 0 |
| 16 minutes | 0 | Χ | Χ | Χ | | | | | # | 9 |
| 18 minutes | 0 | Χ | Χ | 0 | | | Mo | ode | | |
| 20 minutes | 0 | X | 0 | Χ | • | L | Manual | | | Х |
| 22 minutes | 0 | Χ | 0 | 0 | | L | Automatic | On | | 0 |
| 24 minutes | 0 | 0 | Х | Χ | | | | 7 | # | 10 |
| 26 minutes | 0 | 0 | Χ | 0 | | | Overr | | | |
| 28 minutes | 0 | 0 | 0 | Χ | | L | Nor | | | 0 |
| 30 minutes | 0 | 0 | 0 | 0 | | L | Overi | ride | | Χ |
| | | | | | | | | | | |

X=On O=Off ◆=Factory Presets

| S | oide Vi | ew | | | |
|----------------|---------|--------------|---------------|---------------|----------------|
| 4.0' (1.2m) | floor | 30° | 12° | 5° | 0° |
| | | 7' (2.1m) | 19' (5.8m) | 30' (9.1m) | 40' (12.2m) |

Ordering Information

| Catalog No. | Color | Voltage | Load Requirement | Coverage |
|-------------|------------|----------------|---------------------|--------------------------|
| ☐ WI-200-W | White | 120 VAC; 60 Hz | 0-800 Watt Ballast | 180°, 1000 ft² (92.9 m²) |
| | | or | or | |
| ☐ WI-200-A | Lt. Almond | 277 VAC; 60 Hz | 0-1200 Watt Ballast | |

Pub. No. 4508

Order ASP-121 for blank cover plate for 2-gang box; Order ASP-122 for cover plate for 2-gang box with switch option.



Ceiling and Wall Mount Occupancy Sensors

LightOWLTM Dual Technology Ultrasonic and PIR Sensor featuring IntelliDAPT®

KEY FEATURES

- IntelliDAPT self-adaptive technology—no manual adjustment required
- All-digital dual technology (ultrasonic [US] and passive infrared [PIR]) sensor
- Non-volatile memory for sensor settings
- 1,600 square-foot coverage area
- · Optional relay and photocell control
- Optional Quick to Install (QTI) connector
- UL and cUL listed
- California Title 24 compliant
- Five-year warranty



OVERVIEW

The LODT combines ultrasonic (US) and passive infrared (PIR) technologies to turn lighting on and off based on occupancy. Designed specifically for areas where ceiling sensors are not appropriate, this sensor features Hubbell Building Automation's patented IntelliDAPT technology, which makes all the sensor adjustments automatically. Throughout the product's lifespan, smart software analyzes the controlled area and makes digital adjustments to sensitivity and timer settings. Occupancy sensors with IntelliDAPT provide a maintenance-free install-and-forget operation.

FEATURES and BENEFITS

| Features | Benefits |
|--|---|
| IntelliDAPT technology | Sensor automatically determines optimum setting for an area |
| J. | Excellent false trip immunity (for improved accuracy) |
| | No manual sensitivity or timer adjustments required |
| | Provides a maintenance-free install-and-forget operation |
| All-Digital, multi-technology (ultrasonic [US] and passive | Superior US minor-motion detection with excellent PIR long- |
| infrared [PIR]) sensor | range major-motion detection |
| Non-volatile memory for sensor settings | Learned and adjusted settings will not be lost during power |
| | outages |
| Optional relay and photocell control | Easy integration with Building Automation Systems |
| | Increases energy savings by preventing lights from turning on |
| | when there is sufficient natural light |
| Optional Quick-to-Install (QTI) connector | · Dramatically reduces installation costs by removing the time- |
| | consuming process of manually wiring a sensor to a power |
| | pack |
| | Easy to install; fast and efficient; no cutting, stripping, |
| | or wire nuts required |

APPLICATIONS

- Offices
- Small conference rooms
- Break rooms

SPECIFICATIONS


| SPECIFICATIONS | |
|------------------------|--|
| IntelliDAPT technology | Auto reset from test setting |
| | Self-adjusting timer |
| | Self-adjusting ultrasonic and passive infrared thresholds |
| | Automatic false-on/false-off corrections |
| LED lamps | Red – infrared motion |
| · | Green – ultrasonic motion |
| Timer timeout | Automatic mode: 8–30 minutes (self-adjusts based on |
| | occupancy) |
| I II(| Test mode: 8 seconds (for an easy check at installation) |
| Ultrasonic (US) output | Operating frequency: 32kHz |
| RP option | Relay and photocell included Relay 200 A 200 |
| | Relay: N/O + N/C contacts; SPDT; 500 mA rated @ 24 VDC; three-wire isolated relay |
| | Photocell: adjustable natural-light override ranges from 0 to |
| | 100 foot-candles (0–1,000 lux) |
| | Factory set at 3,000 lux (disable photocell) |
| Coverage | • 1,600 square feet |
| Power requirements | • 24 VDC, 33 mA (uses UVPP and MP-Series power pack—not |
| | included) |
| Output | 24 VDC active high-logic control signal with short circuit |
| · | protection and optional dry contact (see: RP Option) |
| Operating environment | Indoor use only |
| | Operating temperature: 32° –104°F (0°–40°C) |
| | Relative humidity (non-condensing): 0%–95% |
| Construction | Casing—rugged, high-impact, injection-molded plastic KJB ABS |
| | Cycolac (UL-945VA) |
| | Color-coded leads are 6" long |
| Size and weight | • Size: 6.58" x 3.63" x 3.72" |
| | Weight: 5.0 oz (142g) |
| Color | Off-white |
| Mounting | Mounting base provided |
| - | Recommended MAX mounting height: 12ft. |
| Certifications | UL and cUL listed |
| Warranty | Five years |
| | |

ORDERING INFORMATION

| Catalog Number | Description | Color | Coverage | | |
|----------------|--|-----------|---------------|--|--|
| LODT | Ultrasonic and Passive Infrared Wall and Ceiling Sensor with IntelliDAPT | Off-white | 1,600 sq. ft. | | |
| LODTRP | Ultrasonic and Passive Infrared Wall and Ceiling Sensor with IntelliDAPT | | | | |
| | (Relay and Photocell) | Off-white | 1,600 sq. ft. | | |

^{*}Add QTI to end of catalog number for optional Quick To Install connector

RANGE DIAGRAM







Ceiling and Wall Mount Occupancy Sensors

OMNITM Ultrasonic Ceiling Sensor featuring IntelliDAPT®

KEY FEATURES

- IntelliDAPT self-adaptive technology—no manual adjustment required
- All-digital ultrasonic (US) technology
- Non-volatile memory for sensor settings
- 500-2,000 square-foot coverage area (depending on model)
- · Optional relay and photocell control
- Optional Quick-to-Install (QTI) connector
- UL and cUL listed
- California Title 24 compliant
- Five-year warranty



OMNIUS500

OVERVIEW

The OMNIUS uses ultrasonic (US) technology to turn lighting on and off based on occupancy. Designed specifically for both areas with obstructions (e.g. columns, cubicles, stalls, and filing cabinets) and areas with long periods of minor-motion activity (e.g. typing), this sensor features Hubbell Building Automation's patented IntelliDAPT technology, which makes all the sensor adjustments automatically. Throughout the product's lifespan, smart software analyzes the controlled area and makes digital adjustments to sensitivity and timer settings. Occupancy sensors with IntelliDAPT provide a maintenance-free install-and-forget operation.

FEATURES and BENEFITS

| Features | Benefits | | |
|---|---|--|--|
| IntelliDAPT technology | Sensor automatically determines the ideal setting for an area Excellent false trip immunity (for improved accuracy) | | |
| | No manual sensitivity and timer adjustments required | | |
| | Provides a maintenance-free install-and-forget operation. | | |
| All-digital ultrasonic (US) sensor | Superior US minor-motion detection | | |
| Non-volatile memory for sensor settings | Learned and adjusted settings will not be lost during power outages | | |
| Optional relay and photocell control | Easy integration with Building Automation Systems Increases energy savings by preventing lights from turning on when there is sufficient natural light | | |
| Optional Quick-to-Install (QTI) connector | Dramatically reduces installation costs by removing the time-consuming process of manually wiring a sensor to a power pack Easy to install; fast and efficient; no cutting, stripping, | | |
| | or wire nuts required | | |

APPLICATIONS

- Hallways
- Restrooms


SPECIFICATIONS

| SPECIFICATIONS | |
|------------------------|---|
| IntelliDAPT | Auto reset from test setting |
| | Self-adjusting timer |
| | Self-adjusting ultrasonic thresholds |
| | Automatic false-on/false-off corrections |
| LED lamp | Green—ultrasonic motion |
| Timer timeout | Automatic mode: 8–30 min. (self-adjusts based on occupancy) |
| | Test mode: 8 seconds (for an easy check at installation) |
| Ultrasonic (US) output | OMNIUS500: 40kHz output |
| ` , , | OMNIUS1000 and OMNIUS2000: 32kHz output |
| RP option | Relay and photocell included |
| · | Relay: N/O + N/C contacts; SPDT; 500 mA rated @ 24VDC; |
| | three-wire isolated relay |
| | Photocell: adjustable natural-light override ranges from 0 to |
| | 100 foot-candles (0–1,000 lux) |
| Coverage | • 500–2,000 square feet (depending on model) |
| Power requirements | 24 VDC, 33 mA (uses UVPP and MP-Series power pack—not |
| | included) |
| Output | 24 VDC active high-logic control signal with short circuit |
| | protection and optional dry contact (see: RP Option) |
| Operating environment | Indoor use only |
| | Operating temperature: 32°-104°F (0°-40°C) |
| | Relative humidity (non-condensing): 0%–95% |
| Construction | Casing—rugged, high-impact, injection-molded plastic KJB ABS |
| | Cycolac (UL-945VA) flame class rating, UV inhibitors |
| | Color-coded leads are 6" long |
| Size and weight | Size: 4.5" diameter, 1.5" height (114 mm diameter, 38mm |
| | height) |
| | Weight: 5.0 oz (142g) |
| Color | Off-white |
| Mounting | Mounting base provided |
| | Recommended MAX mounting height: 12ft. |
| Certifications | UL and cUL listed |
| Warranty | Five years |
| | |


HOW TO ORDER

| Catalog Number | Description | Color | Coverage | |
|--|--|-----------|---------------|--|
| OMNIUS500 | Ultrasonic Ceiling Mount Sensor with IntelliDAPT | Off-white | 500 sq. ft. | |
| OMNIUS500RP | Ultrasonic Ceiling Mount Sensor with IntelliDAPT (Relay and Photocell) | Off-white | 500 sq. ft. | |
| OMNIUS I 000 | Ultrasonic Ceiling Mount Sensor with IntelliDAPT | Off-white | 1,000 sq. ft. | |
| OMNIUS I 000RP | Ultrasonic Ceiling Mount Sensor with IntelliDAPT (Relay and Photocell) | Off-white | 1,000 sq. ft. | |
| OMNIUS2000 | Ultrasonic Ceiling Mount Sensor with IntelliDAPT | Off-white | 2000 sq. ft. | |
| OMNIUS2000RP | Ultrasonic Ceiling Mount Sensor with IntelliDAPT (Relay and Photocell) | Off-white | 2000 sq. ft. | |
| *Add QTI to end of catalog number for optional Quick-to-Install connector. | | | | |

RANGE DIAGRAMS







OMNIUS2000 Range Diagram



Hubbell Building Automation, Inc.
9601 Dessau Road | Building One | Austin, Texas 78754
{512} 450-1100 | {512} 450-1215 fax
hubbell-automation.com

OMNI-DT/OMNI-DT-RP (Option RP)

Dual Technology Ceiling Mount Sensor

KEY FEATURES

- INTELLIGENT Continuously Adapting sensor.
- · Ultrasonic & Infrared Sensing
- · Simple, Fast Installation
- · Snap-Lock Sensor, Ceiling Mounting
- Excellent false tripping immunity
- Non-Volatile Memory: settings saved in protected memory are not lost during power outages.
- Optional Photocell Control and Relay
- 500 to 2000 sq. ft. mounted at 8'
- Multiple Sensor and Power Pack Connections
- 24VDC, Class 2 low voltage wiring
- · Designed & Manufactured in USA



Occupancy sensors have two tasks; keeping the lights on while the room is occupied and keeping the lights off when unoccupied. Hubbell Building Automation's intelligent, continuously adapting sensor technology eliminates manual sensitivity and timer adjustments during installation and over the life of the product. The self-adapting microprocessor constantly assures maintenance free "Install and Forget" operation.

The OMNI-DT is a ceiling mount occupancy sensor that combines both ultrasonic (US) and passive infrared (PIR) sensing. Hubbell Building Automation's self-adapting OMNI-DT addresses areas with complex environments that are difficult to control with single technology sensors. The internal microprocessor analyzes the information from both the US and PIR technologies and determines the optimum setting to use in order to properly cover the space. The automatic timer and automatic sensitivity features of the Omni-DT work independently to prevent "false-offs" and

The OMNI-DT is the sensor replacement combining both the superior minor motion detection of ultrasonic with the excellent long-range major motion detection of passive infrared.



"false-ons." When the sensor detects motion immediately after it turns the lights out, a "false-off" is detected, timer and sensitivity are increased. If the sensor turns the lights on, but detects no immediate follow-up motion, "false-on" is detected, timer and sensitivity are decreased. The "Intelligent software" algorithm determines, for example, if the lights are staying on due to adjacent hallway traffic and responds by adapting its program to compensate for the false trigger and turns out the lights. The OMNI-DT is the sensor replacement combining both the superior minor motion detection of ultrasonic with the excellent long-range major motion detection of passive infrared.

In addition, the OMNI-DT has an optional photocell, which increases energy savings when engaged by preventing the lights from turning on when there is sufficient natural light. This feature is factory disabled and may be activated by the installer.

Designed specifically to meet the challenges found in rooms where tasks entail minor motion for long periods of time. Ultrasonic (doppler shift) motion detection gives maximum sensitivity yet can be vulnerable to false triggering from air conditioning currents, corridor activity and movement of inanimate objects. Infrared motion detection gives immunity to these false triggers, but lacks sensitivity at greater distances. Hubbell Building Automation's intelligent software reads the environment and adapts to meet these specific challenges. Should the room suddenly be reallocated into a copy room with high traffic patterns, the intelligent software will adapt as needed to provide the correct time out for the





Phone: (480) 782-5600 Fax: (480) 782-5601 www.engenuity.com



lights. Using PIR sensing (high error immunity) with US (high sensitivity) provides good performance. Conventional ceiling mounted dual tech sensors use a simple formula for operation: BOTH for ON, EITHER for KEEP ON. This method requires that both sensors receive fixed-strength signals for ON or a single fixed-level signal for KEEP ON. The OMNI-DT uses a more sophisticated method called a composite signal where the signal strengths are added together to form a composite sum. The advantage of this method is that a weak PIR signal plus a strong US signal will turn the lights on because the sum is enough. The installer need not worry that the signal level be balanced for reliable lights on. This technology eliminates time consuming adjustments and callbacks found in non-intelligent sensors.

The sensor requires a 24V DC, MP Series power pack. The mounting base, provided with the sensor, allows guick and easy mounting.

ADAPTIVE FUNCTIONS

The OMNI constantly analyzes and adapts to changing conditions:

| Period | Time | Action |
|---------------------|------------|-------------------------------------|
| Installation | 60 minutes | Timer automatically resets from |
| | | Test (8 seconds) to 8 minutes. |
| Learning | Four weeks | 1.Response to Error |
| | | Conditions: |
| | | (false-ons, false offs) |
| | | 2. Air current adapation |
| | | 3. Timer optimization |
| | | Adjustments Made: |
| | | Últrasonic sensitivity |
| | | Infrared sensitivity |
| | | Timer |
| | | Air current threshold |
| Post learning | After | 1.24 hour occupancy periods |
| Occupancy | Four weeks | learned (circadian) |
| Periods (Circadian) | | 2. Weekly occupancy periods learned |
| (Circadian) | | Adjustments Made: |
| | | a. Generally occupied periods: |
| | | Threshold+High Sensivity |
| | | mode |
| | | b. Generally unoccupied |
| | | periods: |
| | | Threshold=Miser mode |

SPECIFICATIONS

Red Infrared motion, Green Ultrasonic LED Lamp:

motion

Construction: Two ultrasonic transmitters and two narrow

bandwidth receivers each 16mm in diameter. Frequency — Crystal controlled to ±.005%. Transducers — Oriented north and south (DT2000 only, others use single pairs),

angled 30° down from horizontal.

Housing — Rugged, high-impact, injection molded plastic KJB ABS Cyolac (UL-945VA) flame class rating, UV inhibitors.

Color-coded leads are 6".

Size & Weight: 4.5" dia., 1.5" height; 5 oz. (114 mm dia.,

38 mm height; 142 g.)

Color: White.

Power

Requirements: 24 VDC, 33 mA

(use MP-series power pack.)

Automatic - 8 min. to 32 min.; Timer Setting:

test mode - 8 seconds

24 VDC active high logic control signal Output:

with short circuit protection and optional

dry contact (see -RP option).

Operating

Environment: 32°F to 104°F (0°C to 40°C); 0% to 95%

non-condensing, relative humidity.

For indoor use only.


RP Option: Relay and Photocell Included (both).

> Relay: NO + NC contacts, 500ma rated @ 24vdc, three wire, isolated relay. Photocell, 0-1000 Lux adjustable.


Warranty: 5 years limited.

MODELS

| Cat. No. | Color | Coverage | Application |
|----------------|-----------|--------------|--------------------|
| OMNI-DT500 | Off White | 500 sq. ft. | Private Office |
| OMNI-DT500-RP | Off White | 500 sq. ft. | Private Office |
| OMNI-DT1000 | Off White | 1000 sq. ft. | Open Office |
| OMNI-DT1000-RP | Off White | 1000 sq. ft. | Open Office |
| OMNI-DT2000 | Off White | 2000 sq. ft. | Open Office |
| OMNI-DT2000-RP | Off White | 2000 sq. ft. | Open Office |
| | | | |



ORTHOGRAPHIC PROJECTION



DT-500 Range Pattern is not provided





Distributed by: **Engenuity** open systems **⋄** delivered Phone: (480) 782-5600 Fax: (480) 782-5601 www.engenuity.com

OMNI-IR/OMNI-IR-RP (Option RP)

Infrared Ceiling Mount Sensor

KEY FEATURES

- INTELLIGENT Continuously Adapting sensor.
- · Passive Infrared Sensing
- · Simple, Fast Installation
- Snap-Lock Sensor, Ceiling Mounting
- · Excellent false tripping Immunity
- Non-Volatile Memory: settings saved in protected memory are not lost during power outages.
- Optional Photocell Control and Relay
- 450 and 1500 sq. ft. mounted at 8'
- Multiple Sensor and Power Pack Connections
- 24VDC, Class 2 low voltage wiring
- · Designed & Manufactured in USA



Occupancy sensors have two tasks; keeping the lights on while the room is occupied and keeping the lights off when unoccupied. Hubbell Building Automation's intelligent, continuously adapting sensor technology eliminates manual sensitivity and timer adjustments during installation and over the life of the product. The self-adapting microprocessor constantly assures maintenance free "Install and Forget" operation.

The OMNI-IR is a ceiling mount occupancy sensor that uses passive infrared (PIR) sensing to detect occupancy. The sensor uses a small semiconductor heat detector that resides behind a multi-zone optical lens. This Fresnel™ lens establishes dozens of zones of detection. The sensor's detector is sensitive to the heat emitted by the human body. In order to trigger the sensor, the source of heat must move from one zone of detection to another. Non-moving hot objects will not cause the lights to turn on. The internal microprocessor analyzes the information from the PIR technology and determines the optimum setting to use in order to properly cover the space. The automatic timer and automatic sensitivity features of the OMNI-IR work independently to prevent

The OMNI-IR is the sensor replacement providing the best long-range major motion detection.



"false-offs" and "false-ons." When the sensor detects motion immediately after it turns the lights out, a "false-off" is detected, and both the timer and sensitivity are increased. If the sensor turns the lights on, but detects no immediate follow-up motion, a "false-on" is detected; again both the timer and sensitivity are decreased. The "Intelligent software" algorithm determines, for example, if the lights are staying on due to adjacent hallway traffic and responds by adapting its program to compensate for the false trigger and turns out the lights. The OMNI-IR is the sensor that provides the best long-range major motion detection.

Designed to meet the challenges found in a wide variety of spaces the OMNI-IR provides reliable detection with high error immunity. The sensor utilizes Hubbell Building Automation's intelligent software that reads the environment and adapts to meet the specific challenges. Should the room suddenly be reallocated into a room with high traffic patterns versus low, the intelligent software will adapt as needed to provide the correct time out for the lights. Conventional ceiling mounted PIR sensors use simple ON/OFF triggers for operation. This method leaves no room for adaptation or environment changes. This technology eliminates time consuming adjustments and callbacks found in non-intelligent sensors.

In addition, the OMNI-IR has an optional photocell, which increases energy savings when engaged by preventing the lights from turning on when there is sufficient natural light. This feature is factory disabled and may be activated by the installer. The sensor requires a 24V DC, MP Series power





Phone: (480) 782-5600 Fax: (480) 782-5601 www.engenuity.com



pack. The mounting base, provided with the sensor, allows quick and easy mounting.

FEATURES

Timer Setting: Automatic - 8 min. to 100 min. Manual - 8 min. to 32 min. Test mode - 8 sec.

MODELS

| Cat. No. | Color | Coverage | Application |
|--------------|-----------|---------------|--------------------|
| OMNI-IR | Off White | 450 sq. ft. | Work Area |
| OMNI-IR-RP | Off White | 450 sq. ft. | Work Area |
| OMNI-IR-L | Off White | 1,500 sq. ft. | Work Area |
| OMNI-IR-L-RP | Off White | 1,500 sq. ft. | Work Area |

CONTROLS

PC (Photocell Adjustment): 20 to 3,000 Lux (photocell optional).

SPECIFICATIONS

Timer Adjustment

(Manual): 8 sec. to 32 min. LED Lamp: Red Infrared motion.

Lens: The long range lens provides up to 1500 sq. ft.

of coverage, whereas the factory standard

extra dense lens provides 450 sq. ft.

of coverage.

Note: Although the OMNI-IR lens covers a smaller area, the dense coverage provides

better detection of small motions.

Construction: Housing — Rugged, high-impact, injection

molded plastic. Color coded leads are 6" long

(16.24 cm).

Size & Weight: 4.5" dia., 1.5" height; 5 oz.

(114 mm dia., 38 mm height; 142 g).

Color: White.

Power

Requirements: 24 VDC, 33 mA from the MP-series

power pack.

Output: 24 VDC active high logic control signal with

short circuit protection; optional dry contact

included in RP option.

Operating

Environment: 32°F to 104°F (0°C to 40°C); 0%

to 95% relative humidity, non-condensing.

For indoor use only.


Warranty: 5 years.

RP: Relay: SPDT, 500 ma rated @ 24VAC/DC,


three wire, isolated relay.

Photocell: 20-3,000 Lux adjustable.

RANGE DIAGRAM




ORTHOGRAPHIC PROJECTION




PHYSICAL WIRING

Using MP-SERIES Power Pack



Using MP-S SERIES Slave Power Pack





Phone: (480) 782-5600 Fax: (480) 782-5601 www.engenuity.com





WPIR Passive Infrared Ceiling Sensor

PIR sensor turns lights on and off based on occupancy

User-adjustable time delay of 30 seconds to 30 minutes

Automatic or manual-on operation when used with a BZ-150 Power Pack



ASIC technology reduces components and provides greater reliability

 30-segment, multi-element Fresnel lens

PROJECT

LOCATION/TYPE

Product Overview

Description

WattStopper's WPIR Sensor is a versatile ceilingmount sensor that utilizes the latest passive infrared (PIR) technology to turn lights on and off based on occupancy. The WPIR controls lighting in a wide variety of applications, but is especially adept at controlling small spaces with well-defined coverage.

Operation

The WPIR Ceiling Sensor utilizes the latest PIR technology to detect the difference between the infrared energy from a person in motion and the background space within the controlled area. When occupancy is detected, this 24 VDC sensor turns lighting or HVAC systems on through a WattStopper power pack controlled through low voltage wiring. When occupants leave the area, lighting is switched off after the user-adjustable time delay has elapsed.

Features

- ASIC technology enhances reliability and provides immunity to RFI and EMI
- Uses the latest PIR technology to reliably control lighting in a variety of applications
- User-adjustable time delay of 30 seconds to 30 minutes
- Incorporated daylight filter prevents shortwavelength infrared waves, such as those emitted by the sun, from affecting WPIR

Fresnel Lens and Coverage

The WPIR is equipped with a multi-element Fresnel lens that allows the sensor to efficiently collect infrared energy and provides optical gain over a defined field of view. The profile of each groove facet is determined by computer simulation to produce the sharpest images possible from a distant object. The use of a 30-segment lens allows overlapping coverage within the defined field of view. The coverage is partially determined by the view available to the sensor. Mounted to a wall, the WPIR will produce a completely different viewing pattern. Zone 4 and 5 (see diagram on back) are then capable of sensing up to 45 feet.

Applications

The WPIR can effectively cover small offices, utility areas or computer rooms. Additional applications include racquetball courts, garage areas, library aisleways and storage rooms.

- Multi-element Fresnel lens allows the sensor to efficiently collect infrared energy and provide optical gain over a defined field of view
- Alternate viewing patterns depending on mounting choice
- Optional on override through logic key/on bypass
- LED indicates occupancy detection
- Qualifies for ARRA-funded public works projects




Specifications


- Dual-element, temperature compensated pyroelectric sensor
- Adjustable time delay: 30 seconds to 30 minutes
- Poly IR4 lens, optical filter material
- Control output: 100mA maximum
- Max. units per power pack: B = eight; BZ = ten
- Dimensions: 2.5" x 2.5" x 1.14"
 (64mm x 64mm x 29mm) W x L x D
- UL and cUL listed
- Five year warranty

Wiring & Controls

Product Controls




Wiring Diagram




Coverage & Placement

Coverage Pattern



Typical Office Placement




For an enclosed office, the WPIR should be placed in the corner of the room so that it will detect occupants as they enter the room. For the aisleway between bookstacks, the WPIR should be placed at the end of each bookstack to detect occupancy upon entrance to the aisle way from either direction. For longer bookstacks, two or more WPIRs can be used.

Detection Zones

| Ceiting Height | Zone 5 | Zurie 4 | Zone 3 | Zurie z | Zone i |
|----------------|--------|---------|--------|---------|--------|
| 8' | -1 | 1 | 4 | 8 | 15 |
| 10' | -1.5 | 1.5 | 5 | 10 | 19 |
| 12' | -2 | 2 | 6 | 12 | 23 |
| 15' | -2.5 | 2.5 | 8 | 15 | 29 |
| 20' | -3 | 3 | 10 | 18 | 36 |
| 25' | -4 | 4 | 12 | 23 | 45 |
| *8' | 50 | 40 | 25 | 15 | 5 |

* Wall mounted Horizontally

Aisleway Library Bookstack Placement



watt mounted nonzonta

| Catalog No. | Voltage | Current | Coverage | |
|-------------|---------|---------|-------------------|--|
| WPIR | 24 VDC | 14 mA | 300 ft² (27.9 m²) | |

All units are white and use WattStopper power packs.

Ordering Information

Pub. No. 0612 rev. 10/2009

ADJUSTMENTS


A CAUTION A

WHEN ADJUSTING THE TIME DELAY OR WHEN SWITCH IS UNSECURED, YOU SHOULD TURN OFF POWER TO THE SWITCH AT THE CIRCUIT BREAKER.

To test and adjust the unit:

- With a phillips screwdriver, turn time delay trimpot (see diagram) to minimum (all the way counterclockwise).
- 2. Temporarily secure the switch to the wall box.
- Turn on power to the switch at circuit breaker and allow a one minute warm-up.

Note: Whenever the main power is restored to the switch, such as when turning on the circuit breaker, the occupancy sensor charges and may take up to a minute to function properly.



- Test the unit by pushing the Auto/Off button to the auto position to turn lights on. Leave the room and lights should go off after 30 seconds.
- Adjust the time delay trimpot to desired setting, between 30 seconds to 30 minutes (clockwise increases time). For most applications, about 10 minutes is recommended.
- Align wide holes on attached metal bracket with holes in wall box and secure switch with screws provided.
- 7. Install cover plate to switch assembly with provided screws.
- 8. Push the Auto/Off button to the auto position to turn lights on.

ATROUBLESHOOTING

Lights will not turn on: (LED flashes with body motion)

- I. Press the Auto/Off button to the auto position.
- 2. Check all wire connections.
- 3. For technical support call I (800)879-8585.

Lights will not turn on: (LED does not flash)

- I. Make sure the main circuit breaker is on.
- **Note:** Whenever the main power is restored to the switch, the occupancy sensor charges and may take up to one minute to function properly.
- 2. Check all wire connections.
- 3. For technical support call 1(800)879-8585.

Lights will not turn off:

- Depending on the time delay setting, there can be up to a 30 minute time delay after the last occupancy motion is detected.
- To test if unit is operating properly, set time delay to minimum and move out of the sensor's view. Lights should turn off after 30 seconds.
- 3. For technical support call I (800)879-8585.

Sensing motion outside detection areas:

 Opaque adhesive tape is included with the sensor and can be used to limit the detection areas. See "Masking the lens".

IMPORTANT: Rapid successive pressing of the Auto/Off button will cause a delay in proper function.

△ORDERING INFORMATION

| θHz |
|-----|
| Ήz |
| |
| |
| ĸ |
| |

Add -W for White, -I for Ivory, -G for Gray, -B for Black, or -A for Almond to the catalog number.

* One ASP-211 is included with each sensor.

△WARRANTY INFORMATION

The Watt Stopper®, Inc. warranties its products to be free of defects in materials and workmanship for a period of five years. There are no obligations or liabilities on the part of The Watt Stopper, Inc. for consequential damages arising out of or in connection with the use or performance of this product or other indirect damages with respect to loss of property, revenue, or profit, or cost of removal, installation or reinstallation.

The Watt Stopper®

Putting a Stop to Energy Waste®

2800 De La Cruz Boulevard, Santa Clara, CA 95050 USA Technical Support: 1(800)879-8585 1(972)578-1699 86-0480-00 4/98

WD-170 and WD-180 Dimmable PIR Wall Switch



△SPECIFICATIONS

Voltage:

| WD-170 120VAC, 60Hz |
|---|
| WD-180 277VAC, 60Hz |
| Load Rating: |
| @120VAC . 10-500W ballast or incandescent load |
| @277VAC10-500W ballast load |
| Tungsten: Dims incandescent lamps |
| Ballasts: Use with Advance® Mark X™ or Philips Ecotron® electronic dimming ballasts (line voltage forward phase-cut dimming ballasts) |
| Dimmer Adjustment: 5%-100% |
| Time Delay Adjustment: 30 sec.–30 min. |



Santa Clara, CA 95050 1(800)879-8585 1(972)578-1699 U.S.Patents: 4,787,722 4,874,962

A 95050 5,124,566 5 1(972)578-1699 5,640,113

AUNIT DESCRIPTION

The Watt Stopper's WD-170 and WD-180 are dimmable passive infrared wall switches that turn lighting systems on and off based on occupancy in the controlled area. A dimming slider adjusts the light level from minimum to maximum.

The switches work with the Advance® Mark X[™] or Philips Ecotron® electronic dimming ballasts (ballasts that have line voltage forward phase-cut dimming control). The WD-170 also works with incandescent fixtures.

The sensors feature a hard vandal resistant lens which allows them to be used in a wide range of applications, including public spaces.

△OPERATION


The WD-170 and WD-180 sensors turn lights on when a person enters the controlled area. Lights turn on to the level set with the dimming slider. The dimming slider does not turn the lights off, it allows users to increase or decrease the light level.

The lights remain on while the space is occupied. When the space is vacated and the adjustable time delay of 30 seconds to 30 minutes (set during installation) elapses, the lights turn off.

The lights can be manually turned off at any time by pressing the Auto/Off button.

∧COVERAGE PATTERNS

The WD-170 and WD-180 will cover up to 300 sq ft. The recommended coverage for typical desktop activity is 150 sq ft. The sensor has a two-tiered, multi-cell viewing Fresnel lens with a 180° field of view.





Masking the lens

Opaque adhesive tape is supplied so that sections of the sensor's view can be masked. This allows you to eliminate coverage in unwanted areas. Since masking removes bands of coverage, remember to take this into account when trouble-shooting coverage problems.




^INSTALLATION

The WD-170 and WD-180 switches can be connected to single or multiple loads, up to 500 watts maximum.

A CAUTION A


TURN POWER OFF AT CIRCUIT BREAKER
BEFORE WIRING SWITCHES.
ALWAYS FOLLOW PROPER PRECAUTIONS WHEN
WORKING WITH OR NEAR HIGH YOLTAGE.

- I. Make sure that power has been turned off at circuit breaker.
- Connect leads to sensor with UL listed wire connectors (BLACK to line, GREEN to ground, RED to load).
- Do not attach switch to wall box at this time. See "Adjustments".







THE GROUND MUST BE TIGHTLY SECURED OR THE SENSOR WILL NOT WORK!




 ${f C}$ Call (800) 879-8585 For Technical Support ${f C}$



Manufacturer: FINELITE, INC.
Luminaire catalog: FINELITE S10-A12-2T8-EP-OPEN
Luminaire: DIRECT-INDIRECT, SUSPENDED LUMINAIRE
Lamp catalog: PHILLIPS F32T8/TL735 LINEAR FLUORESCENTS
Lamp: TWO 4' 32W T8 3500K FLUORESCENT LAMP




Manufacturer: FINELITE, INC.
Luminaire catalog: FINELITE S10-A12-3T8-91W-OPEN
Luminaire: DIRECT-INDIRECT, SUSPENDED LUMINAIRE
Lamp catalog: PHILLIPS F32T8/TL735 LINEAR FLUORESCENTS
Lamp: THREE 4' 32W T8 3500K FLUORESCENT LAMP




Manufacturer: Lithonia Lighting Luminaire catalog: 2PM3 3 32 18LD 1/3 TUBI Luminaire: PARAMAX PARABOLIC TROFFER 2'X4' 3" LVR 3 LP T8 18 CEL

Lamp catalog: F32T8/735 Lamp: THREE 32-WATT T8 LINEAR FLUORESCENT



Manufacturer: Lithonia Lighting
Luminaire catalog: WP 2 32 DO TUBI
Luminaire: PRECEDENT WALL BRKT 4' 2 LMP


Lamp catalog: F32T8/SPX35 Lamp: TWO 32-WATT T8 LINEAR FLUORESCENT



Manufacturer: Lithonia Lighting
Luminaire catalog: LB 2 32 MVOLT GEB10IS
Luminaire: 2/32W T8 LAMPS 4'SURFACE MNT CURVED BASKET WRAP L

Lamp catalog: F32T8/835/RS


Lamp: 32T8




Manufacturer: Lithonia Lighting Luminaire catalog: 2AV G 3 32 MDR 1/3 ASR

Luminaire: 2X4 AVante, recessed, 3 lamp T8 32 watt, Metal Diffuser w/ Roun

Lamp catalog: F32T8
Lamp: THREE 32-WATT T8 LINEAR FLUORESCENT.




Manufacturer: Lithonia Lighting
Luminaire catalog: TAF ST 1 32 MVOLT GEB10IS
Luminaire: TANDEM INDUSTRIAL TURRET 1' X 8' 2 LAMP T8 WHITE ENAI
Lamp catalog: FO32/35K
Lamp: TWO 32-WATT T8 LINEAR FLUORESCENT.




Manufacturer: Lithonia Lighting Luminaire catalog: DMW 2 32 Luminaire: 4FT_WET_LOCATION ENCLOSURE WITH (2) T8 LAMPS, 50% D

Lamp catalog: F32T8
Lamp: TWO 32-WATT LINEAR FLUORESCENT T8, 735



Manufacturer: COOPER LIGHTING - SHAPER Luminaire catalog: 494-34-CF4/26-120SSB Luminaire: PENDANT MOUNT LUMINAIRE Lamp catalog: CF26DD/E/841. LUMEN RATING = 7300 LMS. Lamp: FOUR SYLVANIA 26 WATT CPFL LAMPS





Air Cooled Screw Chiller **Performance Specification**

| Unit Tag | Qty | Model No | | Capacity (Tons) | Volts/Ph/Hz | Refriperant |
|---------------------|----------|---------------------|-------|-----------------|-------------|-------------|
| CH-1C-1 | 1 | YCIV0187SA46 | | 175.3 | 460/3/60 | R134a |
| Pin No: YCIV0187SA4 | I6VABBXT | XXXXXLXXXX42SXXXXXH | XXXSA | XLXXX5RXXLXND | XXXX | |

| Evaporator Da | la . T | Evaporator Data | (Cont.) | Performance D | afa |
|------------------------|---------------|---------------------------|---------|-----------------------|------------|
| EWT (°F) | 56.0 | GPM Min, Flow Rate | 160.0 | EER / COP | 9.4 / 2.8 |
| LWT (°F) | 42.0 | GPM Max. Flow Rate | 750.0 | EER NPLV/COP NPLV | 12.7 / 3.7 |
| Design Flow Rate (gpm) | 317.7 | | | Minimum Unit Capacity | 10 % |
| Pressure Drop (ft.) | 17.6 | Condenser D | ata | Physical Data | |
| Fluid | P.G. 30.0% | Ambient Temp. Design (°F) | 95.0 | Rigging Wt. (lbs.) | 13540.8 |
| Fouling Factor | 0.00010 | Altitude (ft.) | 0 | Operating Wt. (lbs.) | 14334.4 |
| Water Volume (gal) | 95.0 | Ambient Temp. Min (°F) | 0.0 | - P | 17227.7 |

| | Electr | icál Dáta | | |
|--------------------|--------|-----------|---|---|
| Circuit | 1 | 2 | 3 | 4 |
| Compressor RLA | 162 | 120 | | |
| Fan QTY/FLA (each) | 5/2.8 | 4/2.8 | | |

| | Sin | gle Pôint |
|------------------------------------|----------------|-----------|
| Title Circuit Filipacity | 348 | |
| Recommended Fuse/CB Rating | 400 | |
| Max. Inverse Time CB Rating | 500 | |
| Max. Dual Element Fuse Size (Amps) | 500 | |
| Unit Short Circuit Withstand (STD) | 65KA | |
| Wire Lugs Per Phase* | 2 | |
| Wire Range (Lug Size) | #2/0 - 500 KCM | |
| Unit Power Factor | 0.95 | |

| Control KVA | 1.8 | | | Starter Type | VSD |
|---------------|-------|--------------|------|--------------|-------|
| Compressor kW | 209.4 | Total Fan kW | 15.1 | Total kW | 224.5 |

Notes: OPERATING COST SAVINGS OPPORTUNITY! Consider upgrading to the OPTIMIZED IPLV model to save approximately \$4828 / YEAR in energy costs versus the standard model. Calculation based on; a) national average weather data, b) national average building load profile, c) average building annual run hours (5000 hrs.), and d) national average commercial energy cost (per D.O.E., 2005, \$0.0865/kwh). For a more detailed analysis based on your project please contact your YORK representative.

RATED OUTSIDE THE SCOPE OF ARI STANDARD 550/590.

^{*} Use Copper Conductors only

| | | Part Load Rating Data | | |
|--------|--------------|-----------------------|---------------|-----------------|
| Load % | Ambient (°F) | Capacity (Tons) | Compressor kW | Unit Efficiency |
| 100.0 | 95.0 | 175.3 | 209.4 | 9.4 / 2.8 |
| 75.0 | 80.0 | 131.5 | 109.4 | 12.7/3.7 |
| 50.0 | 65.0 | 87.7 | 76.7 | 12.9/3.8 |
| 25,0 | 55.0 | 43.8 | 40.8 | 12.4/3.6 |

| Project Name: CPS SUBMITTAL | Sold To: | |
|-----------------------------|--------------------|----------------|
| Location: | Customer Purchase | Order No.: |
| Engineer: | York Contract No.: | |
| Contractor: | Date: | Revision Date: |

Printed: 02/02/2009 AT 16:14

Unit Folder: HART-1

Unit Version: 9.52.FDW (Data Source: v5 48 46)

YORKworks v.9.52

CH-1 Performance

Page 1 of 2

Standard Efficiency Ratings - English - 460V/60Hz

| MOE | MODEL: YCIV0157S/P | | | | | | | | | | | | S_II | PLV= | 13.2 | P_II | PLV= | 14.5 | | | | | | | | | |
|------|--------------------|-------|------|-------|-------|------|-------|-------|------|-------|---------|--------|--------|---------|-------|--------|-------|------|-------|-------|-----|-------|-------|------|-------|-------|------|
| | | | | | | | | | | - | AIR TEN | IPERA | TURE (| ON - CO | NDENS | ER (°F |) | | | | | | | | | | |
| LCWT | | 75.0 | | | 80.0 | | | 85.0 | | | 90.0 | | | 95.0 | | | 100.0 | | | 105.0 | | | 110.0 | | | 115.0 | |
| (°F) | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER |
| 40.0 | 149.1 | 131.5 | 12.3 | 148.0 | 141.8 | 11.4 | 146.7 | 152.6 | 10.6 | 145.4 | 164.1 | 9.8 | 143.9 | 176.0 | 9.1 | 142.2 | 189.4 | 8.4 | 138.9 | 202.0 | 7.7 | 136.4 | 216.0 | 7.1 | 132.7 | 229.5 | 6.6 |
| 42.0 | 153.7 | 132.5 | 12.6 | 152.5 | 142.6 | 11.7 | 151.2 | 153.5 | 10.9 | 149.8 | 165.0 | 10.1 | 148.2 | 177.0 | 9.3 | 146.5 | 190.5 | 8.6 | 142.7 | 202.7 | 7.9 | 139.9 | 217.0 | 7.3 | 136.1 | 230.5 | 6.7 |
| 44.0 | 158.3 | 133.5 | 12.9 | 157.1 | 143.6 | 12.0 | 155.7 | 154.4 | 11.1 | 154.3 | 165.9 | 10.3 | 152.6 | 177.9 | 9.6 | 150.8 | 191.5 | 8.8 | 146.5 | 203.4 | 8.1 | 143.6 | 217.8 | 7.5 | 139.6 | 231.3 | 6.8 |
| 45.0 | 160.7 | 134.0 | 13.1 | 159.4 | 144.1 | 12.1 | 158.1 | 154.9 | 11.3 | 156.5 | 166.4 | 10.4 | 154.9 | 178.4 | 9.7 | 153.0 | 192.0 | 8.9 | 148.4 | 203.7 | 8.2 | 145.5 | 218.2 | 7.5 | 141.4 | 231.8 | 6.9 |
| 46.0 | 163.1 | 134.6 | 13.2 | 161.8 | 144.6 | 12.3 | 160.4 | 155.4 | 11.4 | 158.8 | 166.9 | 10.6 | 157.1 | 178.9 | 9.8 | 155.2 | 192.5 | 9.0 | 150.4 | 204.0 | 8.3 | 147.4 | 218.5 | 7.6 | 143.2 | 232.3 | 7.0 |
| 48.0 | 167.9 | 135.7 | 13.5 | 166.6 | 145.7 | 12.6 | 165.1 | 156.5 | 11.7 | 163.5 | 167.9 | 10.8 | 161.7 | 180.0 | 10.0 | 159.7 | 193.6 | 9.3 | 154.3 | 204.7 | 8.5 | 151.2 | 219.3 | 7.8 | 146.9 | 233.2 | 7.1 |
| 50.0 | 172.8 | 137.0 | 13.8 | 171.4 | 146.9 | 12.8 | 169.9 | 157.7 | 11.9 | 168.2 | 169.0 | 11.1 | 166.4 | 181.1 | 10.3 | 164.3 | 194.7 | 9.5 | 158.2 | 205.4 | 8.7 | 155.0 | 220.0 | 8.0 | 148.9 | 228.5 | 7.4 |
| 52.0 | 177.8 | 138.4 | 14.0 | 176.4 | 148.2 | 13.1 | 174.8 | 158.9 | 12.2 | 173.1 | 170.2 | 11.3 | 171.2 | 182.3 | 10.5 | 168.6 | 195.6 | 9.7 | 162.2 | 206.1 | 8.9 | 158.9 | 220.7 | 8.1 | 150.6 | 222.7 | 7.7 |
| 55.0 | 185.4 | 140.6 | 14.4 | 184.0 | 150.3 | 13.5 | 182.3 | 160.8 | 12.6 | 180.5 | 172.1 | 11.7 | 178.5 | 184.1 | 10.8 | 175.0 | 196.8 | 10.0 | 168.3 | 207.2 | 9.2 | 164.9 | 221.8 | 8.4 | 153.1 | 214.2 | 8.1 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MOE | MODEL: YCIV0177S/P | | | | | | | | | | | S_II | PLV= | 13.0 | P_II | PLV= | 14.8 | | | | | | | | | | |
| | | | | | | | | | | 1 | AIR TEN | (IPERA | TURE (| ON - CO | NDENS | ER (°F |) | | | | | | | | | | |
| LCWT | | 75.0 | | | 80.0 | | | 85.0 | | | 90.0 | | | 95.0 | | | 100.0 | | | 105.0 | | | 110.0 | | | 115.0 | |
| (°F) | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER |
| 40.0 | 165.7 | 144.7 | 12.6 | 164.2 | 156.2 | 11.6 | 162.4 | 168.5 | 10.7 | 160.5 | 181.2 | 9.9 | 158.4 | 194.4 | 9.1 | 154.6 | 205.6 | 8.5 | 149.9 | 214.6 | 7.9 | 146.6 | 225.5 | 7.4 | 131.6 | 208.8 | 7.1 |
| 42.0 | 170.9 | 145.7 | 12.9 | 169.3 | 157.3 | 11.9 | 167.5 | 169.5 | 11.0 | 165.5 | 182.3 | 10.1 | 163.3 | 195.6 | 9.4 | 159.1 | 206.2 | 8.7 | 154.0 | 215.3 | 8.1 | 150.7 | 226.2 | 7.5 | 133.2 | 204.3 | 7.3 |
| 44.0 | 176.1 | 146.8 | 13.2 | 174.6 | 158.3 | 12.2 | 172.8 | 170.6 | 11.3 | 170.7 | 183.5 | 10.4 | 168.4 | 196.8 | 9.6 | 163.8 | 206.8 | 8.9 | 158.3 | 215.8 | 8.3 | 154.7 | 227.0 | 7.7 | 135.0 | 200.0 | 7.6 |
| 45.0 | 178.8 | 147.5 | 13.3 | 177.2 | 158.9 | 12.3 | 175.4 | 171.1 | 11.4 | 173.3 | 184.0 | 10.5 | 171.0 | 197.5 | 9.7 | 166.1 | 207.1 | 9.0 | 160.5 | 216.0 | 8.4 | 156.8 | 227.3 | 7.8 | 135.8 | 197.7 | 7.7 |
| 46.0 | 181.5 | 148.2 | 13.5 | 179.9 | 159.5 | 12.5 | 178.1 | 171.7 | 11.5 | 175.9 | 184.6 | 10.7 | 173.5 | 197.8 | 9.9 | 168.5 | 207.3 | 9.2 | 162.6 | 216.2 | 8.5 | 158.9 | 227.6 | 7.9 | 136.5 | 195.4 | 7.8 |
| 48.0 | 186.9 | 149.5 | 13.8 | 185.4 | 160.8 | 12.8 | 183.5 | 173.0 | 11.8 | 181.3 | 185.9 | 10.9 | 178.4 | 198.3 | 10.1 | 173.3 | 207.9 | 9.4 | 167.0 | 216.6 | 8.7 | 161.6 | 224.4 | 8.2 | 138.0 | 190.9 | 8.1 |
| 50.0 | 192.4 | 151.0 | 14.0 | 190.8 | 162.2 | 13.0 | 189.0 | 174.3 | 12.1 | 186.7 | 187.2 | 11.2 | 183.4 | 198.8 | 10.4 | 178.2 | 208.4 | 9.6 | 171.5 | 217.0 | 8.9 | 163.6 | 219.4 | 8.4 | 139.3 | 186.1 | 8.4 |
| 52.0 | 198.0 | 152.6 | 14.3 | 196.4 | 163.7 | 13.3 | 194.5 | 175.8 | 12.3 | 192.2 | 188.6 | 11.4 | 188.5 | 199.4 | 10.6 | 183.1 | 209.0 | 9.9 | 176.0 | 217.4 | 9.1 | 165.5 | 214.4 | 8.7 | 140.6 | 181.5 | 8.7 |
| 55.0 | 206.4 | 155.2 | 14.7 | 204.9 | 166.1 | 13.7 | 202.9 | 178.1 | 12.7 | 200.6 | 190.9 | 11.8 | 196.2 | 200.4 | 11.0 | 190.7 | 209.9 | 10.2 | 182.9 | 217.9 | 9.5 | 168.2 | 206.9 | 9.2 | 142.5 | 174.8 | 9.1 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MOE | EL: | YC | IV01 | 87S | /P | | | | | | | | | | | | | | | | | S_I | PLV= | 13.1 | P_II | PLV= | 14.9 |
| | | | | | | | | | | 1 | AIR TEN | IPERA | TURE C | N - CO | NDENS | ER (°F |) | | | | | | | | | | |
| LCWT | | 75.0 | | | 80.0 | | | 85.0 | | | 90.0 | | | 95.0 | | | 100.0 | | | 105.0 | | | 110.0 | | | 115.0 | |
| (°F) | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER | TONS | KW | EER |
| 40.0 | 180.3 | 156.2 | 12.6 | 178.8 | 168.2 | 11.7 | 177.1 | 181.1 | 10.8 | 175.3 | 194.7 | 10.0 | 173.4 | 208.9 | 9.3 | 171.1 | 224.9 | 8.6 | 166.1 | 236.3 | 7.9 | 162.9 | 249.2 | 7.4 | 158.5 | 260.7 | 6.9 |
| 42.0 | 185.9 | 157.4 | 12.9 | 184.4 | 169.4 | 12.0 | 182.6 | 182.3 | 11.1 | 180.7 | 195.8 | 10.3 | 178.7 | 210.1 | 9.5 | 176.4 | 226.2 | 8.8 | 170.5 | 236.8 | 8.1 | 167.2 | 249.8 | 7.6 | 162.6 | 261.4 | 7.1 |
| 44.0 | 191.7 | 158.8 | 13.2 | 190.0 | 170.7 | 12.3 | 188.2 | 183.5 | 11.4 | 186.3 | 197.1 | 10.5 | 184.2 | 211.3 | 9.8 | 181.7 | 227.5 | 9.0 | 175.1 | 237.3 | 8.3 | 171.6 | 250.3 | 7.8 | 166.8 | 262.1 | 7.2 |
| 45.0 | 194.6 | 159.6 | 13.4 | 192.9 | 171.4 | 12.4 | 191.1 | 184.2 | 11.5 | 189.1 | 197.7 | 10.7 | 186.9 | 212.0 | 9.9 | 184.3 | 228.0 | 9.1 | 177.4 | 237.5 | 8.4 | 173.8 | 250.6 | 7.9 | 168.4 | 260.9 | 7.3 |
| 46.0 | 197.5 | 160.4 | 13.5 | 195.8 | 172.1 | 12.5 | 193.9 | 184.9 | 11.6 | 191.9 | 198.4 | 10.8 | 189.7 | 212.7 | 10.0 | 186.9 | 228.3 | 9.2 | 179.7 | 237.7 | 8.5 | 176.1 | 250.8 | 7.9 | 169.1 | 257.2 | 7.5 |
| 48.0 | 203.5 | 162.1 | 13.8 | 201.7 | 173.7 | 12.8 | 199.8 | 186.3 | 11.9 | 197.6 | 199.8 | 11.0 | 195.3 | 214.1 | 10.2 | 191.9 | 228.9 | 9.4 | 184.5 | 238.1 | 8.7 | 180.7 | 251.2 | 8.1 | 170.6 | 250.2 | 7.7 |
| 50.0 | 209.5 | 163.8 | 14.1 | 207.7 | 175.3 | 13.1 | 205.7 | 187.8 | 12.2 | 203.5 | 201.3 | 11.3 | 201.1 | 215.5 | 10.5 | 196.8 | 229.3 | 9.7 | 189.3 | 238.4 | 9.0 | 185.4 | 251.6 | 8.3 | 172.3 | 243.6 | 8.0 |
| 52.0 | 215.7 | 165.8 | 14.3 | 213.8 | 177.1 | 13.3 | 211.7 | 189.5 | 12.4 | 209.4 | 202.8 | 11.5 | 206.9 | 217.0 | 10.7 | 201.9 | 229.8 | 9.9 | 194.1 | 238.9 | 9.2 | 190.1 | 252.0 | 8.5 | 174.2 | 237.3 | 8.3 |
| 55.0 | 225.2 | 169.0 | 14.7 | 223.2 | 180.0 | 13.7 | 221.0 | 192.2 | 12.8 | 218.6 | 205.4 | 11.9 | 215.9 | 219.6 | 11.0 | 209.6 | 230.6 | 10.2 | 201.5 | 239.5 | 9.5 | 197.3 | 252.7 | 8.8 | 177.1 | 228.5 | 8.7 |

NOTES:

- 1. kWi = Compressor Input Power
- 2. EER = Chiller EER (includes power from compressors, fans, and control panels 0.8 KWi)
 3. LCWT = Leaving Chilled Water Temperature
- 4. Ratings based on 2.4 GPM cooler water per ton
- 5. Rated IAW AHRI Standard 550/590
- 6. Certified IAW the AHRI Water-Chilling Packages Using the Vapor Compression Cycle Certification Program, which is based on AHRI Standard 550/590.

JOHNSON CONTROLS 16