

36

FILE

Norfolk Southern Corporation
Communications and Signal Department
1200 Peachtree Street, N.E., Box 123
Atlanta, Georgia 30309

B. L. Sykes
Chief Engineer
C&S Engineering
404/529-2105

February 26, 2007
CX0118232

Ms. Susan Kirkland
Ohio DOT
1980 W. Broad St.
Columbus, OH 43223

06-1326-RR-Fed

RE: Norfolk Southern's Cincinnati Line Regarding the Modification of Automatic Grade Crossing Warning Devices at Burt Street in Clark County, Ohio, DOT: 527 973K, Milepost CJ-181.80


Dear Ms. Kirkland:

Attached for our review and approval are copies of the detailed cost estimate, material list and engineering plans for this crossing.

Although we cannot give you an exact date of installation at this time we can provide our average installation time, which is 9.1 months after authorization from the state. After this project is authorized, we will order material and schedule for installation once we have received approvals from ODOT's district office.

If you have any questions, please call Mike Rappatta at 404-582-6377.

Sincerely,


B. L. Sykes

Enclosure(s)

BLS/rhr/gbb/mlr/rjs

e/cy: Mr. R. S. Noe, NS Corporation
Ms. Susan Arduini, ORDC
Mr. Tim Perkins, ORDC
Ms. Bonnie Johrendt, PUCO
Mr. George Martin, PUCO
Ms. P. A. Gray, NS Corporation

Cy: ☒ Docketing Division (w/plans, estimate and material list)

PUCO

2007 MAR -5 AM 10:11

RECEIVED-DOCKETING DIV

This is to certify that the images appearing are an accurate and complete reproduction of a case file document delivered in the regular course of business
Technician 3 Date Processed 3.5.07



26-Feb-07

Detailed Estimate for Grade Crossing Warning Devices

City/State: SPRINGFIELD, OH
MilePost: CJ-181.8
State Proj. No.:
S&E Proj. No.: 10.0993
Man Days: 160

Road: BURT ST.
DOT/AAR: 527973K
County: CLARK
AFE: F10098
File Number: 061-10.1034

Purchases - Others	
Meals and Lodging:	\$15,054.34
Rental of Equipment:	\$32,912.00
(2 Trucks, 1 Backhoe w/ Trailer and 1 Pipe-Pusher for 40 Days)	
Construction Supervision Vehicle:	\$2,632.96
Purchases - Other Total:	\$50,599.30
Material And Additives	
Material Cost:	\$122,738.00
Sales and Use Tax:	\$0.00
Material Handling Freight:	\$6,136.89
Material Total:	\$128,874.89
Labor And Additives	
Labor Cost:	\$38,720.00
(4 man crew at \$968.00 a day for: 40 days)	
Payroll Tax & Overheads:	\$38,197.28
Preliminary Engineering:	\$14,208.28
Construction Supervision:	\$10,930.66
Labor Total:	\$102,056.22
Project Cost:	\$281,530.41
Scrap / Salvage Credit:	\$0.00
Project Total:	\$281,530.41

Estimated on: 26-Feb-07

Estimated by: n5s2v

Estimate valid for 1 year from date of estimate



Norfolk Southern Railway
Highway Crossing Signalization Program - Material List

Do not substitute items without permission from S & E Engineering

City:	SPRINGFIELD
Road:	BURT ST.
Mile Post:	CJ-181.8
Drawing Number:	82111818
State ProjectNumber:	
County:	CLARK
A A R Number:	527973K
Project Number:	10.0993
File Number:	061-10.1034
New File Number:	CX0118232
A F E Number:	F10098
Store Number:	
Supervisor:	D.M. FRANCIS
Tax Code:	3500
Vendor to supply the following copies after pricing: 1 Set - Material Management with original Invoice 2 Sets - with plans shipped in car with material 1 Set - S&E Gen. Supt. Construction w/copy of Invoice	

Location: SPRINGFIELD

OH

S&E Proj. No.: 10.0983

AFE No.: F10098

Drawing No.: 8211818

Store No.:

P.O. Number:

Date Required:

Date Shipped:

Vendor: Interrail Engineering, INC

Qty.	Class-Item-CD	UI	Price per Item	Total Price	Item Description	Quantity Shipped	Quantity Date	Quantity Installed Date	Quantity Returned (Credit)	Special Instructions
3	670-360693-4	EA	\$5.04	\$15.12	AAR/DOT NUMBER PLATE/DECAL. ORDER 3 PER PROJECT. 60 DAY LEAD TIME. SUPPLIED BY STRAN.					
1	165-006505-4	EA	\$1,051.54	\$1,051.54	AC SERVICE, COMPLETE LESS METER BASE, ASSEMBLED ON 30' POLE					
23	670-119241-4	EA	\$32.80	\$754.40	ARRESTOR, LIGHTNING HEAVY DUTY CLEAR VIEW SAFETRAN 022585-1X					
19	105-871901-4	EA	\$161.57	\$3,069.83	BATTERY, GNB 265AH MODEL 50A11 SINGLE CELL 2.25 VOLTS					
2	670-980689-4	EA	\$71.71	\$143.42	BRACKET HIGH WIND. (RIGID 3'), WIG- 191036, WALRUS TUSK TYPE					
2	670-561375-4	EA	\$1,197.90	\$2,395.80	BRACKET, GATE SAVER, NEG385102G5, SPRING LOADED SWING AWAY ADAPTER FOR FIBERGLASS/ALUMINUM GATES, USE WITH GATE 28' AND LESS					
1	670-356949-4	EA	\$97.00	\$97.00	CABLE, 10' GENERATOR HOOK UP, SERRMI P/N 40524, FEMALE CONNECTOR					
800	465-292862-4	LF	\$1.04	\$832.00	CABLE, U-2-6 TWISTED, S-23 OKONITE 113-12-3833 SOLID TINNED CONDUCTOR					
1000	465-292829-4	LF	\$3.05	\$3,050.00	CABLE, U.G. 5 COND. NO. 6 AWG SOLID COPPER CABLE TO MEET NS CORP. SPEC. FOR SIGNAL					
400	465-939422-4	LF	\$2.55	\$1,020.00	CABLE, UG 12 CONDUCTOR NO 14 AWG SOLID EACH CONDUCTOR WITH 5/64 IN INSULATION 10 MIL					
100	465-791835-4	FT	\$2.22	\$222.00	CABLE, UG AC ENTRANCE 3C#6-7X OKONITE FMPF-L 094-078 TR W/G 1 X 8 7X W010 BRZ TAPE 600V PRODUCT CODE 206-11-6070					
1	670-477629-4	EA	\$552.20	\$552.20	CHARGER, BATTERY CRAGG MODEL 20 EC-12V 20 AMP TEMP COMPENSATED					
310	165-544477-4	FT	\$2.55	\$790.50	CONDUIT, 4"x10' PVC, SCHEDULE 80 BELL CONNECTOR AT ONE END, 1/2 PT. GLUE IN KIT 670-123298-4					
6	670-090450-4	EA	\$50.38	\$302.28	CONNECTOR, WELDED FAR RAIL HARMON A1000-2W					
6	670-486646-4	EA	\$41.62	\$249.72	CONNECTOR, WELDED NEAR RAIL HARMON A1000-1W					
1	670-314147-4	EA	\$2,045.47	\$2,045.47	CONTROLLER, S.S.C. IIIA 20A SOLID STATE STRAN PART#9000-91165-0001					
2	670-794453-4	EA	\$854.03	\$1,708.06	COUNTERWEIGHT PKAGE, 25-31' GATE STAN S- MECH ONLY, STAINLESS TO INCLUDE HUB, SUPPORT ARMS					

APPROVED BY STATE

APPROVED BY RAILROAD

CAR NUMBER

SEAL NUMBER

Monday, February 26, 2007 9:15 AM

Page: 2 of 6

Location: SPRINGFIELD

OH

S&E Proj. No.: 10.0993

AFE No.: F10098

Drawing No.: 8211818

Store No.:

P.O. Number:

Date Required:

Date Shipped:

Vendor: InterRail Engineering, INC

Qty.	Class-Item-CD	UI	Price per Item	Total Price	Item Description	Quantity Shipped	Quantity Date Quan.	Quantity Installed Date Quan.	Quantity Returned (Credit)	Special Instructions
16	670-760012-4	EA	\$40.02	\$640.32	COVER, FOR 1 WAY FLASHING LIGHT ASSY. 18 OZ. BLACK VINYL COATED NYLON. === TO COVER 2 LAMPS ===					
1	670-986650-4	EA	\$375.69	\$375.69	DISPOSAL, CONSTRUCTION DEBRIS AND CLEANING X'ING EQUIPMENT CONTAINER					
1	670-007684-4	EA	\$672.10	\$672.10	DRIVER, TRACK, MODEL TD-4 ELECTRO PNEUMATIC CORP. FOUR OUTPUTS					
10	670-228165-4	EA	\$10.73	\$107.30	EQUALIZER, SAFETRAN 022700-1X LESS BASE, MODERN NO. 700-1 SHUNT ARRESTER TRACK CIRCUITS CR 02-197950					
1	670-000004-4	EA	\$700.00	\$700.00	FCC LICENSE FOR MONITOR/RADIO					
4	670-000003-4	EA	\$255.85	\$1,023.40	FILLSTONE #57, QUANTITY IS BASED ON TRUCK LOAD PLUS DELIVERY COST					
2	670-744631-4	EA	\$2,706.00	\$5,412.00	FOUNDATION, CFLS FOR SAFETRAN MODEL "WT/F" ARMS 12" TO 30" SINGLE MAST, DIXIE# S-10-3WS-C, 5'10" CR 02-205902					
4	670-015231-4	EA	\$423.50	\$1,694.00	FOUNDATION, DIXIE S-2 GATE 5'6" ASSEMBLED					
2	670-263738-4	EA	\$331.87	\$663.74	GATE, ARM FIBERGLASS-ALUMINUM 25-31 FT. INCLUDES GATE GUARD FOR GATE LIGHT CABLE. 076600-320017, NEG P/N 8002-4NFS/CG					
1	670-477991-4	EA	\$317.90	\$317.90	KIT, GROUNDING ASSY FOR AL I/S INCLUDES 8 GRD RDS, 200#4WIRE, 12 4 WIRE ONE SHOTS, ERICO SBK206					
1	670-123298-4	EA	\$256.93	\$256.93	KIT, HARDWARE SUPPLIES REQUIRED X'ING PACKAGES. WEB CONNECTORS FOR SHUNT(8EA) TAPE, AMPS, P GUM PAINT, SLEEVES, TAGS, GLUE, 100 EA WHITE TAGS, JNE CAN BLUE MARKING PAINT ETC...					
2	670-142763-4	EA	\$849.42	\$1,698.84	LAMP ASSY, 12" LIGHT, 2 WAY IND. FOR MTG ON THE TIP OF W/F CANTILEVER ARM, SAFETRAN P/N 042003-488XNS					
2	670-724041-4	EA	\$470.76	\$941.52	LAMP ASSY, 12" MAST MTG., USE WITH W & W/F MAST, 1W (BACK) (FRONT ON COMBO) IND. 20" BKGRD. FLX-12 W/BULB OLD STRAN# 042003-481XNS					
2	670-816589-4	EA	\$551.10	\$1,102.20	LAMP ASSY, 5" MAST MTG. 1W IND. 20" BKGRD. (BACK) LTS.FLX-12W/BULB STRAN # 042003-001493					
4	670-764166-4	EA	\$907.65	\$3,630.60	LAMP ASSY, 5" MAST MTG. 2W IND. 20" BKGRD. FLX-12 W/BULB STRAN #042003-487XNS					

APPROVED BY STATE

APPROVED BY RAILROAD

CAR NUMBER

SEAL NUMBER

Monday, February 26, 2007 9:15 AM

Page: 3 of 6

Location: SPRINGFIELD

OH

S&E Proj. No.: 10.0993

AFE No.: F10098

Drawing No.: 82111818

Store No.:

P.O. Number:

Date Required:

Date Shipped:

Vendor: Intertail Engineering, INC

Qty.	Class-Item-CD	U	Price per Item	Total Price	Item Description	Quantity Shipped	Quantity Date Quan.	Quantity Date Installed	Quantity Date Returned (Credit)	Special Instructions
6	165-643647-4	EA	\$4.30	\$25.80	LAMP, 18 WATT 10 VOLT S-11 SC BAY 18S11/1SC CLEAR RWY SIGNAL LU-71463 GE					
23	670-440826-4	EA	\$1.01	\$23.23	LINK, SAFETRAN 024620-1X INSL TESTING COMP 1 IN CENTER SIGNAL CIRCUITS CR 02-286662					
6	255-590880-4	EA	\$16.12	\$96.72	LOCK, AMERICAN LOCK MODEL H-10KA KEYPED ALIKE TO PRIVATE KEYWAY D456 AND STAMPED "NS SIG"					
2	670-483458-4	EA	\$6,525.00	\$13,050.00	MAST CANTILEVER 12", W/T/F GATE COMBO, 12' 20' ARM, W/LADDER KIT W/RIGHT HAND OFFSET SAFTRAN P/N 071272-20NS					
4	670-637778-4	EA	\$1,031.41	\$4,125.64	MAST, 5' ALUMINUM 13'10" WITH DOUBLE JCT. BOX BASE. STRAN P# 070519-11AX.					
2	670-850933-4	EA	\$3,352.65	\$6,705.30	MECHANISM, GATE MODEL S-60, WITH DEFROSTER AND MINI TRACKSIDE SENSOR STRAN # 0740007-X002B3					
4	670-001355-4	EA	\$72.59	\$290.36	PACKAGE, HARDWARE SIGN 12 IN. (USE WITH W/T/F MAST) MOUNTING, SERRMI A1250-8, HARMON @ 180004/0007,					
6	670-001347-4	EA	\$63.27	\$379.62	PACKAGE, HARDWARE SIGN 5 IN. MOUNTING, SERRMI A1250-5, HARMON @ 200965-000, OR					
1	670-644144-4	EA	\$201.40	\$201.40	PANEL, SAFETRAN# 91042-19 CABLE TERMINATION PANEL WITH 19 STRAPPED AAR TERMINALS					
4	670-514605-4	EA	\$8.45	\$33.80	PINNUACLE, W-C SECT 1-11, 4" & 5" REF K1 110-8 OR SAFETRAN NO. @035045-503X					
6	670-555609-4	EA	\$45.12	\$270.72	PLUGBOARD, TYPE B-1 GRS A62-506 OR HARMON @ 7062-506 OR					
1	670-427136-4	EA	\$93.49	\$93.49	POWER OFF LAMP INDICATOR FOR SHELTER, SAFETRAN P/N 051958-5					
1	165-018451-4	EA	\$148.50	\$148.50	PROTECTOR, 12VDC, AAR MOUNT LPC 10593-9 LIGHTNING PROTECTION CORP.					
2	165-103293-4	EA	\$62.43	\$124.86	PROTECTOR, LIGHTNING & SURGE LPC 10560-51, 3 ELECTRODE WITH SPADE TERMINAL					
1	165-902002-4	EA	\$308.00	\$308.00	PROTECTOR, SURGE 120/240VAC, ERICO P/N EPD120/240TDFL					
4	670-602559-4	EA	\$112.20	\$448.80	RECTIFIER, ELECTRO-PNEUMATIC TRACK MODEL NO RING-10 TYPE C TRACK CIRCUIT					

APPROVED BY STATE

APPROVED BY RAILROAD

CAR NUMBER

SEAL NUMBER

Monday, February 28, 2007 9:15 AM

Page: 4 of 6

Location: SPRINGFIELD

OH

S&E Proj. No.: 10.0993

AFE No.: F10098

Drawing No.: 82111818

Store No.:

P.O. Number:

Date Required:

Date Shipped:

Vendor: Interrail Engineering, INC

Qty.	Class-Item-CD	UI	Price per item	Total Price	Item Description	Quantity Shipped	Quantity Date	Quantity Installed Date	Quantity Returned (Credit)	Special Instructions
4	465-002899-4	EA	\$22.06	\$88.24	REEL, CABLE DISPOSABLE FOR CROSSING SIGNAL PACKAGES					
1	670-742096-4	EA	\$41.80	\$41.80	RELAY INTERFACE PROBE, ULTRATECH PN 16031-00					
4	670-456936-4	EA	\$150.00	\$600.00	RELAY RACK, SWING, FARADAY SHELTER FOR ONE RELAY, SSFETRAN P/N T15331					
2	670-707995-4	EA	\$313.67	\$627.34	RELAY, TYPE B1, NEW LINE, 900 OHMS, .008 AMPERES GRS A62-308 OR SAFETRAN @400003					
3	670-708018-4	EA	\$353.18	\$1,059.54	RELAY, TYPE B1, NEW LINE, H.D. CONTACTS, 900 OHMS, .008 AMPERES GRS A62-311, SAFETRAN @400022					
1	670-708282-4	EA	\$317.25	\$317.25	RELAY, TYPE B1, TRACK 4 OHM .85A GRS A62-276, STRAN 400011					
1	670-215166-4	EA	\$21.98	\$21.98	RELAY (AC INTERRUPT FOR SEARII) POTTER & BRUMFIELD 120V AC KUMP-14A18-120 SAFETRAN P/N T18354					
2	670-218934-4	EA	\$20.62	\$41.24	RELAY (AC INTERRUPT FOR SEARII) POTTER & BRUMFIELD 12V DC KUMP-14D18-12 SAFETRAN P/N T18353					
6	670-790627-4	EA	\$23.45	\$140.70	RESISTOR ADJUSTABLE 0.63 OHM MINIMUM RESIST 0.068-OHM, ITEM 248 S-500 SAFETRAN P/N 029602-1X					
1	180-000029-4	EA	\$20.83	\$20.83	RESISTOR UNIT, 2W ADJUSTABLE SAFETRAN NO. 029602-6X FOR TRACK CIRCUITS CR 02-425807					
1	180-239123-4	EA	\$20.83	\$20.83	RESISTOR, ADJUSTABLE 5 OHM SAFETRAN NO. 029603-2X FOR TRACK CIRCUITS					
1	670-213363-4	EA	\$5,557.79	\$5,557.79	SCX-1, EPC CONFIG "A", FOR 3 TK. TYPE "C" TRACK SYSTEMS, PLUS EXTRA ISLAND					
1	670-816502-4	EA	\$4,903.75	\$4,903.75	SEARII AUTOMATED INSPECTOR SYSTEM KIT, w/ 1-ILOD, 1-@BELL, 2-GTS, WITHOUT MTSS, 1-GFT, 1-VHFC, 2-RECORDER INTERFACE MODULE, 1-ECHOLON CONNECTOR					
1	670-111783-4	EA	\$516.00	\$516.00	SEARII, (GFT) - GROUND FAULT DETECTOR, SAFETRAN P/N A90297, 1 PER TWO SETS OF BATTERY					
2	670-085658-4	EA	\$373.00	\$746.00	SEARII, (ILOD) - INTELLIGENT LAMP OUT DETECTOR, SAFETRAN P/N A80271, 1 / 20 AMP SSCC, 2 / 40 AMP SSCC					

APPROVED BY STATE

APPROVED BY RAILROAD

CAR NUMBER

SEAL NUMBER

Monday, February 26, 2007 9:15 AM

Page: 5 of 6

Location: SPRINGFIELD OH S&E Proj. No.: 10.0993 AFE No.: F10098 Drawing No.: 82111818
 Store No.: P.O. Number: Date Required: Date Shipped: Vendor: InterRail Engineering, INC

Qty.	Class-Item-CD	UI	Price per Item	Total Price	Item Description	Quantity Shipped	Quantity Date Shipped	Quantity Date Installed	Quantity Date Returned	Quantity Returned (Credit)	Special Instructions
1	670-281280-4	EA	\$7,006.00	\$7,006.00	SHELTER BARE 6X6, ALUMN, FARADAY, W/CABLE CHUTES BEHIND TERMINAL BOARD, W/GEN. CONN. W/ADJUSTABLE PIERS, SAFETRAN P/N 058400-66-78A						
6	670-586967-4	EA	\$37.68	\$226.08	SHUNT COVER W/LAG SCREWS, 19"X19", SERMMI #40271, ORDER 1 PER SHUNT						
4	670-652773-4	EA	\$470.56	\$1,882.24	SHUNT, MULTI-FREQ. #62775-1543 SAFETRAN NARROW BAND						
2	670-393331-4	EA	\$37.43	\$74.86	SIGN CROSSING MALFUNCTION ASSEMBLY FOR 4" AND 5" MAST, SAFETRAN #T17215						
6	670-806648-4	EA	\$56.42	\$338.52	SIGN, X-BUCK, LESS HARDWARE, SAFETRAN 035200-X CR 02-490546						
2	670-353390-4	EA	\$43.04	\$86.08	SIGN, "2 TRACKS" LESS HARDWARE SAFETRAN 035207-2X						
2	670-803355-4	EA	\$32.01	\$64.02	SIGN, "3" TRACK, LESS HARDWARE POWER PARTS						
1	670-330382-4	RL	\$15.68	\$15.68	TAPE, THOR 3" DURATEC, ORANGE 1000' LENGTHS, "WARNING STOP DIGGING"						
23	670-478560-4	EA	\$19.47	\$447.81	TERMINAL BLOCK, ERICO 4 POST P/N B2700A2C1WH W/HARDWARE LESS LIGHTNING ARRESTOR						
6	610-065626-4	EA	\$17.55	\$105.30	ULTRA-TECH 15206-01 CONNECTIVITY BLOCK FOR GRS B1 RELAY						
6	670-007238-4	EA	\$129.46	\$776.76	UNIT, THE INSTALLATION AND WIRING OF A DEVICE WHICH REQUIRE A MINIMUM OF FOUR WIRE CONNECT-						
1	670-255598-4	EA	\$33,124.18	\$33,124.18	WIRED RACK, 6X6 FARADAY, 40AMP DOUBLE TRK SSC0311A, GCP 3000D2, 2 CRAGG CHARGER, 2 RELAY RACKS, SAFTRAN P/N 40A 2TRK, USE WITH I/S 670-281280-4 W/CABLE CHUTES BEHIND THE FARADAY SHIELD						
1	450-986008-4	EA	\$24.84	\$24.84	WRENCH, TEST POST TYPE B DWG 55383-3, GR.1						

Total Material: \$122,737.78

APPROVED BY STATE APPROVED BY RAILROAD CAR NUMBER SEAL NUMBER

TO CP 248
R.R. WEST


TO CP 138
R.R. EAST

INDIANA & OHIO SIDING

INDIANA & OHIO SIDING


UNDERGROUND UTILITIES
TWO WORKING DAYS
BEFORE YOU DIG
CALL 1-800-362-2764 (TOLL FREE)
OHIO UTILITIES PROTECTION SERVICE
NON-MEMBERS
MUST BE CALLED DIRECTLY


IN SERVICE _____ SIGNED _____ DATE _____
☐ S&E ENGINEERING COPY
☐ CONSTRUCTION OFFICE COPY
☐ RETURN TO S&E ENG. AFTER COMPLETION
☐ FIELD COPY
☐ RETURN TO CASE AFTER COMPLETION
☐ PROJECT ENGINEER COPY



- NOTES:
1. MAX. TRAIN SPEED - 50 M.P.H.
 2. LATITUDE N 39° 54' 51" LONGITUDE W 83° 47' 12" ELEVATION 1003'
 3. SIGNAL 'A' TO HAVE BELL.
 4. LOCATE U/G UTILITIES & CABLE BEFORE DIGGING.
 5. CROSSING LOCATED IN CLARK COUNTY.
 6. NEAREST STREET ADDRESS IS 625 BURT ST.
 7. NEAREST INTERSECTING STREET IS SHERIDAN AVE.
 8. DISTANCE TO NEAREST INTERSECTING STREET IS 528. FT.
 9. PRE-EMPTION CIRCUITRY REQUIRED FOR STATE INSTALLATION OF WAYSIDE HORN.
- (A) (B) (C) (D) = QUADRANT MARKERS
* - OFFICE VERIFY DISTANCES

SCALE: 1" = 20'
PROJECT #10-0993
DESIGNED BY: BTM 01-04-07
CHECKED BY: RDO 01-05-07
DATE: 01-04-07
PROJECT: SPRINGFIELD, OH
CFLS/CLS AT BURT ST.
DAYTON DISTRICT
FILE NO. 8211818.01
SHEET 1 of 28





NOTE: ALL AC WIRING IS TO BE IN METALLIC CONDUIT WITH NO EXPOSED TERMINALS. ALL AC 120V AND 240V EQUIPMENT IS TO BE PROPERLY GROUNDED.

SQUARE "D" PART NUMBERS:

LOAD CENTER-----00116L125G

GENERATOR RECEPTACLE;
MALE CONNECTOR - NEMA L1430-F1


MECH INTERLOCK—PK4D11M4LA


MECH INTERLOCK——PK4DTIMALA

REVISION
INITIALS

PROPERTY
PENNSYLVANIA R.R.

DESIGNED BY	BTM 01-04-07	OFFICE OF ASST. VICE PRESIDENT COMM. & SIGNAL, ATLANTA, GA.	M/P	CJ-181.B
DRAWN BY	IRE 01-04-07	SPRINGFIELD, OH CFLOS/FLS AT BLRD. ST.		
CHECKED BY	RDO 01-05-07			
IN SERVICE	- -			
DAYTON DISTRICT		FILE R-		
CADD OR DWG. NO.	8211818.B.04	NO. SHEET	4 of	28





B14-ACR
 B  A
 HEEL 2 A 1
 FRONT 6 5 4
 BACK 3 2 1
 POTTER BUNFIELD
 (REAR VIEW)
 KUMF-14018-12

NOTES:
ALL WIRING TO BE #16AWG
UNLESS NOTED OTHERWISE.
* = CABLE PROVIDED WITH SEAR II

[illegible]

**PANEL - 2" CABLE TERMINATION PANEL
B14 RECTIFIER HOOK-UP**

WS
NORFOLK
SOUTHERN

OFFICE OF ASS'T. VICE PRESIDENT COMM. & SIGNAL, ATLANTA, GA.	MP: CJ-181.8
---	--------------

SPRINGFIELD, OH
CELESTIAL AT BIRTH ST.

DAYTON DISTRICT

CADD or
DWG. No. 82111818.0



EVANS NORFOLK
SOUTHERN

DESIGNED BY:	OFFICE OF ASST. VICE PRESIDENT		MAP	CU-181.8
BTH 01-04-07	COMM. & SIGNAL, ALTANTA, GA.			
DRAWN BY:				
THE 01-04-07				
CHECKED BY:				
RDO 01-05-07				
IN SERVICE:				
-				
SPRINGFIELD, OH				
CROSSINGS AT BURT ST.				
DAYTON DISTRICT				
FILE NO.	R-1			
COORD. SHEET	7 of 28			
DWG. NO.	8211018.07			

● = ECHOLON CONNECTIONS NOT TO EXCEED 53 IN LENGTH AND TOTAL LENGTH NOT TO EXCEED 439' WITH A MAXIMUM OF 8 NODES, RECOMMEND USE BELDEN WIRE CABLE #8461 OR EQUIVALENT.

80063 ADAPTER CARD AND
E-LEVEL OR LATER SOFTWARE
NEEDED FOR SEAR II / ECHOLON
CAPABILITIES.

• = CABLE PROVIDED WITH SEAR IF

ALL WIRING TO BE #16AWG
UNLESS NOTED OTHERWISE.

NOTES

$$T2\text{ IF} = N/A$$
 $\tau_{11f} = 4.0 \text{ KHz}$

30000DZ GCP "A5"

0000DZ GCP .A5

EXPANDED PROGRAMMING

300002 PROGRAMMING CHART	(LEVEL 1)
NUMBER OF TRACK TRANSCIVERS	1
T1: FREQUENCY	285KHZ
T2: FREQUENCY	---KHZ
T1: UNIDIRECTIONAL/BIDIRECTIONAL	BI
T2: UNIDIRECTIONAL/BIDIRECTIONAL	---
T1: XMIT LEVEL (MAX/MED)	MED
T2: XMIT LEVEL (MAX/MED)	---
T1: PREDICTOR/MOTION SENSOR	PRED
T2: PREDICTOR/MOTION SENSOR	---
T1: WARNING TIME	30 Sec
T2: WARNING TIME	---
T1: APPROACH DISTANCE	2522 FT
T2: APPROACH DISTANCE	---
UAX1 PICKUP DELAY (UAX1 0 = OFF)	0 Sec
ENAX1/2 DELAY 10 = ENA1	---
T1: ISLAND DISTANCE	139 FT
T2: ISLAND DISTANCE	---
NUMBER OF DAX'S	0 EQ
DAX A TRACK ASSIGNMENT (T1/T2)	---
DAX A DISTANCE 10 = PREEMPT	FT
DAX A WARNING TIME	---
DAX B TRACK ASSIGNMENT (T1/T2)	---
DAX B DISTANCE 10 = PREEMPT	FT
DAX B WARNING TIME	---
DAX C TRACK ASSIGNMENT (T1/T2)	---
DAX C DISTANCE 10 = PREEMPT	FT
DAX C WARNING TIME	---
DAX D TRACK ASSIGNMENT (T1/T2)	---
DAX D DISTANCE 10 = PREEMPT	FT
DAX D WARNING TIME	---
SLAVING MASTER/SLAVE	MASTER
PASSWORD ENABLED	NO
RECORDER INSTALLED	NO

T1: SWITCH TO MS (ENTER EZ VALUE)	10 %
T2: SWITCH TO MS (ENTER EZ VALUE)	---
T1: TRANSFER DELAY MS TO GCP 10 = OFF	0 Sec
T2: TRANSFER DELAY MS TO GCP 10 = OFF	---
T1: TRANSFER MS TO GCP PRIME (ON/OFF)	---
T2: TRANSFER MS TO GCP PRIME (ON/OFF)	---
T1: TRANSFER MS TO GCP DAX A (ON/OFF)	---
T2: TRANSFER MS TO GCP DAX A (ON/OFF)	---
T1: TRANSFER MS TO GCP DAX B (ON/OFF)	---
T2: TRANSFER MS TO GCP DAX B (ON/OFF)	---
T1: TRANSFER MS TO GCP DAX C (ON/OFF)	---
T2: TRANSFER MS TO GCP DAX C (ON/OFF)	---
T1: TRANSFER MS TO GCP DAX D (ON/OFF)	---
T2: TRANSFER MS TO GCP DAX D (ON/OFF)	---
T1: PRIME PREDICTION OFFSET 10 = OFF	0 FT
T2: PRIME PREDICTION OFFSET 10 = OFF	---
PICKUP DELAY PRIME	15 Sec
PICKUP DELAY DAX A	---
PICKUP DELAY DAX B	---
PICKUP DELAY DAX C	---
PICKUP DELAY DAX D	---
T1: ENHANCED DETECTION (ON/OFF)	OFF
T2: ENHANCED DETECTION (ON/OFF)	---
BACK-TO-BACK T1 AND T2 (NO/YES)	---
T1: STATION STOP TIMER	10 Sec
T2: STATION STOP TIMER	---
T1: NUMBER OF TRACK WIRES (4/6)	4
T2: NUMBER OF TRACK WIRES (4/6)	---
T1: LOW EX ADJUSTMENT	0
T2: LOW EX ADJUSTMENT	---
T1: LOW EZ DETECTION	OFF
T2: LOW EZ DETECTION	---
T1: LOW EZ DETECTION TIMER (ON/OFF)	10 Min
T2: LOW EZ DETECTION TIMER (ON/OFF)	---
T1: POSITIVE START (EZ LEVEL 10 = OFF)	0
T2: POSITIVE START (EZ LEVEL 10 = OFF)	---
T1: POSITIVE START TIMEDOUT 10 = NONE1	---
T2: POSITIVE START TIMEDOUT 10 = NONE1	---
SET AT OPERATION (NORMAL/DIAGNOSTIC)	NORMAL
DIAGNOSTIC MESSAGES (ON/OFF)	ON
DAX MESSAGES (ON/OFF)	ON
ADVANCE PREEMPT TIMER 10 = OFF	0 %
T1: MOTION SENSING LEVEL 10 = NORMAL	0 %
T2: MOTION SENSING LEVEL 10 = NORMAL	---

* = 1ST SLOT AT LEFT END OF BAY

MODEL 300002 GCP MODULE ASSEMBLIES

MODULES POSITION	UPPER BAY	LOWER BAY
M1	M1	M1
M2	M2	M2
M3	M3	M3
M4	M4	M4
M5	M5	M5
M6	M6	M6
M7	M7	M7
M8	M8	M8
M9	M9	M9
M10	M10	M10
M11	M11	M11
M12	M12	M12
M13	M13	M13
M14	M14	M14
M15	M15	M15
M16	M16	M16
M17	M17	M17
M18	M18	M18
M19	M19	M19
M20	M20	M20
M21	M21	M21

NOTES:

1 - SEE IP1 INSTRUCTION AND INSTALLATION MANUAL FOR 8021 ISLAND CALIBRATION PROCEDURE.

2 - TOGGLE SWITCH ON MOTION BOARD DOWN = SINGLE FREQ.


** = 80214 & 80255 (WITH JUMPER) CARDS AND E-LEVEL OR LATER SOFTWARE NEEDED FOR SEARCH II / ECHOLON CAPABILITIES.


PANEL 'A5' 300002 GCP SET-UP

DESIGNED BY: BTM 01-04-07
 CHECKED BY: JRE 01-04-07
 RDO 01-05-07
 IN SERVICE: ☐ ☒

OFFICE OF ASST. VICE PRESIDENT FOR COMM. & SIGNAL, ATLANTA, GA.
 SPRINGFIELD, OH
 CPGS/PLS AT BURT ST.
 DAYTON DISTRICT
 CADG OF: 8211818.08
 SHEET: 8 of 28

PROPERTY: PENNSYLVANIA R.R.





STYLE "C" & EXTERNAL RELAY CIRCUITS

DESIGNED BY:										 NS NORFOLK SOUTHERN									
BTH 01-04-07										OFFICE OF ASST. VICE PRESIDENT									
DRAWN BY:										CONG. & SIGNAL, ATLANTA, GA.									
JRE 01-04-07										M.P.: CJ-181.8									
CHECKED BY:										SPRINGFIELD, OH CFCOS/FLS AT BURT ST.									
R00 01-05-07										DAYTON DISTRICT									
IN SERVICE:										FILE R-									
-										CARD or SHEET NO. 82111818.10									
										SHEET 10 of 28									



DESIGNED BY:	NCS NORTH CAROLINA SOUTHERN		
BTH 01-04-07	OFFICE OF ASST. VICE PRESIDENT		
DRAWN BY:	COMM. & SIGNAL, ATLANTA, GA.		
IRE 01-04-07	CHGS./FLS AT BMT ST.		
CHECKED BY:	SPRINGFIELD, OH		
ROO 01-05-07	DAYTON DISTRICT		
IN SERVICE:	FILE R-	NO.	W.P. C-191.8
-	CADD OF	SHEET	13 of 28
-	CMC. NO.	NO.	
	B2111818.13		

PROGRAM	
FLASHER RATE	40
1 GC DELAY	4 SEC.
2 GC DELAY	4 SEC.
BELL-ON GATE RISING	OFF
MIN ACTIVATION TIME	0 SEC.
ENABLE INPUTS	1 THRU 1
ENABLE OUTPUTS	A AND B
TIME	
DATE	
DAYLIGHT SAVINGS	ON
PASSWORD	DISABLED
SET TO DEFAULT	SKIP


SETUP LAMP VOLTAGE	
SETUP OUTPUT 1L1 XX.X VOLTS	
SETUP OUTPUT 1L2 XX.X VOLTS	
SETUP OUTPUT 2L1 XX.X VOLTS	
SETUP OUTPUT 2L2 XX.X VOLTS	

CONFIGURE	
1: 0 SEC.	
2: 0 SEC.	
3: 0 SEC.	
4: 0 SEC.	
5: 0 SEC.	
6: 0 SEC.	
7: 0 SEC.	
ATCS ADDRESS	756023402107
LOW BATTERY	DISABLED
AUX I/O	INV OUTPUT


TEST CONFIGURE	
LAMP TEST CANCEL TIMER	5 MIN.
LAMP TEST DELAY TIMER	30 SEC.
LAMP TEST ON TIMER	15 SEC.

PANEL 'A2' CROSSING CONTROLLER SET-UP CHART


DESIGNED BY: BTM 01-04-07		DRAWN BY: JRE 01-04-07		CHECKED BY: RDO 01-05-07		IN SERVICE: -	
				OFFICE OF ASST. VICE PRESIDENT COMM. & SIGNAL, ATLANTA, GA.			
DAYTON DISTRICT SPRINGFIELD, OH CLEVELANDS AT BURT ST.				FILE R- SHEET 14 of 28			
REVISION INITIALS		PROPERTY		PENNsylvania R.R.			



'A' TIP FLASHING LIGHTS







'F' TIP FLASHING LIGHTS



CANTILEVER FLASHER LIGHTS

DESIGNED BY:	BTH 01-04-07	NO. OF SHEETS:	17 of 28
DRAWN BY:	IRE 01-04-07	FILE NO.:	R-17
CHECKED BY:	RDO 01-05-07	DATE:	01-18-17
IN SERVICE:		NO. OF SHEETS:	17 of 28
PROPERTY:	PENNSYLVANIA R.R.	DATE:	01-18-17
REVISION:		NO. OF SHEETS:	17 of 28





FLASHER LIGHTS

DESIGNED BY:	BTM 01-04-07	NO. 1	FILE R-
DRAWN BY:	IRE 01-04-07	NO. 2	FILE R-
CHECKED BY:	RDO 01-05-07	NO. 3	FILE R-
IN SERVICE:	DAYTON DISTRICT	NO. 4	FILE R-
PROPERTY:	PENNSYLVANIA R.R.	NO. 5	FILE R-
REVISION:		NO. 6	FILE R-
INITIALS:		NO. 7	FILE R-
		NO. 8	FILE R-
		NO. 9	FILE R-
		NO. 10	FILE R-
		NO. 11	FILE R-
		NO. 12	FILE R-
		NO. 13	FILE R-
		NO. 14	FILE R-
		NO. 15	FILE R-
		NO. 16	FILE R-
		NO. 17	FILE R-
		NO. 18	FILE R-
		NO. 19	FILE R-
		NO. 20	FILE R-
		NO. 21	FILE R-
		NO. 22	FILE R-
		NO. 23	FILE R-
		NO. 24	FILE R-
		NO. 25	FILE R-
		NO. 26	FILE R-
		NO. 27	FILE R-
		NO. 28	FILE R-

LEFT TWO ROWS TERMINAL BOARD 1

"1A"

"1B"



NOTE: INSTALL TEST LINKS ON ALL TRACK WIRES AND ON ALL LOW VOLTAGE UNDERGROUND CABLE TERMINATIONS.

SEE FARADAY SHIELD DETAILS - 1A & 1B FOR HOW THIS PORTION OF THE FARADAY SHIELD IS PREDRILLED. ONLY INSTALL AND USE THE TERMINALS NEEDED.

⚡ = Heavy Duty Equalizer (822700-1X)
 ⚡ = Lightning Arrestor (822585-1X)
 ⚡ = LPC-10560-51

Ⓞ = TERMINALS GROUNDED TO SHIELD.
 4 POST BLOCKS USE EITHER -
 CR - SERIAL PART NO. 61278
 CL - SERIAL PART NO. 61278-1.

REVISION	INITIALS	PROPERTY	DATE
		PENNSYLVANIA R.R.	

DESIGNED BY:	DATE:	FILE NO.
BTH 01-04-07	01-04-07	82111818.21
DRAWN BY:	DATE:	FILE NO.
IRE 01-04-07	01-04-07	82111818.21
CHECKED BY:	DATE:	FILE NO.
RDO 01-05-07	01-05-07	82111818.21
IN SERVICE:	DATE:	FILE NO.

DAYTON DISTRICT	FILE NO.
SPRINGFIELD, OH	82111818.21
CFLGS/PLS AT BURT ST.	
NO. 21 of 28	



BACKBOARD DETAIL - 1A & 1B

NORFOLK SOUTHERN

OFFICE OF ASST. VICE PRESIDENT
 COMM. & SIGNAL, ATLANTA, GA.

MP-4 CJ-181.8

REAR VIEW OF LEFT TWO ROWS TERMINAL BOARD I
 "1B" "1A"



NOTE: ALL 120VAC AND ABOVE WILL BE WIRED
 TO THE REAR OF FARADAY BACKBOARD.
 INSULATED NUTS MUST BE USED ON ALL
 TERMINALS.

* = CLOSED DURING WINTER MONTHS




REAR OF FARADAY BACKBOARD
 REAR BACKBOARD DETAIL - 1A & 1B

DESIGNED BY: BTH 01-04-07	OFFICE OF ASST. VICE PRESIDENT COMM. & SIGNAL, ATLANTA, GA.	FILE NO. CJ-181.8
DRAWN BY: HRE 01-04-07	SPRINGFIELD, OH	FILE NO. R-
CHECKED BY: RDO 01-05-07	CFLGS./FLS AT BURT ST.	SHEET NO. 22 of 28
IN SERVICE:	DAYTON DISTRICT	
CAD OF DRG. NO. 8211818-22		

REVISIONS
 INITIALS
 PROPERTY
 PENNSYLVANIA R.R.

RIGHT ROW TERMINAL BOARD 1

"1C"



NOTE: INSTALL TEST LINKS ON ALL TRACK WIRES AND ON ALL LOW VOLTAGE UNDERGROUND CABLE TERMINATIONS.

SEE FARADAY SHIELD DETAILS - 1A & 1B FOR HOW THIS PORTION OF THE FARADAY SHIELD IS PREDRILLED. ONLY INSTALL AND USE THE TERMINALS NEEDED.

GR

GR = TERMINALS GROUNDED TO SHIELD.
A POST BLOCKS USE EITHER -
GR - SERMI PART NO. 61278
DL - SERMI PART NO. 61278-1.

DL = LPC-10560-51

DL = Lightning Arrestor
(022585-1X)

DL = Heavy Duty Equalizer
(022100-1X)

BACKBOARD DETAIL - 1C

REVISION
INITIALS

PROPERTY
PENNSYLVANIA R.R.

DESIGNED BY:	BTM 01-04-07
DRAWN BY:	IRE 01-04-07
CHECKED BY:	RDO 01-05-07
IN SERVICE:	-
DATE OF DWG. NO.	DAYTON DISTRICT 8211816.23
FILE NO.	FILE R- 23 of 28
NO. OF SHEET	23 of 28

NS NORFOLK
SOUTHERN

OFFICE OF ASST. VICE PRESIDENT
COMM. & SIGNAL, ATLANTA, GA.
U.P.S. C-181.8

SPRINGFIELD, OH
CFLCS/FLS AT BURT ST.


TERMINAL BOARD 1 LEFT HALF

"1A"

"1B"

2" PANDUIT

2" PANDUIT



NOTE: IF THE FARADAY SHIELD WOULD EVER NEED TO BE DRILLED IN THE FIELD, PROPER PRECAUTIONS MUST BE TAKEN TO INSURE METAL SHAVINGS DO NOT GET INTO EXISTING TERMINALS/WIRES.

AREA BELOW IS SCALED WITH AS=75

= INDICATES PLACEMENT OF PANDUIT

THIS SHEET IS FOR REFERENCE ONLY, TO REFLECT HOW THE FARADAY SHIELD IS PREDRILLED, ONLY INSTALL AND USE THE TERMINALS NEEDED.



TERMINALS GROUNDED TO SHIELD.
4 POST BLOCKS USE EITHER -
CR - SERMAN PART NO. 61278
CL - SERMAN PART NO. 61278-1.



L = Lightning Arrester
(022585-1X)



Heavy Duty Equalizer
(022100-1X)

REVISION INITIALS

PROPERTY PENNSYLVANIA R.R.


DESIGNED BY:	BTM 01-04-07
DRAWN BY:	OFFICE OF ASST. VICE PRESIDENT
CHECKED BY:	COMM. & SIGNAL, ATLANTA, GA.
IN SERVICE:	FILE NO. 24 of 28
DAYTON DISTRICT	SPRINGFIELD, OH
CADD NO. B211818.24	CPLGS/PLS AT BURT ST.
NO. 24 of 28	

TERMINAL BOARD 1
LEFT TWO ROWS
FARADAY SHIELD DETAIL - 1A & 1B

NORFOLK SOUTHERN

TERMINAL BOARD 1 RIGHT HALF

1C



NOTE: IF THE FARADAY SHIELD WOULD EVER NEED TO BE DRILLED IN THE FIELD, PROPER PRECAUTIONS MUST BE TAKEN TO INSURE METAL SHAVINGS DO NOT GET INTO EXISTING TERMINALS/WIRES.

AREA BELOW IS SCALED WITH AS-75

INDICATES PLACEMENT OF PANDUIT

THIS SHEET IS FOR REFERENCE ONLY, TO REFLECT HOW THE FARADAY SHIELD IS PREDRILLED, ONLY INSTALL AND USE THE TERMINALS NEEDED.

CR

TERMINALS GROUNDED TO SHIELD.
4 POST BLOCKS USE EITHER -
CR - SERIAL PART NO. 61278 -
CL - SERIAL PART NO. 61278-1.

CL



Lighting Arrestor
(022585-1X)
LPC-10560-51


F

Heavy Duty Equalizer
(022100-1X)

TERMINAL BOARD 1
RIGHT ROW
FARADAY SHIELD DETAIL - 1C

REVISION	INITIALS	PROPERTY	PENNSYLVANIA R.R.	DESIGNED BY	DATE	OFFICE OF ASST. VICE PRESIDENT	FILE NO.	FILE R.	SHEET	25 of 28
				BTB	01-04-07	COMM. & SIGNAL, ATLANTA, GA.	CU-181.8			
				DRAWN BY	01-04-07	SPRINGFIELD, OH				
				CHECKED BY	01-05-07	CFLGS/FLS AT BURT ST.				
				IN SERVICE		DAYTON DISTRICT				
						DAYTON DISTRICT				
						DAYTON DISTRICT				





DESIGNED BY:	BTB	01-04-07
DRAWN BY:	IRE	01-04-07
CHECKED BY:	RDO	01-05-07
IN SERVICE:		
CADD OF:	DAYTON DISTRICT	FILE R-
DRG. NO.:	8211818-27	SHEET 27 OF 28

6' X 6' HOUSE - SIDE 'A'

NORFOLK SOUTHERN

OFFICE OF ASST. VICE PRESIDENT M.P.4 C-181.8
COMM. & SIGNAL, ATLANTA, GA.

SPRINGFIELD, OH
CFLGS/FLS AT BURT ST.



REVISION
INITIALS

PROPERTY
PENNSYLVANIA R.R.

DESIGNED BY:	BTH 01-04-07
DRAWN BY:	IRE 01-04-07
CHECKED BY:	RDO 01-05-07
IN SERVICE:	
DAYTON DISTRICT	FILE R-
CADD OF 8211818.28	SHEET 28 of 28
OFFICE OF ASST. VICE PRESIDENT	COMM. & SIGNAL, ATLANTA, GA.
SPRINGFIELD, OH	CFGS/PLS AT BURT ST.

