# BEFORE THE PUBLIC UTILITIES COMMISSION OF OHIO

In the matter of the Annual Report of the	~	- 1	
Electric Service and Safety Standards,	<u> </u>	Case No: '	Case No: 18 -0999 - EL-ESS
Pursuant to Rule 4901:1-10-26(B) of the Ohio	~		
Administrative Code	~		

# ANNUAL REPORT OF Duke Energy Ohio submitted for the year 2017.

I certify that the following report accurately and completely reflects the annual report requirements pursuant to Rule 4901:1-10-26 of the Ohio Administrative Code.

AMES SOCHACKI 3/28/2018 **Printed Name** ESIDENT CONSTIUCTION & MAINT. Signature

# THE PUBLIC UTILITIES COMMISSION OF OHIO BEFORE

In the matter of the Annual Report of the	<u> </u>	
Electric Service and Safety Standards,	~	Case No: 18 -0999 -EL-ESS
Pursuant to Rule 4901:1-10-26(B) of the Ohio	<u> </u>	
Administrative Code	<u> </u>	

# submitted for the year 2017. ANNUAL REPORT OF Duke Energy Ohio

I certify that the following report accurately and completely reflects the annual report requirements pursuant to Rule 4901/1-10-26 of the Ohio Administrative Code.

Signature

Printed Name

3-28-18 Date

1. 4901:1-10-26(B)(1), (B)(1)(b), (B)(1)(c) Future investment plan for facilities and equipment, covering period of no less than three years

Identification of project, program, or plan	Transmission or Distribution	Project description and goals	Portion of service territory affected	Characteristics of territory affected	Estimated cost	Initiation Date	Planned Completion Date
TOH1928	Transmission	Fransmission Garver 138kV Expansion	North	Rural/Suburban	\$18,823,339	10/30/2017	6/1/2021
TOH2041	Transmission	Ford-Sharonville Install Ring Bus	North	Rural/Suburban	\$5,852,437	12/30/2017	6/30/2020

1a. 4901:1-10-26(B)(1), (B)(1)(a) Relevant characteristics of the service territory

	Underground Miles Notable Characteristics	4,149	
		4	
	Overhead Miles	8,196	1,373
Transmission	or Distribution	Distribution	Transmission

1b. 4901:1-10-26(B)(1) Future investment plan for facilities and equipment

Transmission						
or	2017	2017	2018	2019	2020	2021
Distribution	Planned Costs	Actual Costs	Planned Costs	Projected Costs	Projected Costs	Projected Costs
Distribution	\$183,096,885	\$211,173,620	\$198,746,203	\$217,108,157	\$219,166,164	\$223,025,284
Transmission	\$101,327,318	\$78,447,238	\$118,544,683	\$118,873,870	\$128,759,088	\$124,466,185

# Rule 26 Report for 2017 **Duke Energy Ohio**

# 2. 4901:1-10-26(B)(1)(d), (B)(1)(f) Complaints from other entities

If not resolved, why?	N/A
Date complaint resolved	Duke Energy was informed the matter was resolved on Orthher 6 2017
Resolved (yes/no)	Yes
Action taken to address complaint	None
Nature of complaint	Unknown
Entity making Date complaint complaint	Duke Energy was made aware of the complaint on October 6, 2017
Entity making complaint	Unknown

Notes: Duke Energy was made aware, by NERC via email, of a complaint on October 6, 2017. No details were provided regarding the nature of the complaint, its origins, or its applicability to interests in Ohio.

NERC does not plan any further action on this item.

3a. 4901:1-10-26(B)(1)(e), (B)(1)(f) Electric Reliability Organization standards violations

Standard number	Standard name	Date of violation	Risk factor	Severity factor	Penalty dollars	Violation description	Resolved (yes/no)	Date resolved	If not resolved, why?
CIP-004-6, R2.2.	Cyber Security - Personnel & Training	3/8/2017	Pending	Pending		Confidential, non-public information			
CIP-004-6, R5.1.	Cyber Security - Personnel & Training	4/13/2017	Pending	Pending		Confidential, non-public information			
CIP-006-6, R1.4.	Cyber Security - Physical Security of BES Cyber Systems	4/28/2017	Pending	Pending		Confidential, non-public information			
CIP-011-2, R1.1.,R1.2.	Cyber Security - Information Protection	6/30/2017	Pending	Pending		Confidential, non-public information			

3b. 4901:1-10-26(B)(1)(e), (B)(1)(f) Regional Transmission Organization (RTO) violations

If not resolved,	why?
Date	resolved
Resolved	(yes/no)
Violation	description
Name of RTO	violation

Notes: There were no RTO Violations in 2017

3c. 4901:1-10-26(B)(1)(e) Transmission Load Relief (TLR) events

		Description of event	
Amount of	load (MW)	interrupted	
rirm load	interrupted	during event	
	Highest TLR	during event	
		Event End	
		Event Start	

Notes: There were no TLR Events in 2017

Rule 26 Report for 2017 **Duke Energy Ohio** 

3d. 4901:1-10-26(B)(1)(e) Top ten congestion facilities by hours of congestion

Rank

Description of facility causing congestion

Notes: There were no congested facilities in 2017

3e. 4901:1-10-26(B)(1)(e) Annual System Improvement Plan and Regional Transmission Operator Expansion Plan

Relationship between annual system improvement plan and RTO transmission expansion plan

Notes: No such relationship in 2017

9

4. 4901:1-10-26(B)(2) Report of implementation plans from previous reporting periods

Identification of project, program, or plan	Transmission or Distribution	Planned Completion Date	Actual Completion Date	Identification of deviation from previous plan	Reason for deviation from previous plan
AMOH0616	Distribution	3/1/2017	10/16/2017	Planned Completion date changed	Permit delayed by Sycamore Twp
X04C7993	Transmission	6/1/2018		Planned Completion date changed	Weather delayed completion, waiting to schedule customer outage
AMOH0194	Transmission	12/31/2017	5/12/2017		
X14C8959	Distribution	5/2/2018			
TOH1455	Transmission	6/1/2018			
TOH1488	Transmission	12/31/2018			
TOH1409	Transmission	12/31/2018			
TOH1423	Transmission	12/31/2018			
DOH1598	Distribution	3/1/2019			
TOH1504	Transmission	6/1/2019			
TOH1848	Transmission	12/31/2019			
TOH1072	Transmission	12/31/2020			
TOH1605	Transmission	12/31/2020			
T0H1442	Transmission	12/31/2020			
TOH1443	Transmission	12/31/2020			
DOH1651	Distribution	10/26/2021			
TOH1439	Transmission	12/31/2021			

#### Notes:

# 5. 4901:1-10-26(B)(3), (B)(3)(a) Characterization of condition of company's system

Explanation of criteria used in making assessment for each characterization	Scheduled inspections	Scheduled inspections
Qualitative characterization of condition of system	The condition of the Duke Energy Ohio electric system meets or exceeds industry standards and customer expectations for delivery of safe and reliable electric service. Duke Energy Ohio recognizes that the electric system infrastructure continues to age, and on-going preventive maintenance and corrective actions are necessary. Duke Energy Ohio continues to strive to provide safe and reliable electric service to our customers at a reasonable price. The quality of electric service and the condition of the electric system will parallel each other. Therefore, the quality of electric service can be used to measure the condition of the electric system.	The condition of the Duke Energy Ohio electric system meets or exceeds industry standards and customer expectations for delivery of safe and reliable electric service. Duke Energy Ohio recognizes that the electric system infrastructure continues to age, and on-going preventive maintenance and corrective actions are necessary. Duke Energy Ohio continues to strive to provide safe and reliable electric service to our customers at a reasonable price. The quality of electric service and the condition of the electric system will parallel each other. Therefore, the quality of electric service can be used to measure the condition of the electric system.
Transmission or Distribution	Transmission	Distribution

Duke Energy Ohio Rule 26 Report for 2017

6. 4901:1-10-26(B)(3), (B)(3)(b) Safety and reliability complaints

Total Complaints	379
Public Safety	2
Repair Service	7-
Quality of Service	191
Out of Service	0
Momentary Interruption	27
Damage	۲
Availability of Service	157
Transmission Availabilit or of Distribution Service	Distribution

7a. 4901:1-10-26(B)(3)(c), (B)(3)(c)(i) Transmission capital expenditures

Total transmission capital expenditures in 2017	\$78,447,238
Total Transmission investment as of year end	\$809,377,209
Transmission capital expenditures as % of total transmission investment	%69.6

Notes:

# 7b. 4901:1-10-26(B)(3)(c), (B)(3)(c)(i) Transmission maintenance expenditures

Total transmission maintenance expenditures in 2017	\$8,318,473
Total Transmission investment as of year end	\$809,377,209
Transmission maintenance expenditures as % of total transmission investment	1.03%

7c. 4901:1-10-26(B)(3), (B)(3)(c)(ii), (B)(3)(c)(iii) Transmission capital expenditures - Reliability specific

Transmission capital budget category	2017 Budget	2017 Actual	% Variance	Explanation of variance if over 10%	2018 Budget
Major Cap and R&I	\$17,259,383	\$30,831,061	78.63%	Increased spend in capacity, inactive line removals and retail capacity.	\$21,009,260
Region Reliability & Integrity	\$72,879,506	\$34,765,308	-52.30%	Less Transmission FERC spend in NERC CIP due to more Distribution FERC work. Less spend in Asset Management programs due to outage scheduling and resource availability.	\$80,171,863
Vegetation Management	\$1,205,824	\$2,374,762	96.94%	More vegetation line clearing than budgeted.	\$2,768,618

7d. 4901:1-10-26(B)(3), (B)(3)(c)(ii), (B)(3)(c)(iii) Transmission maintenance expenditures - Reliability specific

Transmission maintenance budget category	2017 Budget	2017 Actual	% Variance	Explanation of variance if over 10%	2018 Budget
Insp/Maint Prog	\$2,249,126	\$1,471,146	-34.59%	Preventive/Corrective maintenance cycles	\$6,731,948
Project O&M	\$1,901,131	\$1,995,173	4.95%		\$9,572,834
Vegetation Management	\$2,780,122	\$3,169,497	14.01%	Non-NERC herbicide program	\$21,835,484

# 8a. 4901:1-10-26(B)(3)(d), (B)(3)(d)(i) Distribution capital expenditures

Total distribution capital expenditures in 2017	\$231,250,932
Total distribution investment as of year end	\$2,553,244,981
Distribution capital expenditures as % of total distribution investment	%90'6

Notes:

# 8b. 4901:1-10-26(B)(3)(d), (B)(3)(d)(i) Distribution maintenance expenditures

2.41%	Distribution maintenance expenditures as % of total distribution investment
\$2,553,244,981	Total distribution investment as of year end
\$61,535,675	Total distribution maintenance expenditures in 2017

8c. 4901:1-10-26(B)(3), (B)(3)(d)(ii), (B)(3)(d)(iii) Distribution capital expenditures - Reliability specific

Distribution capital budget category	2017 Budget	2017 Actual	% Variance	Explanation of variance if over 10%	2018 Budget
Major Cap and R&I	\$36,048,053	\$43,102,355	19.57%	Change in labor strategy that resulted in use of contract labor on Time and Equipment (T&E)	\$39,941,901
Region Reliability & Integrity	\$101,215,562	\$110,278,805	8.95%		\$109,801,432
√egetation Management	\$4,961,992	\$1,989,009	-59.92%	Resources allocated to circuit maintenance	\$5,487,087

8d. 4901:1-10-26(B)(3), (B)(3)(d)(ii), (B)(3)(d)(iii) Distribution maintenance expenditures - Reliability specific

Distribution maintenance budget category	2017 Budget	2017 Actual	% Variance	Explanation of variance if over 10%	2018 Budget
Insp/Maint Prog	\$4,933,541	\$5,373,565	8.92%		\$6,731,948
Project O&M	\$6,533,911	\$12,662,829	93.80%	Increased maintenance spending due to increase in capital spend	\$9,572,834
Region Reliability & Integrity	\$1,620,817	\$1,509,038	-6.90%		\$1,610,872
Vegetation Management	\$12,178,220	\$21,717,920	78.33%	Higher circuit maintenance costs	\$21,835,484

9. 4901:1-10-26(B)(3)(e) Average remaining depreciation life of distribution and transmission facilities

Transmission or Distribution	Asset type	FERC account/ subaccount	Total depreciable life of asset	Total depreciated life of asset	Total remaining life of asset	Percent of remaining life of asset	How age was determined	
Distribution	Structures and Improvements	361	65.00	14.00	51.00	78.46%	Case No. 12-1683-EL-AIR	
Distribution	Station Equipment	362	00.09	15.00	45.00	75.00%	Case No. 12-1683-EL-AIR	
Distribution	Major Equipment	3622	00.09	18.00	42.00	70.00%	Case No. 12-1683-EL-AIR	
Distribution	Distribution Station Equipment	3635	20.00	0.00	20.00	100.00%	Case No. 12-1683-EL-AIR	
Distribution	Poles, Towers and Fixtures	364	20.00	13.00	37.00	74.00%	Case No. 12-1683-EL-AIR	
Distribution	Overhead Conductors and Devices	365	20.00	9.00	44.00	88.00%	Case No. 12-1683-EL-AIR	
Distribution	Underground Conduit	366	65.00	14.00	51.00	78.46%	Case No. 12-1683-EL-AIR	
Distribution	Underground Conduit and Devices	367	58.00	11.00	47.00	81.03%	Case No. 12-1683-EL-AIR	
Distribution	Line Transformers	368/3681	42.00	15.00	27.00	64.29%	Case No. 12-1683-EL-AIR	
Distribution	Customer Transformer Install	3682	45.00	33.00	12.00	26.67%	Case No. 12-1683-EL-AIR	
Distribution	Services - Underground	3691	65.00	14.00	51.00	78.46%	Case No. 12-1683-EL-AIR	
Distribution	Services - Overhead	3692	43.00	12.00	31.00	72.09%	Case No. 12-1683-EL-AIR	
Distribution	Services - Multi Occupancy	3693	0.00	0.00	0.00	0.00%	Case No. 12-1683-EL-AIR	
Distribution	Meters / Leased Meters	370/3701	19.00	19.00	0.00	0.00%	Case No. 12-1683-EL-AIR	
Distribution	Meters - Utility of Future (Smart)	3702	15.00	3.00	12.00	80.00%	Case No. 12-1683-EL-AIR	
Distribution	Company Owned Outdoor Lighting	3710/3712	15.00	15.00	0.00	%00.0	Case No. 12-1683-EL-AIR	
Distribution	Leased Property on Customer Premises	372	25.00	25.00	0.00	%00.0	Case No. 12-1683-EL-AIR	

9. 4901:1-10-26(B)(3)(e) Average remaining depreciation life of distribution and transmission facilities

Transmission or Distribution	Asset type	FERC account/ subaccount	Total depreciable life of asset	Total depreciated life of asset	Total remaining life of asset	Percent of remaining life of asset	How age was determined	
Distribution	Street Lighting - Overhead	3731	28.00	38.00	-10.00	-35.71%	Case No. 12-1683-EL-AIR	
Distribution	Street Lighting - Boulevard	3732	45.00	13.00	32.00	71.11%	Case No. 12-1683-EL-AIR	
Distribution	Street Lighting - Customer Private Outdoor	3733	30.00	75.00	45.00	-150.00%	Case No. 12-1683-EL-AIR	
Transmission	Structures and Improvements	352	90.09	9.00	51.00	85.00%	Case No. 08-709-EL-AIR	
Transmission	Structures and Improvements - CD/CCD	352	00.00	23.00	37.00	61.67%	Case No. 08-709-EL-AIR	
Transmission	Structures and Improvements - CGE - Ky	352	90.00	28.00	32.00	53.33%	Case No. 08-709-EL-AIR	
Transmission	Station Equipment	3530	53.00	8.00	45.00	84.91%	Case No. 08-709-EL-AIR	
Transmission	Station Equipment - Major Equipment	3532	55.00	19.00	36.00	65.45%	Case No. 08-709-EL-AIR	
Transmission	Station Equipment - RTU	3535	20.00	0.00	20.00	100.00%	Case No. 08-709-EL-AIR	
Transmission	Towers & Fixtures	354	80.00	61.00	19.00	23.75%	Case No. 08-709-EL-AIR	
Transmission	Towers & Fixtures - CD/CCD	354	80.00	0.00	80.00	100.00%	Case No. 08-709-EL-AIR	
Transmission	Towers & Fixtures - CGE - Ky	354	80.00	0.00	80.00	100.00%	Case No. 08-709-EL-AIR	
Transmission	Poles and Fixtures	355	55.00	10.00	45.00	81.82%	Case No. 08-709-EL-AIR	
Transmission	Poles and Fixtures - CD/CCD	355	55.00	0.00	55.00	100.00%	Case No. 08-709-EL-AIR	
Transmission	Poles and Fixtures - CGE - Ky	355	55.00	0.00	92.00	100.00%	Case No. 08-709-EL-AIR	
Transmission	Overhead Conductors and Devices	356	62.00	18.00	44.00	70.97%	Case No. 08-709-EL-AIR	

Duke Energy Ohio Rule 26 Report for 2017

9. 4901:1-10-26(B)(3)(e) Average remaining depreciation life of distribution and transmission facilities

Transmission or Distribution	Asset type	FERC account/ subaccount	Total depreciable life of asset	Total depreciated life of asset	Total remaining life of asset	Percent of remaining life of asset	How age was determined
Transmission	Overhead Conductors and Devices - CD/CCD	356	62.00	0.00	62.00	100.00%	Case No. 08-709-EL-AIR
Transmission	Overhead Conductors and Devices - CGE - Ky	356	62.00	4.00	58.00	93.55%	Case No. 08-709-EL-AIR
Transmission	Underground Conduit	357	65.00	38.00	27.00	41.54%	Case No. 08-709-EL-AIR
Transmission	Underground Conduit and Devices	358	45.00	15.00	30.00	%29.99	Case No. 08-709-EL-AIR

10. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i) Inspection, maintenance, repair, and replacement of distribution, transmission, and substation programs summary report

#### Notes:

10a. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) If response in Column "Goals achieved?" of Report 10 is "Yes"

Program Name	Explanation of how goals were achieved	Quantitative description of goal achieved	Summary of Findings
Capacitor Maintenance	Automated capacitors have health check, non- electronic capacitors have "walking" inspection	In 2017, all 2191 capacitors were inspected (194 non- electronic, 1,997 electronic) - 100% of capacitors	As a result of 2017 capacitor inspections, 301 follow up work orders were generated. 161 of those 301 work orders are complete as of 3/26/2018.
Line recloser inspection (Distribution)	(walking) inspections	Annual inspection of 627 recloser installations were completed in 2017.	As a result of 2017 recloser inspections, 805 follow up work orders were generated. 246 follow up work order remaining to be completed as of 3/23/2018.
URD Cable Replacement (Distribution)	During 2016, URD cable replacements continued as needed.	100% of needed projects were scheduled. 530,855 feet of new, replacement URD cable was installed in 2017.	none
Distribution Pole Groundline Inspection and Treatment	(walking) inspection of each pole	In 2017, 35,334 wood poles were inspected - 26,738 Duke owned wood poles, and 8,596 foreign owned wood poles.  During 2017, 10.18% of Duke Energy Ohio distribution wood poles received inspections	As a result of 2017 wood pole inspections, 6,900 follow up work orders were opened. 1,647 of those 6,900 work orders are complete as of 3/14/2018.
Inspection of poles, towers, conductors, and pad mount transformers (Distribution)	(walking and driving) inspection along distribution circuits	During 2017, the distribution inspection program for Ohio completed inspection of 168 distribution circuits	As a result of 2017 distribution circuit inspections, 3,224 follow up work orders were opened. 1,436 of those 3,224 work orders are complete as of 3/14/2018.
Inspection of Transmission substations	(walking) inspection of each substation	201 monthly inspections were performed on Duke Energy Ohio's 17 transmission substations in 2017. 1 substation was put into service March 9th, and had 9 inspections performed.	As a result of 2017 transmission substation inspections, 137 follow up work orders were opened. 29 of those 137 work orders remain open as of 3/11/2018.

10a. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) if response in Column "Goals achieved?" of Report 10 is "Yes"

Program Name	Explanation of how goals were achieved	Quantitative description of goal achieved	Summary of Findings
Inspection of poles, towers, and conductors (Transmission)	inspection flights along transmission lines	During 2017, the transmission circuit inspection program for Ohio completed inspection of 132 transmission circuits - 100% of circuits with overhead mileage.	As a result of 2017 inspection flights, 158 follow up work orders were generated from the inspections, and all of them remain to be completed.
Transmission pole groundline inspection and treatment	(walking) inspection of each pole	In 2017, 3,865 transmission designated wood poles were inspected.	As a result of 2017 wood transmission pole inspection, 479 follow up work orders were generated. 46 of the 479 work orders have been completed.
Transmission vegetation management	(walking and driving) vegetation clearing along transmission circuits	In 2017, total line clearing maintenance was completed on 299 transmission circuit miles. 21.9% of Duke Energy Ohio transmission circuit miles were cleared in 2017.	none

10b. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) If response in Column "Goals achieved?" of Report 10 is "No"

Program Name	Cause(s) for not achieving goals	Description of level of completion	Quantitative description of level of completion	Summary of Findings
Distribution vegetation management	Unable to complete work plan due to current constricted labor market for qualified resources. Discussions are ongoing with commission for a reliability based program.	21.8% of Duke Energy Ohio distribution circuit miles were cleared in 2017.	In 2017, total line clearing maintenance was completed on 1,790.9 distribution circuit miles.	
Distribution Substation	Unable to complete the 3 missed inspections in allotted time due to combined factors of the Work Management System rollout with holidays and weather at the due dates.	2616 inspections were completed for all 218 distribution substations in 2017. 3 of these inspections missed the 40 day inspection requirement, ranging from 1 to 4 days over the 40 day requirement.	100% of inspections were completed, but 99.89% completed within 40 day requirement.	

10c. 4901:1-10-26(B)(3)(f), (B)(3)(f)(iii) Remedial activity

	Program finding(s) resulting in remedial action	Remedial activity performed	Completion date	Remedial activity yet to be performed	Estimated completion date
As a resinspections	As a result of 2017 capacitor inspections, 301 work orders were opened.	161 of the 301 work orders are complete as of 3/26/2018		140 work orders remain to be completed	12/31/2018
As a res inspection orders	As a result of 2017 recloser inspections, 805 follow up work orders were generated.	Of the follow up work orders generated as a result of the 2017 line recloser inspections, 559 of the follow up work orders were completed.		246 follow up work orders remaining to be completed as of 3/23/2018.	12/31/2018
	none	none		none	none
As a result inspections, orders	As a result of 2017 wood pole inspections, 6,900 follow up work orders were opened.	1,647 of those 6,900 work orders are complete as of 3/14/2018.		5,253 work orders remain to be completed from the 2017 inspections. 79 work orders remain from the 2016 inspections. 1 work order remains from the 2015 inspections.	12/31/2018
As a result ircuit inspect work orde	As a result of 2017 distribution circuit inspections, 3,224 follow up work orders were opened.	1,436 of the 3,224 follow up work orders are complete as of 3/14/2018.		1,788 follow up work orders remain to be completed from the 2017 inspections. 5 work orders remain from the 2016 inspections.	12/31/2018
Jnable to cor current con for quali	Unable to complete work plan due to current constricted labor market for qualified resources.	ооч		Discussions are ongoing with commission for a reliability based program.	none
As a result substation follow up v	As a result of 2017 distribution substation inspections, 1,229 follow up work orders were opened.	1,047 of those 1,229 work orders are complete as of 3/11/2018.		182 work orders remain to be completed from the 2017 inspections. 63 Work orders remain from 2016 inspections. 16 Work orders remain from inspections prior to 2016.	12/31/2018

10c. 4901:1-10-26(B)(3)(f), (B)(3)(f)(iii) Remedial activity

Program Name	Program finding(s) resulting in remedial action	Remedial activity performed	Completion date	Remedial activity yet to be performed	Estimated completion date
Inspection of Transmission substations	As a result of 2017 transmission substation inspections, 137 follow up work orders were opened.	108 of those 137 work orders are complete as of 3/11/2018.		29 work orders remain to be completed from the 2017 inspections. 13 Work orders remain from 2016 inspections. 2 Work orders remain from inspections prior to 2016.	12/31/2018
Transmission pole groundline inspection and treatment	As a result of 2017 wood pole inspections, 479 follow up work orders were opened.	46 of the 479 work orders are complete as of 3/7/2018		433 work orders remain to be completed from 2017 inspections. 91 work orders remain from the 2016 inspections. 38 work orders remain from inspections prior to 2016.	12/31/2018
Transmission Inspection of poles, towers, conductors, and pad mount transformers	As a result of 2017 inspection flights, 158 follow up work orders were opened.	0 of the 158 work orders have been completed as of 3/15/2018.		158 follow up work orders remain to be completed from the 2017 inspections. 36 work orders remain from the 2016 inspections.	12/31/2018
Transmission vegetation management	none	none		none	none

10d. 4901:1-10-26(B)(3)(f): Current Year Goals

Asset Type	Program Name	Program Goals
Distribution	Capacitor Maintenance	Visually inspect 100%, functionally inspect 100%, either on-site or remotely. 100% of capacitors planned to be inspected in 2018, either on-site or remotely. Capacitors with communication are remotely monitored.
Distribution	Line recloser inspection	Inspect line reclosers annually. 622 Reclosers planned for for 2018 Line Recloser inspections.
Distribution	URD Cable Replacement	Complete budgeted cable replacements
Distribution	Distribution Pole Groundline Inspection and Treatment	Inspect all distribution poles every 10 years and treat as needed. All Ohio distribution poles will be inspected within ten years. 39,243 poles planned for Distribution Pole Groundline Inspection and Treatment in 2018.
Distribution	Inspection of poles, towers, conductors, and pad mount transformers	Inspect distribution lines every 5 years. 113 circuits planned for inspection of poles, towers, conductors and pad mount transformers in 2018.
Distribution	Distribution vegetation management	Achieve 4-year cycle for vegetation line clearing on distribution circuits. Complete an average of 25% of target circuit miles per year. Discussions are ongoing with commission for a reliability based program.
Distribution Substation	Inspection of Distribution Substations	Inspect distribution substations monthly
Transmission Substation	Inspection of transmission substations	Inspect transmission substations monthly
Transmission	Transmission pole groundline inspection and treatment	Inspect all transmission poles every 10 years and treat as needed.
Transmission	Inspection of poles, towers, conductors, and pad mount transformers	Inspect transmission lines each year
Transmission	Transmission vegetation management	Achieve 6-year cycle for vegetation line clearing on transmission circuits. Complete an average of 16% of target circuit miles per year.

10d. 4901:1-10-26(B)(3)(f): Current Year Goals

**Asset Type** 

**Program Name** 

Program Goals

11. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Prevention of overloading or excessive loading of facilities and equipment

Transmission or Distribution	Program Name	Program Goals
	103H9056	Columbia 138 kV 22.4 MVA Sub - 103H9056
	414H8992	Brighton Sub - Convert 4kV - 414H8992
	AMOH1086	Nickel_Inst Ckts 44 and 45 - AMOH1086
	AMOH1112	South Fairmount Inst New Sub & UG Exits - AMOH1112
	DOH1108	E Provident Dr New Ckts - DOH1108
	DOH1120	Charles Sub L_M_O 4kV Conv - DOH1120
	DOH1138	Linwood 12kV Ckt Upg Cbl OH Reco - DOH1138
	DOH1284	Oakley P_Reco Ckt 40 - DOH1284
	DOH1584	West End 42 Upg - DOH1584
	DOH1595	Hyde Park Relief - DOH1595
	DOH1596	Goodwin 10 5 MVA XTR Ckt 41-42 DOH1596
	DOH1597	Hamlet 10.5 MVA XTR, CKT 42 DOH1597
	DOH1598	N Rich 10 5 MVA XTR Ckt 42_43 - DOH1598
	DOH1599	Delhi 43 Reco Pedretti DOH1599
	DOH1636	Madeira New Ckt 43 Rbid 41 42 - DOH1636
	DOH1651	Brown 52 N Pole 41 Rbld Ext - DOH1651
	DOH1653	Rem 53-42 Rbld Reco Humphrey Rd - DOH1653
	DOH1685	Morgan 53 Conv Stepdown - DOH1685
	DOH1769	Bethany 45 4kV Conversion DOH1769

11. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Prevention of overloading or excessive loading of facilities and equipment

Ŋ	- DOH1770	- DOH1772	vd - DOH1778	normalistica de la composição de la comp	H1782	SCER DOH1879	DOH1899	eek DOH1907	з - DOH1909	DOH1910	86 - DOH1939	IOH1945	DOH1962	DOH1963	um DOH1964	d DOH1976	on DOH1985	OH2007	JOH2028
Program Goals	Kleenman 46 Repl Cond – DOH1770	Terminal 42-44 Repl Cond - DOH1772	Rochelle 43_48 Reco MLK Blvd - DOH1778	Inst Seward Xtr 3 DOH1781	Seward 44 Reco DOH1782	Fairfax 43 Ext_Ret Oakley 829 SCER DOH1879	Felicity A Conv Rel 4kV DOH1899	Ebenezer 41 Reco Muddy Creek DOH1907	Amanda Inst 12 kV Feeders - DOH1909	Amanda Sub 12kV Conv DOH1910	Eastwood 52 Conv 4kV SR 286 - DOH1939	Oakley 52 853 Rcnfgr DOH1945	Deer Park Prop Purch - DOH1962	Banning 41 Reco OH Exit DOH1963	Rochelle 45 Reco Euclid Auburn DOH1964	Felicity 41 Conv Vern Hill Rd DOH1976	Finneytown 41 Reco Compton DOH1985	Manchester 41 Reco DOH2007	Oak Knoll 34.5kV Conv DOH2028
Program Name	DOH1770	DOH1772	DOH1778	DOH1781	DOH1782	DOH1879	DOH1899	DOH1907	DOH1909	DOH1910	DOH1939	DOH1945	DOH1962	DOH1963	DOH1964	DOH1976	DOH1985	DOH2007	DOH2028
or Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution

11. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Prevention of overloading or excessive loading of facilities and equipment

Wera Cruz 10  Mitchell 41 F Simpson 4; Olive Branc Columi Tre Newtown 44 R Allen 43 Hensk Beth Fran Prince West End-Bre Beckjord P Feeder 8887-1 Evendale	Transmission or Distribution	Program Name	Program Goals	
		DOH2043	Vera Cruz 10.5 MVA XTR CKT 42 DOH2043	
		DOH2109	Mitchell 41 Reco Cliftn Woolper DOH2109	
		DOH2119	Simpson 43 58 Add 600A Swi DOH2119	
		DOH2120	Olive Branch 22.4 MVA XTR - DOH2120	
		DOH2154	Columbia 41 UG Exit DOH2154	
		DOH2174	Trenton BK 4 DOH2174	
		DOH2180	Newtown 44 Reco Round-Bottom Rd DOH2180	
		DOH2181	Allen 43_Instl 12kV Fdr DOH2181	
		DOH2182	Hensley 42 Instl Fdr DOH2182	
		DOH2196	Union 42 Reco and Ext DOH2196	
		DOH2273	Seward 46 Cap Inst DOH2273	
		DOH2414	Bethany 42 Reco DOH2414	
		DOH2488	Franklin 41 Reco DOH2488	
		DOH2530	Princeton 42 Fdr Ext DOH2530	
		AMOH0194	West End-Brent Spence Bridge - AMOH0194	
		AMOH0765	Beckjord P_C Separation - AMOH0765	
		AMOH0833	Feeder 8887-Purchase Property - AMOH0833	
		AMOH1012	Evendale_69 kV Rcnfgr - AMOH1012	
		AMOH1013T	Shaker Run-Liberty Inst 69kV Ckt - AMOH1013	

11. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Prevention of overloading or excessive loading of facilities and equipment

Program Goals	Ford-Sharonville-Inst Loop Feed - AMOH1085	Black Start Portable Gen Conn - AMOH1202	Fdr 3861 Ext - AMOH1276	F9064 Trntn-Colnsvi Rbid ORP - AMOH1367	F4666 Evndl-Pt Un Rbid ORP - AMOH1369	Miami Fort-Exp 345 kV Ring Bus - TOH1423	Ebenezer_138kV Rcnfgr - TOH1504	868 Senco_Summerside Rbld OTIP - TOH1556	868 Oakley_Fairfax Rbld OTIP - TOH1557	3261 Trntn_Prnctn Rbld OTIP - TOH1560	3261 Pmctn_Pt Un RBLD - TOH1561	5680 Warren Nickel Rbld OTIP - TOH1562	Todhuntr_Rpl CB 913_919_925_93 - TOH1605	F4501 Pierce-Beckjord Rem - TOH1661	F3263 Ext and Ronfgr - TOH1847	5863 Rebuild Brown to South Bethel - TOH1848	F3881_Wards Corner Re-feed - TOH1870	Beckjord P_C Cntrl Bldg Rmv - TOH1903	Garver 138kV Exp - TOH1928	
Program Name	AMOH1085	AMOH1202	AMOH1276	AMOH1367	AMOH1369	TOH1423	TOH1504	TOH1556	TOH1557	TOH1560	TOH1561	TOH1562	TOH1605	TOH1661	TOH1847	TOH1848	TOH1870	TOH1903	TOH1928	
Transmission or Distribution	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	

11. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Prevention of overloading or excessive loading of facilities and equipment

	Program Goals	F3881-5483 Purc Prop - TOH2032	F868-Reconductor Fairfax-Senco - X04C7993
	Program Name	TOH2032	X04C7993
Transmission	or Distribution	Transmission	Transmission

12. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Actions to remedy overloading or excessive loading of facilities and equipment

Actual	completion	date
	Actions taken	to remedy overloading
Estimated	completion	date
		Plan to remedy overloading
Date	overloading	identified
	Sub/Circuit	name
<b>Transmission</b>	o	Distribution

Notes: Duke Energy had no overloading events in 2017.

# 13. 4901:1-10-26(B)(3)(f), (B)(3)(f)(vi): Programs deleted

Facility Type

Deleted Program Name

Notes: Duke Energy did not delete any inspection, maintenance, repair, or replacement programs during 2017.

# 14. 4901:1-10-26(B)(3)(f), (B)(3)(f)(vi): Programs modified

**Facility Type** 

**Deleted Program Name** 

Notes: Duke Energy did not modify any inspection, maintenance, repair, or replacement programs during 2017.

15. 4901:1-10-26(B)(3)(f), (B)(3)(f)(vi): Programs added

**Facility Type** 

**Deleted Program Name** 

Notes: Duke Energy did not add any inspection, maintenance, repair, or replacement programs during 2017.

16. 4901:1-10-26(B)(4): Service interruptions due to other entity

	Sub/Circuit	Interrupted Cause of interruption
Impact on	Transmission	or Distribution
Name of entity	causing	interruption
Type of entity	causing	interruption
Time	o	Interruption
Date	oţ	Interruption

Notes: Duke Energy Ohio had no customer service interruptions that were due solely to the actions or inactions of another electric utility, regional transmission entity, and/or a competitive retail electric supplier in 2017.

This foregoing document was electronically filed with the Public Utilities

**Commission of Ohio Docketing Information System on** 

3/29/2018 3:39:47 PM

in

Case No(s). 18-0999-EL-ESS

Summary: Annual Report Duke Energy Ohio Annual Report of Electric Distribution System Reliability Pursuant to 4901:1-10-26 electronically filed by Dianne Kuhnell on behalf of Duke Energy Ohio, Inc. and Rocco D'Ascenzo and Watts, Elizabeth H.