BEFORE THE PUBLIC UTILITIES COMMISSION OF OHIO

In the matter of the Annual Report of the Electric Service and Safety Standards, Pursuant to Rule 4901:1-10-26(B) of the Ohio Administrative Code) Case No: 19-1000-EL-ESS)	
---	-----------------------------	--

ANNUAL REPORT OF Dayton Power & Light submitted for the year 2018.

I certify that the following report accurately and completely reflects the annual report requirements pursuant to Rule 4901:1-10-26 of the Ohio Administrative Code.

Signature

Printed Name

Printed Name

A/1/19

Title

Date

Dayton Power & Light Rule 26 Report for 2018

1. 4901:1-10-26(B)(1), (B)(1)(b), (B)(1)(c) Future investment plan for facilities and equipment, covering period of no less than three years

RAP-015	PRP-015	PRC-011	ORP-015	CRP-015	CAP-015	Identification of project, program, or plan
Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Transmission or Distribution
Reliability Action Plan - complete repairs, upgrades or other reliability improvements to least-reliable branch- lines	Distribution Pole Inspection and Replacement Program - inspect distribution poles and repair/replace poles as necessary	Planned replacement of cutouts	Overhead Reliability Program - complete repairs, upgrades or other reliability improvements to least- reliable circuits	Cable Replacement Program - replace or inject deteriorating bare neutral primary cable	Capacitor Program - install new capacitors and controls to optimize reactive supply on circuits	Project description and goals
Various	Various	Various	Various	Various	Various	Portion of service territory affected
Various	Various	Various	Various	Various	Various	Characteristics of territory affected
\$500,000	\$5,000,000	\$1,000,000	\$750,000	\$3,250,000	\$200,000	Estimated cost
1/1/2022	1/1/2022	1/1/2022	1/1/2022	1/1/2022	1/1/2022	Initiation Date
12/31/2022	12/31/2022	12/31/2022	12/31/2022	12/31/2022	12/31/2022	Planned Completion Date

Dayton Power & Light Rule 26 Report for 2018

1. 4901:1-10-26(B)(1), (B)(1)(b), (B)(1)(c) Future investment plan for facilities and equipment, covering period of no less than three years

Name of the last o				
Identification of project, program, or plan	TPI-015	TRU-014	RTP-01	RTP-02
Transmission or Distribution	Transmission	Transmission	Transmission	Transmission
Project description and goals	Transmission Pole Inspection - inspect transmission poles and repair or replace as necessary	Transmission Relay Upgrade - replacing/upgrading transmission relays	Expansion of West Milton Substation for capacity needs and system resiliency	Build new substation in Marysville to support load growth
Portion of service territory affected	Various	Various	Various	Various
Characteristics of territory affected	Various	Various	Various	Rural
Estimated cost	\$910,000	\$1,000,000	\$12,000,000	\$14,000,000
Initiation Date	1/1/2022	1/1/2022	1/1/2019	1/1/2019
Planned Completion Date	12/31/2022	12/31/2022	12/31/2021	12/31/2021

Notes: DP&L budgets annually for this ongoing program

1a. 4901:1-10-26(B)(1), (B)(1)(a) Relevant characteristics of the service territory

Transmission

Distribution	Transmission	or Distribution
10,451	1,717	Overhead Miles
3,735	&	Underground Miles
A review of Dayton Power & Light's historical reliability performance clearly shows the distribution system to be in excellent condition.	System reliability performance is a good indicator of the physical condition of the system and industry standard measures show that system performance is consistently reliable.	Notable Characteristics

Notes: DP&L's transmission has the capacity to meet projected loading, System Operating monitors the condition of the transmission system on a daily basis. Any findings that may impact safety or reliability are immediately addressed.

1b. 4901:1-10-26(B)(1) Future investment plan for facilities and equipment

Distribution	Transmission	Transmission or Distribution
\$10,400,000	\$3,550,000	2018 Planned Costs
\$14,235,000	\$4,529,000	2018 Actual Costs
\$11,175,000	\$1,550,000	2019 Planned Costs
\$10,800,000	\$1,750,000	2020 Projected Costs
\$10,550,000	\$27,750,000	2021 Projected Costs
\$10,200,000	\$1,750,000	2022 Projected Costs

Notes: Transmission reliability projects less than 3 years are not included.

Distribution reliability projects less than 3 years are not included.

2. 4901:1-10-26(B)(1)(d), (B)(1)(f) Complaints from other entities

why?	resolved	(yes/no)	address complaint	Nature of complaint	received	complaint
If not resolved,	Date complaint	Resolved	Action taken to		Date complaint	Entity making

Notes: No Complaints

3a. 4901:1-10-26(B)(1)(e), (B)(1)(f) Electric Reliability Organization standards violations

why?	resolved	(yes/no)	description	dollars	factor	factor	violation	name	number
If not resolved,	Date	Resolved	Violation	Penalty	Severity	Risk	Date of	Standard	Standard

Notes: No Violations

3b. 4901:1-10-26(B)(1)(e), (B)(1)(f) Regional Transmission Organization (RTO) violations

Notes: No Violations

3c. 4901:1-10-26(B)(1)(e) Transmission Load Relief (TLR) events

Event Start		
Event End		
during event	Highest TLR	
during event	interrupted	Firm load
interrupted	load (MW)	Amount of
Description of event		

Notes: No TLR

3d. 4901:1-10-26(B)(1)(e) Top ten congestion facilities by hours of congestion

Description of facility causing congestion

Rank

Notes: No facilities experienced congestion

3e. 4901:1-10-26(B)(1)(e) Annual System Improvement Plan and Regional Transmission Operator Expansion Plan

Relationship between annual system improvement plan and RTO transmission expansion plan

Our annual system improvement plan includes the regional transmission operator's transmission project plan. The RTO driven project is the West Milton-Eldean transmission line which is in the permitting process at the Ohio Power Siting Board.

4. 4901:1-10-26(B)(2) Report of implementation plans from previous reporting periods

RTU-011	RAP-013	RAP-012	RAP-011	PRP-013	PRP-012	PRP-011	PRC-009	PRC-008	PRC-008	ORP-013	ORP-012	ORP-011	CRP-013	CRP-012	CRP-011	CAP-013	CAP-012	CAP-011	Identification of project, program, or plan
Distribution	Transmission or Distribution																		
12/31/2018	12/31/2020	12/31/2019	12/31/2018	12/31/2020	12/31/2019	12/31/2018	12/31/2020	12/31/2019	12/31/2018	12/31/2020	12/31/2019	12/31/2018	12/31/2020	12/31/2019	12/31/2018	12/31/2020	12/31/2019	12/31/2018	Planned Completion Date
12/31/2018			12/31/2018			12/31/2018			12/31/2018			12/31/2018			12/31/2018			12/31/2018	Actual Completion Date
																			Identification of deviation from previous plan
																			Reason for deviation from previous plan

4. 4901:1-10-26(B)(2) Report of implementation plans from previous reporting periods

Project on an as needed basis	Dollars reduced		12/31/2021	Distribution	RTU-014
			12/31/2021	Transmission	TRU-013
Project scope increased	Increased dollars		12/31/2021	Transmission	TPI-014
			12/31/2021	Distribution	RAP-014
			12/31/2021	Distribution	PRP-014
			12/31/2021	Distribution	PRC-010
			12/31/2021	Distribution	ORP-014
			12/31/2021	Distribution	CRP-014
			12/31/2021	Distribution	CAP-014
			12/31/2020	Transmission	TRU-012
			12/31/2019	Transmission	TRU-011
		12/31/2018	12/31/2018	Transmission	TRU-010
Changed scope of project	Increased dollars		12/31/2020	Transmission	TPI-013
Changed scope of project	Increased dollars		12/31/2019	Transmission	TPI-012
Changed scope of project	Increased dollars	12/31/2018	12/31/2018	Transmission	TPI-011
Project completed in 2017		12/31/2017	12/31/2018	Transmission	TCW-003
			12/31/2020	Distribution	RTU-013
			12/31/2019	Distribution	RTU-012
Reason for deviation from previous plan	Identification of deviation from previous plan	Actual Completion Date	Planned Completion Date	Transmission or Distribution	Identification of project, program, or plan

4. 4901:1-10-26(B)(2) Report of implementation plans from previous reporting periods

from previous plan	from previous plan	Date	Date	Distribution	program, or plan
Reason for deviation	Identification of deviation	Completion	Completion	or	Identification of project,
		Actual	Planned	Transmission	

5. 4901:1-10-26(B)(3), (B)(3)(a) Characterization of condition of company's system

Transmission System reliability condition of the system	Distribution A review of Dayton shows the distributio Put	Transmission or Distribution Qualitative cl
System reliability performance is a good indicator of the physical condition of the system and industry standard measures show that system performance is consistently reliable.	A review of Dayton Power & Light's historical reliability performance shows the distribution system has met the standards prescribed by the Public Utilities Commission of Ohio.	Qualitative characterization of condition of system
DP&L's transmission has the capacity to meet projected loading, System Operating monitors the condition of the transmission system on a daily basis. Any findings that may impact safety or reliability are	The performance of the electric system over a period of several years is reflective of its physical condition. Consistently safe and reliable service can only be achieved through a well-maintained distribution system. System level reliability performance is tracked on a monthly basis and reported annually as required by O.A.C. 4901:1-10-10.	Explanation of criteria used in making assessment for each characterization

6. 4901:1-10-26(B)(3), (B)(3)(b) Safety and reliability complaints

Distribution	Transmission or Distribution
	Availability of Service
	Damage
2	Momentary Interruption
16	Out of Service
	Quality of Service
	Repair Service
	Public Safety
18	Total Complaints

Notes:

1

7a. 4901:1-10-26(B)(3)(c), (B)(3)(c)(i) Transmission capital expenditures

\$412,102,805 1.50%	Total Transmission investment as of year end Transmission capital expenditures as % of total transmission investment
\$6,187,000	Total transmission capital expenditures in 2018

Notes:

7b. 4901:1-10-26(B)(3)(c), (B)(3)(c)(i) Transmission maintenance expenditures

Transmission maintenance expenditures as % of total transmission investment	Total Transmission investment as of year end	Total transmission maintenance expenditures in 2018
1.27%	\$412,102,805	\$5,220,170

7c. 4901:1-10-26(B)(3), (B)(3)(c)(ii), (B)(3)(c)(iii) Transmission capital expenditures - Reliability specific

Transmission Reliability - CCD	Transmission Reliability - Projects	Transmission Blankets - Other	Transmission - Substation Reliability	budget category	Transmission capital
\$500,000	\$3,728,000	\$1,000,000		Budget	2018
\$-3,511,000	\$6,269,000	\$768,000		Actual	2018
-702.20%	68.00%	23.20%		% Variance	
In 2018 the CCD construct was dissolved.	RTEP Projects	Forced repairs were lower than budgeted.	Transmission Catastrophic Repairs and Distribution Catastrophic Repairs are budgeted together as one number. The budget is only included in Distribution Catastrophic Repairs.	Explanation of variance if over 10%	
	\$39,451,000	\$1,000,000		Budget	2019

7d. 4901:1-10-26(B)(3), (B)(3)(c)(ii), (B)(3)(c)(iii) Transmission maintenance expenditures - Reliability specific

Transmission Line Clearance	Transmission Reliability	Transmission maintenance budget category
\$2,131,272	\$278,611	2018 Budget
\$2,117,398	\$292,366	2018 Actual
-0.07%	5.00%	% Variance
		Explanation of variance if over 10%
\$2,480,435	\$340,166	2019 Budget

8a. 4901:1-10-26(B)(3)(d), (B)(3)(d)(i) Distribution capital expenditures

Notes:

8b. 4901:1-10-26(B)(3)(d), (B)(3)(d)(i) Distribution maintenance expenditures

2.63%	Distribution maintenance expenditures as % of total distribution investment
\$1,826,132,233	Total distribution investment as of year end
\$48,088,772	Total distribution maintenance expenditures in 2018

8c. 4901:1-10-26(B)(3), (B)(3)(d)(ii), (B)(3)(d)(iii) Distribution capital expenditures - Reliability specific

Distribution capital budget category Distribution - Specific Projects Distribution - Field Reliability Distribution - Substation Reliability Distribution - Underground Reliability	2018 Budget \$1,648,000 \$6,167,000 \$3,570,000 \$3,570,000	2018 Actual \$1,238,000 \$9,121,000 \$5,884,000 \$5,852,000	% Variance -25.00% 47.00% 65.00% 67.00%	Explanation of variance if over 10% Projects expenditures in 2018 were less than budgeted. Replaced additional poles. Increased spend to address transformer failures. Replaced additional cable.	2019 Budget \$2,500,000 \$6,400,000 \$4,425,000 \$3,000,000
Distribution - Underground Reliability	\$3,500,000	\$5,852,000	67.00%	Replaced additional cable.	\$3,000,000
Distribution - Blanket Other	\$8,500,000	\$8,374,000	-2.00%		\$7,300,000
Distribution Planning - Reliability	\$1,550,000	\$1,576,000	19.50%	Fewer network events.	\$1,500,000
Distribution Blanket - Transformers	\$13,250,000	\$15,836,000	19.00%	Replaced more transformers than anticipated.	\$13,500,000

8d. 4901:1-10-26(B)(3), (B)(3)(d)(ii), (B)(3)(d)(iii) Distribution maintenance expenditures - Reliability specific

Distribution Line Clearance	Distribution Reliability	Distribution maintenance budget category
\$16,251,541	\$25,123,704	2018 Budget
\$15,800,508	\$33,850,008	2018 Actual
-3.00%	35.00%	% Variance
	Storm Activity	Explanation of variance if over 10%
\$20,630,678	\$25,253,464	2019 Budget

9. 4901:1-10-26(B)(3)(e) Average remaining depreciation life of distribution and transmission facilities

Devices Line Transformers Services Meters
Underground Conductors and 367 Devices Line Transformers 368 Services 369 Meters 370
38.00 44.00 33.00 32.00
41.30 30.82 31.68 29.33 24.47
13.70 7.18 12.32 3.67 7.53
24.92% 18.90% 28.02% 11.13% 23.54%
Net Plant/Gross Plant

9. 4901:1-10-26(B)(3)(e) Average remaining depreciation life of distribution and transmission facilities

Distribution Leased	Distribution Insta	Transmission or Distribution
Leased Property on Customer Premises	Installations on Customer Premises	Asset type
372	371	FERC account/ subaccount
40.00	20.00	FERC Total account/ depreciable subaccount life of asset
0.00	18.58	Total Total depreciated remaining life of asset life of asset
0.00	1.42	Total remaining life of asset
0.00%	7.10%	Percent of remaining life of asset
Net Plant/Gross Plant	Net Plant/Gross Plant	How age was determined

10. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i) Inspection, maintenance, repair, and replacement of distribution, transmission, and substation programs summary report

TS and DS	TS	TS and DS	TS and DS	Transmission	Transmission	TS and DS	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Asset type
Visual Inspection of Circuit Breakers	Operational Testing of Circuit Breakers	Substation Transformer Power Factor Test	Substation Transformer LTC Maintenance	Substation Transformers Dielectric Oil Breakdown Test	Thermographic Imaging of Substation Transformers	External visual inspection of Substation Transformers	Transmission Inspection Program	Herbicide Application	Transmission Line Clearance	Thermographic Inspection of Transmission Lines	69 kV Aerial Patrol	138 kV Aerial Patrol	345 kV Aerial Patrol	Program Name
Inspect approximately 1,300 Circuit Breakers monthly	Conduct an operational test for breakers that are not otherwise operated during the calendar year	Perform power factor testing on 65 substation transformers	Complete maintenance on 56 LTCs	Perform oil dielectric breakdown on 65 transformers	Infrared approximately 300 Substation Transformers	Inspect approximately 300 Substation Transformers monthly	Inspect 25 circuits in metro - no fly zone	Apply herbicide as needed	Trim trees where needed	Perform thermographic inspections where needed	Inspect 69 kV circuits, semi-annually	Inspect 138 kV circuits, 4 times per year	Inspect 345 kV circuits, 4 times per year	Program Goals
~	z	~	~	~	~	~	~	~	~	~	~	~	~	Goals achieved?

10. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i) Inspection, maintenance, repair, and replacement of distribution, transmission, and substation programs summary report

Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	ST	Distribution	DS	ST	TS/DS	Asset type
Pole Replacement and Testing Program	Distribution Line Clearance	Distribution Circuit Patrol	Monitor Branch Line Reliability Performance	Monitor Circuit Reliability Performance	Underground Device Inspections	Recloser Inspections	Capacitor Inspections	Visual Inspection of Airbreak Switches	Thermographic Inspection of Substation Switches	Distribution Relay Testing	Non-BES Relay Testing	BES Relay Testing	Circuit Breaker Preventive Maintenance	Program Name
Inspect approximately 34,628 poles on 45 circuits	Perform full circuit vegetation maintenance on 2,787 miles and 108 circuits in order to return to a 5 year cycle. Fewer miles will be trimmed if increased costs and labor resource constraints continue as discussed in Section 10b.	Inspect 94 circuits	Evaluate least-reliable branch lines and initiate remedial action where needed	Evaluate least-reliable circuits and initiate remedial action where needed	Inspect URD devices on 349 map grids	Complete the inspection of approximately 584 reclosers	Complete the inspection of approximately 1329 capacitors	Inspect approximately 1,616 switches	Infrared approximately 2,362 Substation Switches	Test 386 Distribution relays (12/4 kV)	Test 241 Non-BES transmission relays	Test 78 BES relays	Complete maintenance on 288 circuit breakers	Program Goals
~	rce N	~	~	~	~	~	~	~	≺	~	~	~	~	Goals achieved?

10. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i) Inspection, maintenance, repair, and replacement of distribution, transmission, and substation programs summary report

Asset type **Program Name Program Goals** Goals achieved?

10a. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) If response in Column "Goals achieved?" of Report 10 is "Yes"

Substation Transformer Power Factor Test	Substation Transformer LTC Maintenance	Substation Transformers Dielectric Oil Breakdown Test	Thermographic Imaging of Substation Transformers	External visual inspection of Substation Transformers	Transmission Inspection Program	Herbicide Application	Transmission Line Clearance	Thermographic Inspection of Transmission Lines	69 kV Aerial Patrol	138 kV Aerial Patrol	345 kV Aerial Patrol	Program Name
Power factor testing was performed on 67 transformers.	Performed maintenance on 56 LTCs.	Performed oil dielectric breakdown tests on 67 transformers.	Performed infrared inspection on 300 transformer units.	Performed monthly inspections on approximately 300 transformer units monthly.	Inspected 25 circuits in metro no fly zone.	82 areas received herbicide application.	Full maintenance on 34590 and 34591. Spot trimming completed in 297 locations and maintenance trimming in 387 locations.	No inspections were scheduled in 2018.	Inspected 89-69 kV transmission lines, 2 times each	Inspected 33-138 kV transmission lines, 4 times each	Inspected 14-345 kV transmission lines, 4 times each	Explanation of how goals were achieved
100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	100%	Quantitative description of goal achieved
												Summary of Findings

10a. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) If response in Column "Goals achieved?" of Report 10 is "Yes"

221 Non-BES transmission relays tested. 100% In 2018, DP&L moved 32- 138 kV Capacitor Type (U.P. relays into the 2018 relay testing plan as a result of second fellows of this type of th
100% In 2018, DP&L moved 32- 138 kV Capacitor Type (U.P.) relays into the 2018 relay testing plan as a result of
100%

10a. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) If response in Column "Goals achieved?" of Report 10 is "Yes"

reuit through the 100% Program. istribution circuits 100% lans initiated where on 94 circuits. 100% circuits through the 100% Approximate number of poles reported in 4901:1-26(10) ogram.	Analyzed the 39 Rule 11 circuit through the Overhead Reliability Program. Multiple branchlines on 15 distribution circuits were inspected and reliability plans initiated where appropriate. Completed inspections on 94 circuits. Inspected 34,609 poles on 45 circuits through the pole inspection program.	Monitor Circuit Reliability Performance Monitor Branch Line Reliability Performance Distribution Circuit Patrol Pole Replacement and Testing Program
how Quantitative description ieved of goal achieved Summary of Findings	Explanation of how goals were achieved	Program Name

10b. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) If response in Column "Goals achieved?" of Report 10 is "No"

Distribution Line Clearance	Program Name
Challenging labor market conditions affecting the entire vegetation management industry have led to widespread price increases and schedule completion shortfalls for many utilities. Currently there is not enough qualified labor in the utility vegetation management industry to effectively meet the increasing needs of electricity providers. DP&L employs 6 contractors (5 national, 1 local) who all are struggling with these labor market conditions and we continue to evaluate more potential vendors to grow the local workforce. As a result, DP&L has faced significant challenges in trying to overcome the labor shortages and the related price increases. To the best of its ability, DP&L made strategic decisions to focus its vegetation management efforts in such a way as to maximize the potential benefit to customers by prioritizing circuits based on safety, reliability and vegetation risk.	Cause(s) for not achieving goals
Per DP&L's ESSS Rule Vegetation Management program, full circuit maintenance trimming was completed on 71 circuits. The remaining 37 circuits are being deferred until there is sufficient contractor resources to safely and effectively complete the work due to the aforementioned cost and labor resource issues. DP&L provides monthly program updates to PUCO Staff which include circuit completion, budget utilitization and crew status.	Description of level of completion
We identified the circuits to be deferred based upon safety, reliability and vegetation risk.	Quantitative description of level of completion
Performed full circuit vegetation management on 1319.25 miles of our distribution system which encompasses 71 circuits.	Summary of Findings

10b. 4901:1-10-26(B)(3)(f), (B)(3)(f)(i), (B)(3)(f)(ii) If response in Column "Goals achieved?" of Report 10 is "No"

operated in January 2019.		open breakers and only routinely used as circuit ties in the event they are needed. 4 breakers could not be operated due to a customer outage.	for breakers that are not otherwise operated during the calendar year	Breakers
4 of the normally open breakers were	98.9% of breakers operated	4 breakers that are normally	Conduct an operational test	Operational Testing of Circuit
Summary of Findings	Quantitative description of level of completion	Description of level of completion	Cause(s) for not achieving goals	Program Name

10c. 4901:1-10-26(B)(3)(f), (B)(3)(f)(iii) Remedial activity

Thermographic Inspection of Substation Switches	Visual Inspection of Circuit Breakers	Operational Testing of Circuit Breakers	Substation Transformer Power Factor Test	Thermographic Imaging of Substation Transformers	External visual inspection of Substation Transformers	Transmission Aerial Patrols	Program Name
Infrared inspections of substation switches identified bad or deteriorated contacts. 5 problems were identified during inspections.	17 items were identified requiring remedial activity.	2 breakers failed to operate and 1 had a burnt trip coil	2 repair items identified	There were 3 loose connection issues identified using infrared.	6 maintenance items were identified as requiring remedial activity. Examples of repair items include: inoperative cooling fans, inoperative winding temperature gauge, bushing low oil level, low oil level in main tank or LTC compartments, major LTC filter oil leak and sudden pressure relay operations	Found 33 items that needed repaired	Program finding(s) resulting in remedial action
A second thermographic picture was taken to confirm problem. Once the problem(s) was confirmed the switches were replaced or removed from service, cleaned, maintenance and returned to service. 5 repairs were made in 2018.	12 repair items include compressor or motor problems, low oil or SF6 gas levels.	All repairs were complete.	All repairs were complete.	All repairs were completed.	All repairs were completed.	Completed 10 repair items from 2018 patrols.	Remedial activity performed
12/31/2018	12/31/2018	12/31/2018	12/31/2018	12/31/2018	12/31/2018	12/31/2018	Completion date
	5 minor breaker problems are scheduled to be repaired in conjunction with next maintenance cycle.					23 repair items are scheduled to be repaired in conjunction with regular work on the circuit.	Remedial activity yet to be performed
							Estimated completion date

10c. 4901:1-10-26(B)(3)(f), (B)(3)(f)(iii) Remedial activity

6/1/2021 12/31/2019	inspections which will be scheduled with routine work on the circuit. 344 poles to be reinforced and 2,931 poles to be replaced. Refer to Rule 11 for specifics on remedial items for individual ORP circuits		3,298 poles failed the inspection or integrity test with 23 poles replaced. Refer to Rule 11 for specifics on remedial items for individual ORP circuits.	Inspected 34,609 poles through the pole replacement program Repair items were identified during the inspection of ORP circuits. Typical repair items include: Lightning arrestors, cut-out, pole replacements/reinforcements, cable injection or replacement	Pole Replacement and Testing Program Monitor Circuit Reliability Performance
	208 repair items still need to be completed. Additionally, 28 repair items still need to be completed from 2016 inspections, and 94 repair items form 2017 inspections which will be scheduled with regular work on circuit. 185 items remain from the 2018 inspections. Additionally, 625 repair items from 2017 inspections, 501 repair items from 2016 inspections.	2/12/2019 3/6/2019	630 repair items completed. 3,098 items have been completed.	838 repair items were identified during the underground device inspection program. Typical repair items can be described as defective locking mechanisms, defective pads, exposed cable 3,283 repairs were identified during the inspections. Repair items include broken groundwires and loose or broken groundwires and loose or broken groundwires.	Underground Device Inspections Distribution Circuit Patrol
		12/31/2018	All repairs were completed during the inspection.	2 repair items were identified during recloser inspections. Items identified were cutouts.	Recloser Inspections
	28 maintenance repairs to be completed from the 2018 inspections.	3/6/2019	Completed 76 repairs.	104 repair items were identified during the capacitor inspections. Typical repairs include replacing blown fuses, bad capacitors, or control issues.	Capacitor Inspections
	4 repair items remain from 2018 which will be scheduled with regular work on the circuit.	12/31/2018	Completed 9 airbreak repairs .	13 repair items were identified during the airbreak inspections. Typical repairs include blown lightning arresters and pole grounds, etc.	Visual Inspection of Airbreak Switches
Estimated completion date	Remedial activity yet to be performed	Completion date	Remedial activity performed	Program finding(s) resulting in remedial action	Program Name

10c. 4901:1-10-26(B)(3)(f), (B)(3)(f)(iii) Remedial activity

Program Name reme	res	Progra
medial action	sulting in	ım finding(s)
performed	Remedial activity	
date	Completion	
yet to be performed	Remedial activity	
date	completion	Estimated

10d. 4901:1-10-26(B)(3)(f): Current Year Goals

TS and DS	TS	TS and DS	TS and DS	Transmission	Transmission	TS and DS	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Transmission	Asset Type
	O.	Su	Sı	Die	1	0			Tra	Τh				***************************************
Visual Inspection of Circuit Breakers	Operational Testing of Circuit Breakers	Substation Transformer Power Factor Test	Substation Transformer LTC Maintenance	Substation Transformers Dielectric Oil Breakdown Test	Thermographic Imaging of Substation Transformers	External visual inspection of Substation Transformers	Transmission Inspection Program	Herbicide Application	Transmission Line Clearance	Thermographic Inspection of Transmission Lines	69 kV Aerial Patrol	138 kV Aerial Patrol	345 kV Aerial Patrol	Program Name
Inspect approximately 1,300 Circuit Breakers monthly	Conduct an operational test for breakers that are not otherwise operated during the calendar year	Perform power factor testing on 55 substation transformers	Complete maintenance on 44 LTCs	Perform oil dielectric breakdown on 55 transformers	Infrared approximately 300 Substation Transformers	Inspect approximately 300 Substation Transformers monthly	Inspect 25 circuits in metro - no fly zone	Apply herbicide as needed	Trim trees where needed	Perform thermographic inspections where needed	Inspect 69 kV circuits, semi-annually	Inspect 138 kV circuits, 4 times per year	Inspect 345 kV circuits, 4 times per year	Program Goals

10d. 4901:1-10-26(B)(3)(f): Current Year Goals

Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	Distribution	TS	Distribution	DS	ST	TS/DS	Asset Type
Program Regulator Inspection Program	Pole Replacement and Testing	Distribution Circuit Patrol	Monitor Branch Line Reliability Performance	Monitor Circuit Reliability Performance	Underground Device Inspections	Recloser Inspections	Capacitor Inspections	Thermographic Inspection of Substation Switches	Non-BES Distribution Relays	Non-BES Transmission Relays	BES Relays	Circuit Breaker Preventive Maintenance	Program Name
Inspect approximately 540 regulators	trimmed if increased costs and labor resource constraints continue as discussed in Section 10b. Inspect approximately 30,111 poles on 48 circuits	Inspect 91 circuits	Evaluate least-reliable branch lines and initiate remedial action where needed	Evaluate least-reliable circuits and initiate remedial action where needed	Inspect URD devices on 346 map grids	Complete the inspection of approximately 584 reclosers	Complete the inspection of approximately 1335 capacitors	Infrared approximately 2,362 Substation Switches	Test 550 relays	Test 150 relays	Test 100 relays	Complete maintenance on 208 circuit breakers	Program Goals

10d. 4901:1-10-26(B)(3)(f): Current Year Goals

11. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Prevention of overloading or excessive loading of facilities and equipment

T	D	Transmission or Distribution
Transmission Planning	Distribution Planning	Program Name
DP&L performs an evaluation of its transmission system on an annual basis and in response to significant proposed changes to the system, such as the installation of a generating plant or a large change in customer load at a given location. DP&L bases its transmission system evaluations on a recent power flow model developed by ReliabilityFirst on behalf of its members. A detailed model of the DP&L transmission system is then inserted in order to include all 69 kV and 138 kV facilities. Changes may be made to the generation dispatch in order to evaluate the most stressful conditions on the system. The evaluations typically consist of comprehensive contingency analyses including outages of single segment transmission lines, multiple-terminal transmission lines, transformers, generating units, and double circuits. The results of these studies are checked for thermal overloading and excessive voltage drop according to NERC/ReliabilityFirst.	The distribution planning process includes an ongoing analysis of each component and its response to current and projected peak loads. Short and long-range plans are developed and continually refined based on changing customer needs and the dynamic nature of the distribution system.	Program Goals

12. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Actions to remedy overloading or excessive loading of facilities and equipment

Transmission or Distribution	Sub/Circuit name	Date overloading identified	Plan to remedy overloading	Estimated completion date	Actions taken control to remedy overloading	Actual completion date
Distribution	Marysville / CB1202	10/26/2016	Improve relay setting protection	8/30/2019	Install recloser and change fusing on distribution circuit CB1202 to improve relay coordination at the substation	
Distribution	Coldwater / KA1201	2/6/2017	Improve relay setting protection		Install recloser and change fusing on distribution circuit KA1201 to eliminate overload condition and improve relay coordination at the substation	Project cancelled
Distribution	Greenville / LD1202	1/23/2017	Improve relay setting protection	5/30/2018	Replace capacitor bank with voltage regulator on LD1202	2/20/2018
Distribution	Airway/AJ1205	1/8/2018	Phase Balancing	5/1/2019	Phase swap on distribution circuit AJ1205 to balance phases	
Distribution	Glady Run/GR1212	1/8/2018	Phase Balancing	5/30/2019	Phase swap on distribution circuit GR1212 to balance phases	
Distribution	Middleboro/ HM1202	1/8/2018	Phase Balancing	5/30/2019	Phase swap on distribution circuit HM1202 to balance phases	
Distribution	Urbana/DB1206	4/4/2017	Upgrade line regulators	9/1/2018	Upgrade line regulator from 219A to 3 -328A	5/24/2018
Distribution	Martinsville/HD1206	11/12/2018	Upgrade circuit and line reclosure	9/1/2019	Reconductoring part of the circuit and installing reclosures	
Distribution	Wilmington/HB1202	1/23/2018	Upgrade line recloser	7/1/2019		
Distribution	Wilmington/HB1202	1/23/2018	Upgrade line regulator	7/1/2019		
Distribution	Staunton/OE1204	6/18/2018	Upgrading OVHD Conductor	6/15/2019		
Distribution	Greenville/LD1211	3/1/2018	Upgrading OVHD Conductor	7/1/2019		
Distribution	Brookville/ME1204	8/28/2018	Installing Line Recloser	4/15/2019	Installed Solids and Removed fusing	

12. 4901:1-10-26(B)(3)(f), (B)(3)(iv): Actions to remedy overloading or excessive loading of facilities and equipment

Distribution	Transmission or Distribution
Glady Run/GR1213	Sub/Circuit name
1/30/2019	Date overloading identified
Upgrade Recloser and swap phases	Plan to remedy overloading
10/1/2019	Estimated completion date
	Actions taken to remedy overloading
	Actual completion date

13. 4901:1-10-26(B)(3)(f), (B)(3)(f)(vi): Programs deleted

Facility Type Deleted Program Name

Distribution Airbreak Switch Inspection

Notes: Airbreak Switches are inspected during Distribution Line Patrol.

14. 4901:1-10-26(B)(3)(f), (B)(3)(f)(vi): Programs modified

Facility Type

Deleted Program Name

Notes: No programs modified

15. 4901:1-10-26(B)(3)(f), (B)(3)(f)(vi): Programs added

Facility Type

Deleted Program Name

Notes: No program changes

16. 4901:1-10-26(B)(4): Service interruptions due to other entity

6/9/18	Date of Interruption
3:03 PM	Date Time of of Interruption Interruption
Other Electric Utility	Type of entity causing interruption
Midwest REA	Name of entity causing interruption
Transmission and Distribution	Impact on Transmission or Distribution
Coldwater/Rossburg - 6684 LC1201- KG1201-KG1203	Sub/Circuit Interrupted
Tree	Cause of interruption

This foregoing document was electronically filed with the Public Utilities

Commission of Ohio Docketing Information System on

4/1/2019 11:59:33 AM

in

Case No(s). 19-1000-EL-ESS

Summary: Report Annual Report Pursuant to Rule 4901:1-10-26 Annual System Improvement Plan for the year 2018 electronically filed by Mr. Alan M. O'Meara on behalf of The Dayton Power and Light Company