Memo

To: Docketing Division

From: Jill Henry, Rail Specialist, Rail Division

Cc: PUCO Legal Department

Date: 5/31/2019

Re: PUCO Case No. 19-423-RR-STP- In the Matter of a Request for Upgrades at Akron Barberton Cluster Railway Crossings in Medina County and Portage County, Ohio.

On November 14, 2018, Commission Staff (PUCO) and Akron Barberton Cluster Railway (AB) entered into a stipulation agreement whereby upgraded warning devices would be installed at the following AB crossings:

Grade Crossing #	Location	Nature of Upgrades
262-564G	Main Street, Kent, Portage County	Upgrade to cantilever lights and gates
265-079J	Medina Line Road/CR 2 Barberton, Medina County	Upgrade to lights and gates
265-076N	Main Street Wadsworth, Medina County	Upgrade lights and gates and move devices closer to tracks.

On April 3, 2019, the Commission issued a Finding and Order approving the project, requiring plans and estimates, by July 3, 2019, and ordering project completion by April 3, 2020.

On May 28, 2019, AB filed with the Rail Division all plans and estimates for the projects.

The plans and estimates submitted by AB have been reviewed and authorization is recommended. (See attached documentation.)







M. Beth Trombold Lawrence K. Friedeman Dennis P. Deters Daniel R. Conway

May 31, 2019

Mr. Andrew Shuster Akron Barberton Cluster Railway Signals & Communications Supervisor 43 Second Street NW Barberton, Ohio 44203

> Re: AB Grade Crossing Upgrades, Main St, Kent DOT#262-564G Medina Line Rd DOT#265-079J Main St, Wadsworth DOT#265-076N

Mr. Shuster:

Akron Barberton Cluster Railway (AB) is now authorized to proceed with field construction for the above referenced projects. This authorization is contingent upon accepting the following:

- 1) AB will make any adjustments to the plans noted in the field reports dated May 31, 2019 (Attached).
- AB will furnish e-mail, fax, or phone notification five (5) working days prior to the date work will start at the project site. Notification to be made to Jill Henry, PUCO, at E-MAIL <u>jill.henry@puco.ohio.gov</u>, or PHONE 614-466-0435.
- 3) AB will arrange for utilities to be relocated and/or dropped (as soon as possible) at the project sites through the applicable utility companies.
- 4) AB will arrange for utilities to be located at the project sites by the Ohio Utilities Protection Service (OUPS) prior to any construction activities at the sites. Utilities that are not participating members of the OUPS service must be contacted directly by AB.
- 5) AB's project foreman will notify the PUCO Railroad Inspector of any changes in the scope of work, cost overruns, material changes, etc. which are not included in the approved plans and estimates and secure approval of same before the work is performed.
- 6) AB will furnish three (3) copies of each partial bill to the PUCO.

- 7) AB will furnish the final-inclusive bill to PUCO stating that exact dates of starting and completing work, the initial and final dates of construction and location where the accounts may be audited.
- 8) AB will furnish as-built detailed circuit plans directly to the PUCO.
- 9) AB is to schedule and complete the subject projects by April 3, 2020. If any extraordinary circumstances unique to the projects occur, please notify the Commission's rail staff immediately.

Thank you for you cooperation in this matter.

Sincerely,

Henn 100

Jill Henry Rail Specialist PUCO Railroad Division

Enclosure

cc: File

PUBLIC UTILITIES COMMISSION OF OHIO TRANSPORTATION DEPARTMENT RAIL DIVISION

Date of Assignment: May 28, 2019

Subject: Plans and estimates review for active warning devices at Main Street, Kent (262-564G), Akron Barberton Cluster Railway, Portage County.

DOT #: 262-564G

FINDINGS

On May 28, 2019, the plans and estimates for the above mentioned crossing were received from Akron Barberton Cluster Railway (AB). They were reviewed by Jill Henry, PUCO Rail Specialist, and Shawn Zurfley, FRA/PUCO Field Investigator.

Main Street is a 4 lane urban roadway traveling east/west and intersecting a single track of AB traveling north/south. Existing warning devices include mast mounted lights and gates with short arm cantilevers, pedestrian gates, advanced warning signs, pavement markings and crossbucks.

SUMMARY AND CONCLUSIONS

We reviewed the plans and estimates for the crossing. The plans and estimates appear to be fundamentally correct. Construction authorization is granted for this project with the following conditions:

1) The bungalow being placed in the NE quadrant needs to be placed as far back as possible to try and meet the 25' Ohio Manual of Uniform Traffic Control Devices (OMUTCD) placement recommendation.

Jill Henry PUCO Rail Specialist Date: May 31, 2019

AKRON BARBERTON CLUSTER RAILWAY COMPANY

Andrew Shuster Signal & Communication Supervisor 43 Second Street N.W. Barberton, OH 44203

Tel. 330-813-6133

ashuster@abcrwy.com

Fax: 330-745-4519

5/21/19

Public Utilities Commission of Ohio Jill Henry

Re: Estimate for Railroad Crossing Warning System at Main Street in Kent, Ohio,

Dear Jill Henry,

I am providing this estimate for the crossing package and installation at Main Street,

Material Package, & Installation	\$ 2	272,372.18
Crosier Inc.	\$	70,178.00
Two Gate and cantilever Foundations (note 1)	\$	7,746.00
Electric Service (Included in Crosier Estimate)	\$	0.00
Wintrow Railroad Construction (Provide and Install Allegheny Joints)	\$	30,750.00
Estimated Total	\$.	381,046.18

Please contact me if additional details are required.

Respectfully,

Andrew Shuster

Notes

1: Direct purchase from Fabricated Metals, 60' galvanized gate foundation, \$598 ea. Purchased from Dixie Precast, Pour in place cantilever Foundation \$3275 ea.

DWG. NO.	DESCRIPTION
00	INDEX
01	SITE LAYOUT
02	CROSSING SIGNAL ALIGNMENT
03	SITE LAYOUT NOTES
04	XP4/VIO CIRCUITS
05	XP4 SETUP SHEET
06	TRACK CONNECTION CIRCUITS
07	ENTRANCE GATE CONTROL CIRCUIT
08	ENTRANCE GATE CONTROL CIRCUIT
09	RECORDER
10	BGD
11	ARRESTOR PANEL
12	СТР
13	GATE #1 MECHANISM (NEAR SIDE)
14	GATE #1 LIGHTS (NEAR SIDE)
15	GATE #2 MECHANISM (FAR SIDE)
16	GATE #2 LIGHTS (FAR SIDE)
17	CANT #1 & CANT #2 LIGHTS
18	BATTERY CHARGERS
19	AC POWER DISTRIBUTION
20	RACK FRONT VIEW
21	RACK BACK VIEW
22	SIDE "A"
23	SIDE "C"

REV.	GENERAL NOTES		
AND DEVIC	ATION OF THE CIRCUITS AND EQUIPMENT REPRESENTED HER ES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN ST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BI	EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM	
		AKRON BARBERTON CLU	TEL
	JOHN T. SHARKEY 75147 PROJECTERED PEGISTERED CONTACTER	RATL WAY	SIEN
	JOHN T. SHARKEY 75147 ACG ISTERES SLAMA L ENGINE	LOCATION MAIN STREET	
	75147	KENT, OHIO	

CTC

CTC

CHECKER

RRMP 191.53

DOT NO. 262 564G

SCALE


SHEET

N.T.S.


00 of 23



REVISION BLOCK



- ASSEMBLIÈŚ.
- IN THE LOCATION SHOWN.
- 4.) IN THE LOCATION SHOWN.




CONSTRUCTION NOTES

1.) INSTALL NEW 6' X 6' BUNGALOW IN NORTHEAST QUADRANT.

2.) INSTALL (2) NEW FLASHING LIGHTS WITH GATES AND (2) CANT

3.) METER POLE LOCATION SHOWN ON THE PLAN IS SUBJECT TO CHANGE WITHIN RAILROAD RIGHT-OF-WAY IF UNDERGROUND OBSTRUCTIONS PREVENT THE INSTALLATION OF THE POLE

BUNGALOW LOCATION SHOWN ON THE PLAN IS SUBJECT TO CHANGE WITHIN RAILROAD RIGHT-OF-WAY IF UNDERGROUND OBSTRUCTIONS PREVENT THE INSTALLATION OF THE BUNGALOW



/av	ORIGINAL DATE	1/1//2018	TITLE CROSSING SIGN	
	DESIGNER	CTC	^{SUB} KENT-RAVENNA	CN18008
	DRAFTSMAN	CTC	^{RRMP} 191.53	SCALE N.T.S.
	CHECKER	СТС	^{DOT NO.} 262 564G	SHEET 02 OF 23

OCATION

MAIN STREET KENT, OHIO

AKRON BARBERTON CLUSTER RATLWAY

BACK LIGHTS ON CANTILEVER MAIN MAST ADJUST LIGHT UNIT HORIZONTALLY TO ALIGN AXIS OF BEAM TO A POINT 50 FT. IN APPROACH TO THE SIGNAL ON OPPOSITE SIDE OF TRACK AND IN CENTER OF APPROACH TRAVEL WAY. BACK LIGHTS CANTILEVER ARM ADJUST LIGHT UNIT HORIZONTALLY TO ALIGN AXIS OF BEAM TO A POINT 100 FT. IN APPROACH TO THE SIGNAL ON OPPOSITE SIDE OF TRACK AND IN CENTER OF APPROACH TRAVEL WAY.

BACK LIGHTS ON GATES ADJUST LIGHT UNIT VERTICALLY TO ALIGN AXIS OF BEAM 5 FT. 6 IN. ABOVE PAVEMENT AT A POINT 50 FT. IN APPROACH TO THE SIGNAL ON OPPOSITE SIDE OF TRACK.

ADJUST LIGHT UNIT HORIZONTALLY TO ALIGN AXIS OF BEAM TO CENTER OF APPROACH LANE IN APPROACH TO SIGNAL AT SELECTED ALIGNMENT DISTANCE, MAINTAINING VERTICAL ALIGNMENT. BOTH LAMPS SHOULD BE ALIGNED TO SAME POINT.

FRONT LIGHTS ON CANTILEVER MAST & ARM ADJUST LIGHT UNIT VERTICALLY TO ALIGN AXIS OF BEAM 5FT. 6IN. ABOVE PAVEMENT AT SELECTED ALIGNMENT DISTANCE. BOTH LAMPS SHOULD BE ALIGNED TO SAME POINT.


CANT #2 BACK ARM LIGHTS CANT #1 BACK ARM LIGHTS

CANT #2 FRONT MAST & ARM LIGHTS

LEGEND


CROSSING SIGNAL ALIGNMENT

1.) CROSSING IS LOCATED:



SITE LAYOUT NOTES

41.1537602 LATITUDE LONGITUDE -81.3590482



ADJUSTME	ENT NAME	MDR1		/\\\\\		
NA	ME	HIGHWAY CROSSING	KHQHY	///////////////////////////////////////		
WARNIN	IG TIME	30 SEC		45/550/////////////////////////////////		
CW,	/MD	MD		//\$\$\//////////////////////////////////		
AP	TIME	00 SEC		\$\$/\$ <u>\$</u> \$///////////////////////////////		
CWE	-WT	00 SEC		198/1944////////////////////////////////		
AUX RECOV	ERY DELAY	05 SEC		///////////////////////////////////////		
		TK1 TK2/X/XX3/	///////////////////////////	4/X//\$&\$/X//\$&4/		
TRACK ASSIGNED		ASSIGN	///////////////////////////////////////			
OFFSET DISTANCE		O FT	///////////////////////////////////////	///////////////////////////////////////		
MD RE	ESTART	* /////////////////////////////////////	///////////////////////////////////////			
SUDDEN SI	HUNT ZONE	* /////////////////////////////////////				
POSITIVE	PSEN	DISABLE	///////////////////////////////////////			
START	PSRX	NA	///////////////////////////////////////			
START	PST	NA ////////////////////////////////////	///////////////////////////////////////			
POSE JOINTE	PJEN	DISABLE	///////////////////////////////////////	<u> X </u>		
	PJRX	NA ////////////////////////////////////				
DLILUI	PJDT	NA ////////////////////////////////////	///////////////////////////////////////	///////////////////////////////////////		

BASIC TRACK SETUP								
	TK1	\/%\////%\%						
FREQUENCY	970 HZ							
MASTER/SLAVE	MASTER							
RX ADJUST	100							
TCA	*							
DIRECTION MODE	BI							
LIA	*							
ADVANCED APR. CAL	INACTIVE							
NBS COMP RX	*							
TRK ISLAND ASSIGN	ISL1							
APPROACH LENGTH	520 FT							
AUTO RX	ENABLE							

IXC-A SETUP							
CROSSING TEST MODE	OFF						
FLASH RATE	55FPM						
	IXC-1 //XC-2//XC-3//XC-A						
VOLTAGE REGULATION	ON / ØN / //////////////////////////////						
L1 VOLTAGE	* 10.0 * 10.0						
L2 VOLTAGE	* 10.0 * 10.0						
GATE 1 DELAY	3 SEC 3 SEC						
GATE 2 DELAY	3 SEC 3 8EC						

* PER RAILROAD REQUEST XP4 UNIT TO BE SET IN MOTION DETECTION *

IXC-B SETUP								
CROSSING TEST MODE	OFF							
FLASH RATE	55FPM							
	IXC-1 //XC-2//XC-3//XC-4							
VOLTAGE REGULATION	ON //ØK//////////////////////////////////							
L1 VOLTAGE	* 10.0 * 10.0							
L2 VOLTAGE	* 10.0 * 18.0							
GATE 1 DELAY	3 SEC 3 SEC							
GATE 2 DELAY	3 SEC 3 SEC							


ADVANCED TRACK SETUP							
		TK1	\//xk2////xk3////xk4//				
MOTION DET TIMER	MDEN	DISABLE	X/////X/////X//////				
MOTION DET HMER	MDTT	10 MIN	\//////////////////////////////////////				
	FSEN	DISABLE	\//////////////////////////////////////				
FALSE SHUNT	FSRX	NA	\//////////////////////////////////////				
	FST	NA	V////X////X/////				
	AREN	DISABLE					
APPROACH RELEASE	ARRX	NA	\//////////////////////////////////////				
	ART	NA	\//////////////////////////////////////				
LOS TIME		16 SEC					
IJ-LOS TIME		5 SEC	\//////////////////////////////////////				
NRML_SHHTR_VRSF	HRT	NRML *	\//////////////////////////////////////				
			<u> </u>				

ISLAND SETUP						
	TK1 /XK2///XK3///XK4/					
ENABLE/DISABLE	ENABLE					
FREQUENCY	4.0 KHZ					
LOSS OF SHUNT	4 SEC					
FAULT DELAY	1					

APPROACH 1		NO S	HUNT	100%	SHUNT	50% SHUNT		LIA A
(EA	AST)	RX	PHASE	RX	PHASE	RX	PHASE	± 1
Track 1	Normal							
HUCK I	Standby							
	Normal							
	549900							
	DACH 2 EST)							
Track 1	Normal							
	Standby							
7.rack, 2	Norma							
	5100000							

INITIAL VALUES WHEN PLACED IN SERVICE


SHUNT RECORDS




	APPLICATION SO	FTWARE INFORMATION
	NAME	*
	REV.	1
	CHECKSUM	
	CRC	
	CHASSIS ID	
	LOCATED BEHIND UCI-3	
	Ì) = TAB INTACT = TAB PUNCHED OUT
	EXECUTIVE INFOR	MATION
/DM_		


VPM-3	VERSION	PART NUMBER			
CROSSING SOFTWARE	*	083024-716			








AKRONT	BARBERTON TRATLWAY	CLUSTER			
MAIN STREET KENT, OHIO					
ORIGINAL DATE 1/17/2018	TITLE TRACK CONNEC	TION CIRCUITS			
DESIGNER CTC	SUB KENT-RAVENNA	CTC NO. CN18008			
DRAFTSMAN CTC	RRMP 191.53	SCALE N.T.S.			
CHECKER OTO	DOT NO. OCO. E CAO	SHEET			













 ORIGINAL DATE
 1/17/2018
 TITLE
 BGD


 DESIGNER
 CTC
 SUB
 KENT-RAVENNA
 CTC
 NO. 2018

 DRAFTSMAN
 CTC
 RRMP
 191.53
 SCALE
 N.T.S.

 CHECKER
 CTC
 DOT NO. 262
 564G
 SHEET
 10
 OF 23








AKRON BARBERTON CLUSTER

CONTACT	CLOSED	FUNCTION	TENSION
1B	75-90 DEG.	POWER DOWN	18-28 OZ.
1F	0-70 DEG.	SNUB DOWN	18-28 OZ.
2	0-86 DEG.	POWER UP	18-28 OZ.
3	0-10 DEG.	GATE DOWN	16-24 OZ.
4	82-90 DEG.	GATE CLEAR	16-24 OZ.
5	10-90 DEG.	BELL	16-24 OZ.
6	SPARE	SPARE	16-24 OZ.
7	0-2 DEG.	SNUB	16-24 OZ.



LEGEND:

🔘 = INSULATED NUT

NOTES:

REVISION


BLOCK


* BELL TO BE ELECTRONIC.

→ = INTERNAL GATE WIRES THAT SHARE ELECTRICAL CONNECTIONS WITH OTHER WIRES THAT ARE ASSIGNED THE SAME NUMBER.

> REFER TO SHEET 14 FOR GATE ARM LIGHT WIRING


ADD STRAP FROM: 3A TO 3B





av	ORIGINAL DATE	1/1//2018	GATE #1 LIGHTS	S (NEAR SIDE)
			SUB KENT-RAVENNA	CTC NO. CN18008
	DRAFTSMAN	CTC	RRMP 191.53	SCALE N.T.S.
	CHECKER	CTC	^{DOT NO.} 262 564G	SHEET 14 OF 23

CONTACT	CLOSED	FUNCTION	TENSION
1B	75-90 DEG.	POWER DOWN	18-28 OZ.
1F	0-70 DEG.	SNUB DOWN	18-28 OZ.
2	0-86 DEG.	POWER UP	18-28 OZ.
3	0-10 DEG.	GATE DOWN	16-24 OZ.
4	82-90 DEG.	GATE CLEAR	16-24 OZ.
5	10-90 DEG.	BELL	16-24 OZ.
6	SPARE	SPARE	16-24 OZ.
7	0-2 DEG.	SNUB	16-24 OZ.



LEGEND:

🔘 = INSULATED NUT


NOTES:

* BELL TO BE ELECTRONIC.


→ = INTERNAL GATE WIRES THAT SHARE ELECTRICAL CONNECTIONS WITH OTHER WIRES THAT ARE ASSIGNED THE SAME NUMBER.


> REFER TO SHEET 16 FOR GATE ARM LIGHT WIRING


ADD STRAP FROM: 3A TO 4A AND 4A TO 4B



REVISION BLOCK











SPARE T1_APP 50T T1_ALL 45T ROR-4 PO DB1 BGD B1 SPARE RCDR TB1-4 RCDR TB6-1	21 20 19 18 17 16 15 14 13	SPARE VI01 J3-5 VI01 J3-2 VI01 J3-11 PO DB3 BGD N1 SPARE RCDR TB1-3 RCDR TB6-2	
SPARE MDSA-1 B+ MB BATT+ 	12 11 10	RLR-7/ROR-7 MDSA-1 B- MN BATT- L	
MB BUSS (TOP)	AA	MN BUSS (BOTTOM)	


57	SPARE
56	I SPARE
55	I XIP-B N
54	XIP-B L1B-N
53	BGD N2
52	XIP-A G1-
51	RA5T
50	RA15T
49	XIP-A N
48	IXC-A J5-2
47	IXC-A J5-10
46	SPARE
45	GPR 1E
44	IXC-A J5-14
43	RCDR TB4-15
42	RCDR TB1-1
41	XIP-A L1B-N
40	XN BATT-
СА	XN BUSS (BOTTOM)
	56 55 54 53 52 51 50 49 48 47 46 45 44 43 42 41 40











6' X 6' ALUMINUM BUNGALOW PTMW PN:91000564 D-1	SIDE "D"
C C C C C C C C C C C C C C C C C C C	MAIN STREET KENT, OHIO SIDE "C" NT-RAVENNA 191.53 SCALE 1"=2' SCALE 1"=2' SCALE 1"=2' SCALE 1"=2' SCALE 1"=2' SCALE SHEET 23 OF 23

Akron Barberton Cluster Railway Kent, OH. MP 191.53 DOT# 262 564G CTC Project Estimate

ENGINEERING					
Description	Qty	UOM	Unit Price	Amount	
SIGNAL DESIGNER	80	HR	32.69	\$2,615.20	
SIGNAL CHECKER, LEVEL 1	20	HR	43.72	\$874.40	
SIGNAL CHECKER, LEVEL 2/FIELD ENGINEER	10	HR	35.00	\$350.00	
SUBTOTAL				\$3,839.60	
G&A BURDEN FOR LABOR (162%)				\$6,220.15	
FIXED FEE (14%)				\$1,408.37	
ENGINEERING TOTAL				\$11,468.12	

PROJECT MANAGEMENT					
Description	Qty	UOM	Unit Price	Amount	
SENIOR SIGNAL ENGINEER	16	HR	\$100.00	\$1,600.00	
PROJECT MANAGER	40	HR	\$39.66	\$1,586.40	
CONSTRUCTION MANAGER	160	HR	\$39.66	\$6,345.60	
ACCOUNTING, LEVEL1	16	HR	\$39.81	\$636.96	
ADMINISTRATIVE	4	HR	\$26.44	\$105.76	
SUBTOTAL				\$10,274.72	
G&A BURDEN FOR LABOR (162%)				\$16,645.05	
FIXED FEE (14%)				\$3,768.77	
PROJECT MANAGEMENT TOTAL				\$30,688.53	

EAF LABOR					
Description	Qty	UOM	Unit Price	Amount	
EAF MANAGER	8	HR	\$28.00	\$224.00	
EAF LEAD FORMAN	24	HR	\$20.19	\$484.56	
LEAD WIREMAN	40	HR	\$19.25	\$770.00	
WIREMAN	24	HR	\$15.00	\$360.00	
TEST	16	HR	\$36.00	\$576.00	
QC	8	HR	\$28.85	\$230.80	
SUBTOTAL				\$2,645.36	
G&A BURDEN FOR LABOR (162%)				\$4,285.48	
FIXED FEE (14%)				\$970.32	
EAF LABOR TOTAL				\$7,901.16	

CONSTRUCTION LABOR					
Description	Qty	UOM	Unit Price	Amount	
SIGNAL FOREMAN	160	HR	\$29.04	\$4,646.40	
SIGNALMAN	160	HR	\$23.40	\$3,744.00	
SIGNAL HELPER	320	HR	\$19.00	\$6,080.00	
SUBTOTAL				\$14,470.40	
G&A BURDEN FOR LABOR (162%)				\$23,442.05	
FIXED FEE (14%)				\$5,307.74	
CONSTRUCTION LABOR TOTAL				\$43,220.19	

Akron Barberton Cluster Railway Kent, OH. MP 191.53 DOT# 262 564G

CTC Project Estimate

CONSTRUCTION LABOR EXPENSES					
Description	Qty	UOM	Unit Price	Amount	
EMPLOYEE MEALS (PER DIEM)	64	EA	\$30.00	\$1,920.00	
EMPLOYEE LODGING	64	EA	\$70.00	\$4,480.00	
MOBILIZATION	3	EA	\$1,500.00	\$4,500.00	
SUBTOTAL				\$10,900.00	
CONSTRUCTION LABOR EXPENSES TOTAL				\$10,900.00	

CONSTRUCTION EQUIPMENT					
Description	Qty	UOM	Unit Price	Amount	
TRUCK, PU, 1 TON CREW CAB	160	HR	\$15.71	\$2,513.60	
TRAILER, UTILITY (12,000lb SC410)	160	HR	\$7.55	\$1,208.00	
RENTAL EQUIPMENT (FORKLIFT - 8K)	2	WK	\$1,400.00	\$2,800.00	
RENTAL EQUIPMENT (BACKHOE W/18" BKT)	2	WK	\$1,200.00	\$2,400.00	
EQUIPMENT DELIVERY/PICKUP	4	LS	\$195.00	\$780.00	
SUBTOTAL				\$9,701.60	
CONSTRUCTION EQUIPMENT TOTAL				\$9,701.60	

MATERIAL					
Description	Qty	UOM	Unit Price	Amount	
HOUSE MATERIAL (SEE ATTACHED DETAIL)	1	LS		\$59,076.74	
FIELD MATERIAL (SEE ATTACHED DETAIL)	1	LS		\$83,150.84	
CONCRETE	20	YD	\$500.00	\$10,000.00	
COVER ROCK (3/4" CRUSHED - WHITE)	10	TN	\$26.50	\$265.00	
FREIGHT & CONTAINER PRICE	1	LS	\$6,000.00	\$6,000.00	
SUBTOTAL				\$158,492.58	
MATERIAL TOTAL				\$158,492.58	

TOTAL PROJECT ESTIMATE

\$272,372.18

HOUSE MATERIALS				
DESCRIPTION	QTY	UOM	UNIT PRICE	TOTAL PRICE
Bungalow, Alum. 6 X6 w/Heater P/N 91000564 D-1, PTMW (WLE SPECS)	1	EA	\$9,477.00	\$9,477.00
Wrench, AAR terminal - 11", P/N 032619-9X, Siemens	1	EA	\$43.63	\$43.63
Sensor, Hermetic Door Switch, P/N 70168986, Allied Electric	1	EA	\$4.99	\$4.99
Actuator, Hermetic Door Switch, P/N 70168991, Allied Electric		EA	\$1.99	\$1.99
Decal, Danger 240V (5"X3.5"), P/N 3XDU5, Grainger		EA	\$2.94	\$2.94
Decal, MUTCD Emergency Notification, 30"X18", Eagle Traffic		EA	\$68.00	\$68.00
Wire, Case, #16AWG 1000' spool, Blue, P/N 152-11-3002, Okonite		EA	\$198.00	\$99.00
Wire, Case, #10AWG 1000' spool, Blue, P/N 152-11-3038. Okonite	0.5		\$407.00	\$203.50
Wire, Case, #6AWG, Green, P/N N6GNM, Reynolds	100		\$0.35	\$35.00
Wire, Case, #6AWG, Black, P/N N6BM, Reynolds Wire, Case, #6AWG. Red, P/N N6RD, Reynolds	100 100		\$0.35 \$0.35	\$35.00 \$35.00
MDA-II With Current Sensors DTMF Radio and GFD-Complete, P/N NAS-WLE, NAS		EA	\$6,431.00	\$6,431.00
MDA-II with current sensors DTMF Radio and GrD-Complete, P/N NAS-WEE, NAS-MEE, NAS-MEE, NAS-MEE, NAS-WEE, NAS-WEE		EA	\$474.00	\$474.00
XP4 Chassis P/N 16-220000433, GE **(Populated as shown on Plans)**		EA	\$27,450.00	\$27,450.00
XIP-20 w/Lamp Resistor, P/N 227561-000, Alstom		EA	\$602.00	\$1,204.00
Cable, XIP 8 ft (cable #1) (need 1 for XP4 Assy) P/N 075046-001, Alstom		EA	\$104.00	\$208.00
Cable, XIP 8 ft (cable #2) (need 1 for XP4 Assy) P/N 075047-001, Alstom		EA	\$104.00	\$208.00
Current Sensor w/25ft. Cable, P/N CS100-CBL-25, NAS		EA	\$90.00	\$180.00
Relay, 500 Ohm, 6PT, Nuetral relay, plug-in, P/N A62-0262, Alstom		EA	\$1,256.80	\$3,770.40
Plugboard, Kit (1E/3E test posts) P/N 59686-019-02, Alstom		EA	\$125.00	\$375.00
Wrench, 3E test tool, P/N P03-0320, Alstom		EA	\$51.10	\$51.10
Extractor Tool, Terminal clip, P/N 032619-25, Siemens	1	EA	\$1.18	\$1.18
Relay, 8-pin KRPA style, 10A/240VAC, P/N 70198711, Allied	1	EA	\$18.62	\$18.62
Relay, 8-pin KRPA style, 10A/12VDC, P/N 70199265, Allied	2	EA	\$15.87	\$31.74
Socket, 8-pin KRPA style, P/N 70199343, Allied		EA	\$5.61	\$16.83
Spring, Hold down for KRPA style relay, P/N 70198576, Allied		EA	\$0.33	\$0.99
Battery Charger, ETC-12V 40AMP, P/N 520740, Railway Equipment		EA	\$590.00	\$1,180.00
Battery, NiCad 340 A.H., P/N SPL-340, Saft		EA	\$310.50	\$2,794.50
Battery, NiCad 250 A.H., P/N SPL-250, Saft		EA	\$225.00	\$2,250.00
Terminal, Battery, 3-PT, P/N 225481-000, J&A Industries		EA	\$24.25	\$97.00
Battery Tray 12'x38", Holds (5) Batteries, P/N 027004-01, J&A		EA	\$51.00	\$204.00
Nema Plug, Locking, 15 Amp/240V, P/N L6-15P, Reynolds		EA EA	\$14.50 \$139.56	\$29.00 \$139.56
Power Indicator, 2 Eye/4 Wire, Wago connector, P/N LC2-001WB-WG4, Velcorp Gems SO Cord, 14 AWG/4 Conductor, P/N SJOOW-14-4-BLK-250R, Graybar	100		\$139.56	\$139.30
Tie-wrap, 11 1/2", PKG 100, Black, P/N LTS11-0, Vantex		EA	\$20.21	\$20.21
Tie-wrap, mounting, PKG 100, P/N TYM, Vantex		EA	\$20.21	\$20.21
Loom, Spiral Wrap 100', Black, P/N SW38-0, Vantex		EA	\$48.54	\$48.54
Panduit, Wire Duct, 2"X3"X6' Gray, P/N G2X3LG6, Graybar		EA	\$4.61	\$13.83
Panduit, Cover. 6' Grav. P/N C2LG6. Gravbar		EA	\$1.16	\$3.48
Terminal, 2X6 W/ Flat nut/washer, P/N 220-0101, Rebel		EA	\$10.45	\$94.05
Terminal, Block, 2 3/8" center - 2 post w/hardware, P/N 220-0301, Rebel		EA	\$3.95	\$31.60
Terminal, 4-post, Block Kit, w/ 14-24 AAR Hardware, P/N B2700A2C1WH, Erico	17	EA	\$21.15	\$359.55
RailSurge Plane Strip Busbar (36"), P/N B2700HC36, Erico		EA	\$36.90	\$36.90
Connector, Buss strap (1" - 36 holes), P/N 9A2216-36, L&W Industries	2	EA	\$17.89	\$35.78
Connector, 2 3/8", strap style, P/N 220-0507, Rebel	10	EA	\$0.70	\$7.00
Connector, 1", flat, strap style, P/N 220-0501, Rebel		EA	\$0.30	\$3.00
Arrestor, Air Gap, With Cover, P/N 4000-44585-001X, Siemens		EA	\$24.80	\$520.80
Equalizer, Air Gap, with Cover/Hardware , P/N 4000-44700-001X, Siemens		EA	\$23.36	\$46.72
Binding Nut, P/N 13073-000, Rebel	200		\$0.18	\$36.00
Clamp Nut, P/N 13079-000, Rebel	100		\$0.14	\$14.00
Insulated Nut, 1 3/16" , P/N 023408-1X, Safetran		EA	\$4.00	\$100.00
Washer, P/N 013074-000, Rebel	200		\$0.07	\$14.00
Gold Test Nut, P/N 13296-001, Rebel	100		\$0.55 \$1.75	\$55.00
1' Test Link, Flat, P/N 32257-002, Rebel	100		\$1.75	\$175.00
Terminal Ring, HD, 1/4", insulated, #14 - #16 (yellow w/blk stripe), P/N NC-10HDB, Vantex	100	EA EA	\$0.83 \$29.87	\$83.00 \$59.74
Terminal, Ring, 1/4", insulated #14 - #16 (100 pk), P/N NB14, Vantex Terminal, Ring, 1/4" insulated, #10 - #12 (100 pk), P/N NC14, Vantex		EA EA	\$29.87	\$62.48
Terminal, Ring, 1/4" insulated, #10 - #12 (100 pk), P/N NC14, Vantex		EA	\$31.24	\$20.10
Terminal, Ring, 3/8" non-insulated, #6, Battery Lug, P/N T6-38, Vantex		EA	\$0.97	\$14.55
	_0		TOTAL	\$59,076.74
			IUIAL	\$37,0/0./4

FIELD MATERIALS				
DESCRIPTION	QTY	UOM	UNIT PRICE	TOTAL PRICE
Cable, 7/C#6, Armored, 206-11-6247, Okonite	1000	FT	\$8.11	\$8,110.00
Cable, 7C#14, Armored, 206-11-6887, Okonite	500	FT	\$2.99	\$1,495.00
Cable, 3C#6, Armored, #206-11-6243, Okonite	250	FT	\$6.00	\$1,500.00
Wire, Track, 2C/#6, Twist, Solid, 113-12-3933, Okonite	300	FT	\$1.86	\$558.00
Tape, Marker - "Buried RR line"/"Buried electrical line"	2	ROLL	\$15.99	\$31.98
Bootleg Kit, Crossing complete, Wood, 1 Track, CTC Inc.	2	EA	\$500.00	\$1,000.00
Bond Wire, 7 1/2" XS Style, P/N SBS24883, Erico	200	EA	\$5.12	\$1,024.00
Connector, Track, Web of Rail, P/N SBTBBU4A, Erico	200	EA	\$4.63	\$926.00
Rail Welding Material F80, P/N SB25, Erico	100	EA	\$1.56	\$156.00
Wheel, grinding, P/N SB22122, Erico	4	EA	\$35.87	\$143.48
Wire, Bondstrand, 3/16" Black (500'), P/N SBSLINSUL, Erico	0.5	FT	\$595.00	\$297.50
5/8" X 8' Copper Ground Rod P/N 615880. Erico	8	EA	\$9.50	\$76.00
5/8" Ground Rod Weld, P/N SBNT1161G, Erico	8	EA	\$4.48	\$35.84
Wire, Ground, #6AWG, Bare Copper, Graybar	100	FT	\$0.34	\$34.00
FSS-IA, Tunable NBS. P/N 250850-000, GE	2	EA	\$847.00	\$1,694.00
Shunt Enclosure, Orange, P/N 500-400-100-09-Orange, G&B	2	EA	\$374.00	\$748.00
Cantilever, 22' Alum. walkout, w/pour in-place foundation, Progress Rail	1	EA	\$18,000.00	\$18,000.00
Cantilever, 24' Alum. walkout, w/pour in-place foundation, Progress Rail	1	EA	\$20,000.00	\$20,000.00
Mast, Gate, 18'X5" w/pigtail (single-sided Jct Box), P/N 715-324-2-GS, WCH	2	EA	\$578.00	\$1,156.00
Ict box, Gate, 5" single hole w/24 terminals, P/N 2149-A-139, WCH	2	EA	\$462.00	\$924.00
Gate, Model 3597, P/N 3597-131-P-H-M1 (WLE Spec), WCH	2	EA	\$3,762.00	\$7,524.00
Crossarm Assy, 5" Mtg., 1 Way BACK, P/N 975-0804-XA-12, WCH	2	EA	\$503.00	\$1,006.00
Lights, 12" LED, P/N 433121680XLTC-00, Arms	16	EA	\$74.00	\$1,184.00
Counterweight Package, P/N 070755-18X, Siemens	2	EA	\$3,261.00	\$6,522.00
Sign, Crossbuck, No brackets/hardware, P/N 070-0065, Rebel Railway	4	EA	\$84.00	\$336.00
5" Sign Kit, Brackets/extensions/Ubolts/hardware, P/N 070-5008, Rebel Railway	6	EA	\$56.70	\$340.20
Wind Bracket, 36", Tusk style, P/N 2010-001-01, RDG	2	EA	\$136.00	\$272.00
Bell, Electronic, 5" Base, P/N EB-3-360-5, GSI	2	EA	\$165.00	\$330.00
Gate Keeper, 2-Way, w/Hardware & Buffer Spring, P/N SK-1000-2W, GSI	2	EA	\$1,100.00	\$2,200.00
E-Z Gate 42'(Vertical stripe)LED gate w/lamp kit, P/N 9298-6154, Railway Equip	2	EA	\$649.00	\$1,298.00
Sleeve, 4' Aluminum, P/N 92958, Railway Equipment	2	EA	\$39.00	\$78.00
Wrench, Torque (KIT), P/N 2590-K-9, WCH	1	EA	\$191.00	\$191.00
Sign, Emergency, ENS, 15"X9" Blue, Eagle Traffic	2	EA	\$38.00	\$76.00
Field cable Tag Kit, P/N FLDTGKT, CTC Inc.	1	EA	\$1,100.00	\$1,100.00
Schedule 40 2" & 4" PVC Conduit Kit with Elbows	1	LOT	\$2,500.00	\$2,500.00
Duct seal, 1lb, P/N 31-601, Graybar	1	EA	\$2.93	\$2.93
Duct seal, 5lb, P/N 31-605, Graybar	1	EA	\$9.41	\$9.41
Lock, Barrel Style	6	EA	\$45.25	\$271.50
Total \$83,150.84				

6/6/2018

673 Norton Ave. Barberton, Ohio 44203

ABC Railway

Tele: (330) 753-2983

Various Locations

Insulated Joints Installation - Proposal

Attn: Andrew R. Shuster Phone: 330-813-6133 Email: ashuster@abcrwy.com

Wintrow Construction Corp. will provide all supervision, labor, equipment, and specified materials to complete the following described work:

Main St., Wadsworth, Ohio

 Furnish and install 8-Insulated joints for crossing signal project New Alleghany glue joints will be furnished-39' overall length Insulated joints will be bolted in place Location of joints to be marked by others

	Total:	\$31,825
	Labor/Equip:	\$12,931
	Materials:	\$18,894
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$1,971)

Medina Line Rd., Norton, Ohio

1. Furnish and install 8-Insulated joints for crossing signal project New Alleghany glue joints will be furnished-39' overall length Insulated joints will be bolted in place Location of joints to be marked by others

	Total:	\$30,544
	Labor/Equip:	\$11,650
	Materials:	\$18,894
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$1,971)

Main St., Kent, Ohio

 Furnish and install 1-Insulated joints in curve closure rail in turnout south of road New Alleghany glue joint will be furnished-39' overall length Insulated joint will be bolted in place

Location of joint to be marked by others

	Total:	\$4,315
Labo	r/Equip:	\$1,649
Μ	aterials:	\$2,666
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$246)

673 Norton Ave. Barberton, Ohio 44203

Tele: (330) 753-2983

ABC Railway

Various Locations

Insulated Joints Installation - Proposal

Contingencies/Notes

Sales Taxes Not included in Quotation

No Warranty or Guarantees are apart of this proposal

Payment: Net 30 Days. Late payment charge of 1 1/2% (18% annum) will be charged on all past due balances.

We are not responsible for repair or relocation of Under Ground Utilities

Weather conditions prevail and may affect the construction schedule.

Track must be free of rail cars and rail traffic.

ONE Mobilization is included in the quotation.

All work is at straight time labor rates unless specified otherwise in the quotation Work description and material specifications haven't as yet been approved by the railroad

Engineering, plans and layout survey by others.

Material Subject to Pryor Sale

Progress payments are to be paid by the 15th of the month.

No costs for possible flagman services is included

Costs include continuous work windows with no train delays

*No destressing of rails is included-Rail temperature is

assumed to be within rage when installation is scheduled*

No wiring or bonding is included in pricing

From:Andrew ShusterTo:Henry, JillSubject:Fw: Main St. Kent, Ohio EstimateDate:Wednesday, May 29, 2019 7:15:57 AM

Jill, this is Croziers estimate for Main Street Kent

Andrew R. Shuster

Signals and Communications Supervisor Akron Barberton Cluster Railway 43 Second Street NW, Barberton, Ohio 44203 330-813-6133 cell | ashuster@abcrwy.com email

From: Bob Crosier <trailrnrbob@hotmail.com>
Sent: Monday, June 18, 2018 5:16 AM
To: Andrew Shuster
Subject: Main St. Kent, Ohio Estimate

The following estimate is for crossing pre-installation construction at Main Street Kent, Ohio Portage Co DOT 262564G

Labor $$18 \times 180 \text{ hr} = 3240$ Operator $25 \times 180 \text{ hr} = 4500$ Project Man. $50 \times 180 \text{ hr} = 9000$ Admin $30 \times 3 \text{ hr} = 90$ sub total labor 16830.00 Labor total G&A x 1.6 = \$26928.00

Excavator E32 31.20 x 80 hr = 2496 Backhoe 580 42.33 x 20 hr = 846.6 Excavator E55 40.20 x 180 hr = 7236 Dump Truck 40 x 30 hr = 1200 Directional Drill 59.62 x 24 hr =1430.88 Locator 8.75 x 10 hr = 87.50 Equip truck 21.35 x 180 hr = 3843 Digger Derrick 55.20 x 18 hr = 993.60 Tamper 4.25 x 20 hr = 85 Traffic cones .13 x 180 hr = 23.40 Traffic signs .23 x 180 hr = 41.40

```
Cut off saw 3.50 x 20 hr = 70
Hydra breaker 34.10 x 24 hr = 818.40
Hydra tamper 17.05 x 20 = 341
Equipment total = $19512.78
185' - 5" pvc conduit @ 3.50 = 647.50
2 - 5" 90s @ 22 = 44
1 - 5" 45 @ 21
6 - 5" coup @ 5.15 = 30.90
240' - 4" pvc conduit @ 2.20 = 528
8 - 4" sweeps @ 25 = 200
6 - 4" 45s @ 11.50 = 69
20 - 4" coup @ 2.22 = 44.40
220' - 2" pvc conduit @ .94 = 206.80
4 - 2" 45s @ 2.10 = 8.40
3 - 2" sweeps @ 18.50 = 55.50
2 - ground rods @ 17.75 = 35.50
750' - pull rope @ .14 = 105
1 - 17x30x18 pull box @ 385
1 - 24x36x18 pull box @ 505
2 cans pvc cement @ 10 = 20
20' - 3" steel conduit @ 11.25 = 225
10 bags cement @ 4.50 = 45
60 tons limestone @ 25 = 1500
Material total $4676.00
Total labor $26928.00
Total equip $19512.78
Total material $4676.00
sub total $51116.78
10% profit $5111.68
Asphalt/concrete cutting $500.00
Concrete contractor pour in place found. $6000.00
Curbs and walks $4000.00
Road opening permit $450.00
Asphalt $3000.00
Estimate total $70178.46
Thank you,
Bob Crosier
```

Crosier Industrial Construction LLC

8938 Peck Rd Ravenna, Ohio 44266 330 592 3082

PUBLIC UTILITIES COMMISSION OF OHIO TRANSPORTATION DEPARTMENT RAIL DIVISION

Date of Assignment: May 28, 2019

Subject: Plans and estimates review for active warning devices at Medina Line Road (265-079J), Akron Barberton Cluster Railway, Medina County.

DOT #: 265-079J

FINDINGS

On May 28, 2019, the plans and estimates for the above mentioned crossing were received from Akron Barberton Cluster Railway (AB). They were reviewed by Jill Henry, PUCO Rail Specialist, and Shawn Zurfley, FRA/PUCO Field Investigator.

Medina Line Road is a 2 lane rural roadway traveling north and south and intersecting a single track of AB traveling east/west. Existing warning devices include mast mounted lights and gates, advanced warning signs, pavement markings and crossbucks.

SUMMARY AND CONCLUSIONS

We reviewed the plans and estimates for the crossing. The plans and estimates appear to be fundamentally correct. Construction authorization is granted for this project.

Jill Henry PUCO Rail Specialist Date: May 31, 2019

AKRON BARBERTON CLUSTER RAILWAY COMPANY

Andrew Shuster Signal & Communication Supervisor 43 Second Street N.W. Barberton, OH 44203

Tel. 330-813-6133

ashuster@abcrwy.com

Fax: 330-745-4519

29 June 2018

Public Utilities Commission of Ohio Jill Henry

Re: Estimate for Railroad Crossing Warning System at Medina Line Road in Norton, Ohio

Dear Jill Henry,

I am providing this estimate for the crossing package and installation at Medina Line Rd.,

CTC Managed Services, Material Package, & Installation	\$ 153,050.02
Crosier Inc.	\$ 24,317.66
Two Gate Foundations (note 1)	\$ 1,196.00
Electric Service	\$ 3,500.00
Wintrow Railroad Construction (Provide and Install Allegheny Joints)	\$ 30,544.00
Estimated Total	\$ 212,607.68

Please contact me if additional details are required.

Respectfully,


Andrew Shuster


Notes

1: Direct purchase from Fabricated Metals, 60' galvanized gate foundation, \$598 ea.


DWG. NO.	DESCRIPTION
00	INDEX
01	SITE LAYOUT
02	CROSSING SIGNAL ALIGNMENT
03	SITE LAYOUT NOTES
04	CROSSING CONTROL CIRCUITS
05	RELAYS
06	RECORDER
07	BGD
08	SSCC III PLUS
09	1LSP
10	СТР
11	GATE #1 MECHANISM (NEAR SIDE)
12	GATE #1 LIGHTS (NEAR SIDE)
13	GATE #2 MECHANISM (FAR SIDE)
14	GATE #2 LIGHTS (FAR SIDE)
15	BATTERY CHARGERS
16	AC POWER DISTRIBUTION
17	RACK FRONT VIEW
18	RACK BACK VIEW
19	SIDE "A"
20	SIDE "C"

	REV.		GENERAL NOT	ËS		
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
	ND DEVICI	ES ARE CONNECTED TO FORM A	A COMPLETE SYSTEM, OR	AN EFFECTIVE SUBSY	STEM. SUCH SYSTEM OR	SUBSYSTEM
PICAL: N PICAL:	MU	<u>St be given complete circut</u>	I AND UPERATIONAL TES	IS BEFORE BEING PLA	ued in regular operat	<u>IUN.</u>
PICAL: N PICAL:						
PICAL: N PIC						
PICAL: N ORIGINAL DATE 1/15/2018 TITLE INDEX		STATE OF ON OTHER				
DESIGNER CTC SUBWADSWORTH-RITTMAN CTC NO. CN18007	à	JOHN T. SHARKEY 75147	ABC		RATLWA	Y) (CR 2)





- - IN THE LOCATION SHOWN.
- 4.) IN THE LOCATION SHOWN.
- 5.) CREW LIGHT RED IN COLOR.



CONSTRUCTION NOTES


1.) INSTALL NEW 6' X 6' BUNGALOW IN SOUTHWEST QUADRANT.

2.) INSTALL (2) NEW FLASHING LIGHTS WITH GATES.

3.) METER POLE LOCATION SHOWN ON THE PLAN IS SUBJECT TO CHANGE WITHIN RAILROAD RIGHT-OF-WAY IF UNDERGROUND OBSTRUCTIONS PREVENT THE INSTALLATION OF THE POLE

BUNGALOW LOCATION SHOWN ON THE PLAN IS SUBJECT TO CHANGE WITHIN RAILROAD RIGHT-OF-WAY IF UNDERGROUND OBSTRUCTIONS PREVENT THE INSTALLATION OF THE BUNGALOW

6.) POWER OFF LIGHT (SOLID AC) (FLASH DC)



CROSSING SIGNAL ALIGNMENT

LEGEND

GATE #1	FRONT MAST LIGHTS
GATE #1	BACK MAST LIGHTS
GATE #2	FRONT MAST LIGHTS

GATE #2 BACK MAST LIGHTS

FRONT LIGHTS ADJUST LIGHT UNIT VERTICALLY TO ALIGN AXIS OF BEAM 5FT. 6IN. ABOVE PAVEMENT AT SELECTED ALIGNMENT DISTANCE. BOTH LAMPS SHOULD BE ALIGNED TO SAME POINT.


ADJUST LIGHT UNIT HORIZONTALLY TO ALIGN AXIS OF BEAM TO CENTER OF APPROACH LANE IN APPROACH TO SIGNAL AT SELECTED ALIGNMENT DISTANCE, MAINTAINING VERTICAL ALIGNMENT. BOTH LAMPS SHOULD BE ALIGNED TO SAME POINT.

BACK LIGHTS ADJUST LIGHT UNIT VERTICALLY TO ALIGN AXIS OF BEAM 5 FT. 6 IN. ABOVE PAVEMENT AT A POINT 50 FT. IN APPROACH TO THE SIGNAL ON OPPOSITE SIDE OF TRACK.

ADJUST LIGHT UNIT HORIZONTALLY TO ALIGN AXIS OF BEAM TO A POINT 50 FT. IN APPROACH TO THE SIGNAL ON OPPOSITE SIDE OF TRACK AND IN CENTER OF APPROACH TRAVEL WAY.


AKRONBARBERTONCLUSTER RATLUAY

1.) CROSSING IS LOCATED:




SITE LAYOUT NOTES

LATITUDE 41.0152265 LONGITUDE -81.6879500




ST RELAY LAYOUT




LEGEND:

1TR = TRACK RELAY (1T) 2TR = TRACK RELAY (2T) 3TR = TRACK RELAY (3T) OOS1R = OUT OF SERVICE RELAY




EXAMPLE





ST1, 400000 500Ω, 6FB, NEUTRAL


✓ CONTACT, NOT USED▼ CONTACT, USED











RAFTSMAN

CHECKER

CTC


CTC


24.06


^{DOT NO.} 265 079J


NTS

07 OF 20










CONTACT	CLOSED	FUNCTION	TENSION	
1B	75-90 DEG.	POWER DOWN	18-28 OZ.	
1F	0-70 DEG.	SNUB DOWN	18–28 OZ.	
2	0-86 DEG.	POWER UP	18-28 OZ.	
3	0-10 DEG.	GATE DOWN	16-24 OZ.	
4	82-90 DEG.	GATE CLEAR	16-24 OZ.	
5	10-90 DEG.	BELL	16-24 OZ.	
6	SPARE	SPARE	16-24 OZ.	
7	0-2 DEG.	SNUB	16-24 OZ.	



LEGEND:

\bigcirc = insulated nut

NOTES:

REVISION


BLOCK


* BELL TO BE ELECTRONIC.


→ = INTERNAL GATE WIRES THAT SHARE ELECTRICAL CONNECTIONS WITH OTHER WIRES THAT ARE ASSIGNED THE SAME NUMBER.

> REFER TO SHEET 12 FOR GATE ARM LIGHT WIRING


ADD STRAP FROM: 3A TO 3B AND 3B TO 4B







CONTACT	CLOSED	FUNCTION	TENSION
1B	75-90 DEG.	POWER DOWN	18-28 OZ.
1F	0-70 DEG.	SNUB DOWN	18-28 OZ.
2	0-86 DEG.	POWER UP	18-28 OZ.
3	0-10 DEG.	GATE DOWN	16-24 OZ.
4	82-90 DEG.	GATE CLEAR	16-24 OZ.
5	10-90 DEG.	BELL	16-24 OZ.
6	SPARE	SPARE	16-24 OZ.
7	0-2 DEG.	SNUB	16-24 OZ.



LEGEND:

\bigcirc = insulated nut

NOTES:


REVISION


BLOCK


- * BELL TO BE ELECTRONIC.
- → = INTERNAL GATE WIRES THAT SHARE ELECTRICAL CONNECTIONS WITH OTHER WIRES THAT ARE ASSIGNED THE SAME NUMBER.

REFER TO SHEET 14 FOR GATE ARM LIGHT WIRING

ADD STRAP FROM: 3A TO 3B











I SPARE I	27	I SPARE I
00S2R-25	26	00S2R-22
CC56	25	CC54
00S1R-35	24	00S1R-32
CC52	23	I CC50 I
1 1TR 15	22	1TR 12
TD-4 B	21	TD-4 N
3TR 22	20	SPARE
3TR 15	19	3TR 12
2TR 15	18	2TR 12
PO DB1	17	PO DB3
2TR 22	16	SPARE
BGD INPUT 1	15	BGD INPUT 2
SPARE	14	RLR 7
RCDR TB6-1	13	RCDR TB6-2
RCDR TB1-4	12	RCDR TB1-3
1 1TR 22	11	SPARE
MB BATT+	10	MN_BATT
MB BUSS (TOP)	AA	MN BUSS (BOTTOM)

SPARE	48	SPARE
SPARE	47	SPARE
CC58	46	SSCC J3-9
DOOR SWITCH	45	SSCC J3-11
BGD INPUT 3	44	BGD INPUT 4
RCDR TB1-2	43	RCDR TB1-1
CC58T	42	RCDR TB4-15
1LSP B-BATT	41	1LSP N-BATT
XB BATT+	40	XN BATT—
XB BUSS (TOP)	СА	XN BUSS (BOTTOM)











AKRON BARBERTON CLUSTER





	side to field Side "C"		
BUN	ALUMINUM GALOW 1000564 D—1		SIDE "D"
	SIDE "A"		
THIS S	SIDE TO TRACKS		
С.	LOCATION	BARBERTON RATLWAY	JSTER
C vay	ORIGINAL DATE 1/15/2018 DESIGNER CTC DRAFTSMAN CTC CHECKER CTC	NORTON, OHIO TITLE SIDE "C" SUB WADSWORTH-RITTMAN RRMP 24.06 DOT NO. 265 079J	CN18007 1"=2' 20 of 20

Akron Barberton Cluster Railway Norton, OH. - Medina Line Rd DOT # 265 079J CTC Project Estimate

ENGINEERING					
Description	Qty	UOM	Unit Price	Amount	
SIGNAL DESIGNER	56	HR	33.65	\$1,884.40	
SIGNAL CHECKER, LEVEL 1	16	HR	43.72	\$699.52	
SIGNAL CHECKER, LEVEL 2/FIELD ENGINEER	8	HR	52.88	\$423.04	
SUBTOTAL				\$3,006.96	
G&A BURDEN FOR LABOR (164%)				\$4,931.41	
FIXED FEE (10%)				\$793.84	
ENGINEERING TOTAL				\$8,732.21	

PROJECT MANAGEMENT					
Description	Qty	UOM	Unit Price	Amount	
SENIOR SIGNAL ENGINEER (PE STAMP)	8	HR	\$100.00	\$800.00	
PROJECT MANAGER	40	HR	\$36.06	\$1,442.40	
CONSTRUCTION MANAGER	40	HR	\$39.61	\$1,584.40	
ACCOUNTING, LEVEL1	8	HR	\$40.86	\$326.88	
ADMINISTRATIVE	8	HR	\$28.85	\$230.80	
SUBTOTAL				\$4,384.48	
G&A BURDEN FOR LABOR (164%)				\$7,190.55	
FIXED FEE (10%)				\$1,157.50	
PROJECT MANAGEMENT TOTAL				\$12,732.53	

EAF LABOR					
Description	Qty	UOM	Unit Price	Amount	
EAF MANAGER	16	HR	\$28.85	\$461.60	
EAF LEAD FORMAN	32	HR	\$20.19	\$646.08	
LEAD WIREMAN	56	HR	\$19.25	\$1,078.00	
TEST	12	HR	\$36.00	\$432.00	
QC	8	HR	\$31.25	\$250.00	
SUBTOTAL				\$2,867.68	
G&A BURDEN FOR LABOR (164%)				\$4,703.00	
FIXED FEE (10%)				\$757.07	
EAF LABOR TOTAL				\$8,327.74	

CONSTRUCTION LABOR						
Description	Description Qty UOM Unit Price					
SIGNAL FOREMAN	80	HR	\$31.25	\$2,500.00		
SIGNALMAN	80	HR	\$28.50	\$2,280.00		
SIGNAL HELPER	160	HR	\$21.00	\$3,360.00		
SUBTOTAL				\$8,140.00		
G&A BURDEN FOR LABOR (164%)				\$13,349.60		
FIXED FEE (10%)				\$2,148.96		
CONSTRUCTION LABOR TOTAL				\$23,638.56		

Akron Barberton Cluster Railway Norton, OH. - Medina Line Rd DOT # 265 079J CTC Project Estimate

CONSTRUCTION LABOR EXPENSES						
Description	Amount					
EMPLOYEE MEALS (PER DIEM)	32	EA	\$35.00	\$1,120.00		
EMPLOYEE LODGING	32	EA	\$75.00	\$2,400.00		
MOBILIZATION	1	EA	\$1,500.00	\$1,500.00		
CONSTRUCTION LABOR EXPENSES TOTAL				\$5,020.00		

CONSTRUCTION EQUIPMENT						
Description	Qty	UOM	Unit Price	Amount		
TRUCK, PU, 1 TON CREW CAB	80	HR	\$15.71	\$1,256.80		
TRAILER, UTILITY (12,000lb SC410)	80	HR	\$7.55	\$604.00		
RENTAL EQUIPMENT (FORKLIFT - 8K)	1	WK	\$1,600.00	\$1,600.00		
RENTAL EQUIPMENT (BACKHOE W/18" BKT)	1	WK	\$1,400.00	\$1,400.00		
EQUIPMENT DELIVERY/PICKUP	2	LS	\$250.00	\$500.00		
CONSTRUCTION EQUIPMENT TOTAL				\$5,360.80		

MATERIAL					
Description	Qty	UOM	Unit Price	Amount	
HOUSE MATERIAL (SEE ATTACHED DETAIL)	1	LS		\$43,109.83	
FIELD MATERIAL (SEE ATTACHED DETAIL)	1	LS		\$35,911.09	
FILL DIRT	15	TN	\$25.89	\$388.35	
COVER ROCK (3/4" CRUSHED - WHITE)	20	TN	\$26.50	\$530.00	
FREIGHT & CONTAINER PRICE	1	LS	\$5,500.00	\$5,500.00	
MATERIAL TOTAL				\$85,439.27	

TOTAL PROJECT ESTIMATE

\$149,251.12

HOUSE MATERIALS		
DESCRIPTION	QTY	υом
Bungalow, Alum. 6 X6 w/Heater P/N 91000564 D-1, PTMW (WLE SPECS)		EA
Assembly Board, 20.31X12.00X0.75, w/Hardware, P/N R66000139PH, PTMW	5	EA
Indicator, Horizontal, 1 Eye, Red LED, P/N LC-1EY-HGS-R, Velcorp Gems	2	EA
Wrench, AAR terminal - 11", P/N 032619-9X, Siemens		EA
Sensor, Hermetic Door Switch, P/N 70168986, Allied Electric		EA
Actuator, Hermetic Door Switch, P/N 70168991, Allied Electric		EA
Decal, Danger 240V (5"X3.5"), P/N 3XDU5, Grainger Decal, MUTCD Emergency Notification, 30"X18", Eagle Traffic		EA EA
Wire, Case, #16AWG 1000' spool, Blue, P/N 152-11-3002, Okonite	0.5	
Wire, Case, #10AWG 1000' spool, Blue, P/N 152-11-3038. Okonite	0.5	
Wire, Case, #6AWG, Green, P/N N6GNM, Reynolds	100	
Wire, Case, #6AWG, Black, P/N N6BM, Reynolds	100	FT
Wire, Case, #6AWG. Red, P/N N6RD, Reynolds	100	FT
MDA-ll With Current Sensors DTMF Radio and GFD - Complete, P/N NAS-WLE, NAS		EA
MDSA-1X Surge arrestor panel, P/N 250204-100, Alstom		EA
LSP, Lightning Surge Panel w/Arrestors, P/N 9000-91170-0001, Siemens		EA
Track Driver, TD-4 AC/DC, P/N 800-081033-100, GE Arrestor, Track Surge, P/N 250787-000, GE		EA EA
Controller, SSCC III Plus, 40 Amp, P/N 9000-91190-0101, Siemens		EA
Relay, 500 Ohm, 6PT, Nuetral relay, plug-in, P/N A62-0262, Alstom		EA
Relay, 4 Ohm, 6PT, Biased Nuetral, P/N A62-682, Alstom		EA
Plugboard, Kit (1E/3E test posts) P/N 59686-019-02, Alstom		EA
Wrench, 3E test tool, P/N P03-0320, Alstom	1	EA
Extractor Tool, Terminal clip, P/N 032619-25, Siemens	1	EA
Relay, 8-pin KRPA style, 10A/240VAC, P/N 70198711, Allied		EA
Relay, 8-pin KRPA style, 10A/12VDC, P/N 70199265, Allied		EA
Socket, 8-pin KRPA style, P/N 70199343, Allied		EA EA
Spring, Hold down for KRPA style relay, P/N 70198576, Allied Resistor, Adjustable, 5.69 Ohms, P/N 1110-7D, WCH		EA
Resistor, Adjustable, 11.21 Ohms, P/N 1110-10D, WCH		EA
Battery Charger, ETC-12V 40AMP, P/N 520740, Railway Equipment		EA
Track Charger, ERB-C 5/5, P/N 16615-10, NRS		EA
Battery, NiCad 340 A.H., P/N SPL-340, Saft	9	EA
Battery, NiCad 250 A.H., P/N SPL-250, Saft	10	
Battery, Absolyte GP, 152 A.H., P/N 1-50G07, Exide/GNB		EA
Terminal, Battery, 3-PT, P/N 225481-000, J&A Industries		EA
Battery Tray 12"x38", Holds 5 Batteries, P/N 027004-001, J&A Nema Plug, Locking, 15 Amp/240V, P/N L6-15P, Reynolds		EA EA
Power Indicator, 2 Eye/4 Wire, Wago connector, P/N LC-101WB-WG4, Velcorp Gems		EA
SO Cord, 14 AWG/4 Conductor, P/N SJOOW-14-4-BLK-250R, Graybar	100	
Tie-wrap, 11 1/2", PKG 100, Black, P/N LTS11-0, Vantex		EA
Tie-wrap, mounting, PKG 100, P/N TYM, Vantex	1	EA
Loom, Spiral Wrap 100', Black, P/N SW38-0, Vantex		EA
Panduit, Wire Duct, 2"X3"X6' Gray, P/N G2X3LG6, Graybar		EA
Panduit, Cover, 6' Gray, P/N C2LG6, Graybar		EA
Terminal, 2X6 W/ Flat nut/washer, P/N 220-0101, Rebel Terminal, Block, 2 3/8" center - 2 post w/hardware, P/N 220-0301, Rebel		EA EA
Terminal, 4-post, Block Kit, w/ 14-24 AAR Hardware, P/N B2700A2C1WH, Erico		EA
RailSurge Plane Strip Busbar (36"), P/N B2700HC36, Erico		EA
Connector, 2 3/8", strap style, P/N 220-0507, Rebel		EA
Connector, 1", flat, strap style, P/N 220-0501, Rebel		EA
Arrestor, Air Gap, With Cover, P/N 4000-44585-001X, Siemens	10	EA
Equalizer, Air Gap, with Cover/Hardware , P/N 4000-44700-001X, Siemens		EA
Binding Nut, P/N 13073-000, Rebel	200	
Clamp Nut, P/N 13079-000, Rebel	100	
Insulated Nut, 1 3/16" , P/N 023408-1X, Safetran Washer, P/N 013074-000, Robel	20 200	
Washer, P/N 013074-000, Rebel Gold Test Nut, P/N 13296-001, Rebel	100	
1' Test Link, Flat, P/N 32257-002, Rebel	100	
Terminal Ring, HD, 1/4", insulated, #14 - #16 (yellow w/blk stripe), P/N NC-10HDB, Vantex	100	
Terminal, Ring, 1/4", insulated #14 - #16 (100 pk), P/N NB14, Vantex		EA
Terminal, Ring, 1/4" insulated, #10 - #12 (100 pk), P/N NC14, Vantex	2	EA
Terminal, Ring, 1/4" insulated, #6, Blue, P/N T6-14N, Vantex		EA
Terminal, Ring, 3/8" non-insulated, #6, Battery Lug, P/N T6-38, Vantex	15	EA

FIELD MATERIALS					
DESCRIPTION	QTY	иом			
Cable, 7/C#6, Armored, 206-11-6247, Okonite	250	FT			
Cable, 7C#14, Armored, 206-11-6887, Okonite	250	FT			
Cable, 3C#6, Armored, #206-11-6243, Okonite	150	FT			
Wire, Track, 2C/#6, Twist, Solid, 113-12-3933, Okonite	400	FT			
Tape, Marker - "Buried RR line"/"Buried electrical line"	1	ROLL			
Bootleg Kit, Crossing complete, Wood, 1 Track, CTC Inc.	2	EA			
Bond Wire, 7 1/2" XS Style, P/N SBS24883, Erico	100	EA			
Connector, Track, Web of Rail, P/N SBTBBU4A, Erico	100	EA			
Wheel, grinding, P/N SB22122, Erico	4	EA			
Bondstrand, 3/16" Black, 500' Reel, P/N SBS8LINSUL, Erico	0.5	EA			
5/8" X 8' Copper Ground Rod P/N 615880. Erico	6	EA			
5/8" Ground Rod Weld, P/N SBNT1161G, Erico	6	EA			
Wire, Ground, #6AWG, Bare Copper, Graybar	60	FT			
Ring 10, Track Diode, P/N 800-004080-001, GE	2	EA			
Mast, Gate, 18'X5" w/pigtail (single-sided Jct Box), P/N 715-324-2-GS, WCH	2	EA			
Jct box, Gate, 5" single hole w/24 terminals, P/N 2149-A-139, WCH	2	EA			
Pinnacle, 5", P/N 010-9034, Rebel	1	EA			
Gate, Model 3597, P/N 3597-131-P-H-M1 (WLE Spec), WCH	2	EA			
Resistor, Adjustable, 5 OHM, P/N 1110-7D, WCH	4	EA			
Crossarm Assy, 5" Mtg., 2 Way, P/N 975-0804-5, WCH	2	EA			
Lights, 12" LED, P/N 433121680XLTC-00, Arms	8	EA			
Counterweight Package, P/N 070755-18X, Siemens	2	EA			
Sign, Crossbuck, No brackets/hardware, P/N 070-0065, Rebel Railway	2	EA			
5" Sign Kit, Brackets/extensions/Ubolts/hardware, P/N 070-5008, Rebel Railway	4	EA			
Wind Bracket, 36", Tusk style, P/N 2010-001-01, RDG	2	EA			
Bell, Electronic, 5" Base, P/N EB-3-360-5, GSI	1	EA			
Gate Keeper, 2-Way, w/Hardware & Buffer Spring, P/N SK-1000-2W, GSI	2	EA			
E-Z Gate (Vertical stripe) LED gate w/lamp kit, P/N 9298-6154, Railway Equip	2	EA			
Sleeve, 4' Aluminum, P/N 92958, Railway Equipment	2	EA			
Wrench, Torque (KIT), P/N 2590-K-9, WCH	1	EA			
Sign, Emergency, ENS, 15"X9" Blue, Eagle Traffic	2	EA			
Field cable Tag Kit, P/N FLDTGKT, CTC Inc.	1	EA			
Schedule 40 2" & 4" PVC Conduit Kit with Elbows	1	LOT			
Duct seal, 1lb, P/N 31-601, Graybar	1	EA			
Duct seal, 5lb, P/N 31-605, Graybar	1	EA			
Lock, Barrel Style	4	EA			

6/6/2018

673 Norton Ave. Barberton, Ohio 44203

ABC Railway

Tele: (330) 753-2983

Various Locations

Insulated Joints Installation - Proposal

Attn: Andrew R. Shuster Phone: 330-813-6133 Email: ashuster@abcrwy.com

Wintrow Construction Corp. will provide all supervision, labor, equipment, and specified materials to complete the following described work:

Main St., Wadsworth, Ohio

 Furnish and install 8-Insulated joints for crossing signal project New Alleghany glue joints will be furnished-39' overall length Insulated joints will be bolted in place Location of joints to be marked by others

	Total:	\$31,825
	Labor/Equip:	\$12,931
	Materials:	\$18,894
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$1,971)

Medina Line Rd., Norton, Ohio

1. Furnish and install 8-Insulated joints for crossing signal project New Alleghany glue joints will be furnished-39' overall length Insulated joints will be bolted in place Location of joints to be marked by others

	Total:	\$30,544
	Labor/Equip:	\$11,650
	Materials:	\$18,894
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$1,971)

Main St., Kent, Ohio

 Furnish and install 1-Insulated joints in curve closure rail in turnout south of road New Alleghany glue joint will be furnished-39' overall length Insulated joint will be bolted in place

Location of joint to be marked by others

	Total:	\$4,315
Labo	r/Equip:	\$1,649
Μ	aterials:	\$2,666
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$246)

673 Norton Ave. Barberton, Ohio 44203

Tele: (330) 753-2983

ABC Railway

Various Locations

Insulated Joints Installation - Proposal

Contingencies/Notes

Sales Taxes Not included in Quotation

No Warranty or Guarantees are apart of this proposal

Payment: Net 30 Days. Late payment charge of 1 1/2% (18% annum) will be charged on all past due balances.

We are not responsible for repair or relocation of Under Ground Utilities

Weather conditions prevail and may affect the construction schedule.

Track must be free of rail cars and rail traffic.

ONE Mobilization is included in the quotation.

All work is at straight time labor rates unless specified otherwise in the quotation Work description and material specifications haven't as yet been approved by the railroad

Engineering, plans and layout survey by others.

Material Subject to Pryor Sale

Progress payments are to be paid by the 15th of the month.

No costs for possible flagman services is included

Costs include continuous work windows with no train delays

*No destressing of rails is included-Rail temperature is

assumed to be within rage when installation is scheduled*

No wiring or bonding is included in pricing

Crosier Industrial Construction Ltd

8938 Peck Rd Ravenna, Ohio 44266 Ph (330) 592-3082 trailrnrbob@hotmail.com

Creation Industrial Construction II C			Date		13-Feb-18		
Crosier Industrial Construction, LLC			Invoice Number	TBD	13-FED-10		
Project Cost Estimate Project: Medina Line Road 265-079J			Invoice Number		ster/Shankli		
LABOR			Rate/Hr	Hou			ib-total
Equipment Operator (backhoe, excavator)			\$25.00	nou	80	30	\$2,000.00
Laborer, skilled			\$18.00		80	\$	1,440.00
Project Manager			\$18.00		80	ۍ \$	4,000.00
Administrative			\$30.00		2	э \$	4,000.00
Administrative			\$30.00 Sub-Total		2	\$	7,500.00
			G&A Burden fo			э	
				or Lab	O	_	4,500.00
FOUNDATION	o		Total Labor			\$	12,000.00
EQUIPMENT	Quantity	rate/h	r		Hours		Total
Excavator, Bobcat E32 (331)		\$ 31.20			20	\$	624.00
E55		\$ 40.20			60	\$	2,412.00
Dump Truck		\$ 40.00			20	\$	800.00
Directional Drill		\$ 59.62			12	\$	715.44
Truck, equipment		\$ 21.35			80	\$	1,708.00
HydroTamper		\$ 17.05			20	\$	341.00
Traffic Cones		\$ 0.13			80	\$	10.40
Traffic Signs		\$ 0.23			80	\$	18.40
Tamper		\$ 4.25			6	\$	25.50
Digger Derrick		\$ 55.20			4		220.80
			Total Equipme	ent		\$	6,875.54
MATERIALS			Quantity		rice/Each		Total
5" pvc conduit			120	\$	2.86	\$	343.20
5" 90 degree			2	\$	20.10	\$	40.20
5" coup			4	\$	4.98	\$	19.92
4" pvc conduit			40	\$	2.18	\$	87.20
4" sweeps			3	\$	23.50	\$	70.50
4" 90 degree			1	\$	11.50	\$	11.50
4" 45 degree			2	\$	11.50	\$	23.00
4" coup			8	\$	2.10	\$	16.80
3" pvc conduit			40	\$	1.72	\$	68.80
3" sweeps			2	\$	21.10	\$	42.20
3" coup			4	\$	1.45	\$	5.80
2" pvc conduit			30	\$	0.94	\$	28.20
2" sweeps			1	\$	17.95	\$	17.95
2" 45 degree			2	\$	1.95	\$	3.90
Pull Rope			225	\$	0.13	\$	29.25
Ground rods			2	\$	17.25	\$	34.50
Cement			1	\$	8.50	\$	8.50
Pull Box			2	\$	315.00	\$	630.00
Gravel			70	\$	25.00	\$	1,750.00
			Material Total			\$	3,231.42
			Job Sub-Total				22,106.96
			Profit Addition		10%	\$	2,210.70
			TOTAL PROJECT E	STINA		_	24,317.66
Day 1: Pore read and place 5" conduit			IOTAL PROJECT E	JIIVIA	AIE	\$	24,317.00

Day 1: Bore road and place 5" conduit

Day 2: Excavate and place near foundation. Excavate conduit to pull box location. Backfill and tamp. Set AC meter pole.

Day 3: Excavate and place far foundation. Excavate conduit to pull box location. Place far track wire conduit. Backfill/tamp.

Day 4: Excavate AC conduit and near track wire conduit. Backfill/tamp. Spread and tamp gravel.

Day 5: Place pull boxes, ground rods and pull rope. Spread/tamp gravel.

Day 6: Spread and tamp gravel. Finish grade.

Duties Performed throughout the project:

* Coordinate delivery of fill material

- * Coordinate curb and sidewalk construction
- $^{\star}\,$ Transport foundations, conduit, pull box to site
- * Remove spoils and debris
- * Supply and erect traffic control devices for work zone safety
- * Call Ohio Utility Protection Service as required by Ohio Law
- * Establish Railroad Roadway Worker Protection daily to comply with Federal Regulation

PUBLIC UTILITIES COMMISSION OF OHIO TRANSPORTATION DEPARTMENT RAIL DIVISION

Date of Assignment: May 28, 2019

Subject: Plans and estimates review for active warning devices at Main Street, Wadsworth (265-076N), Akron Barberton Cluster Railway, Medina County.

DOT #: 265-076N

FINDINGS

On May 28, 2019, the plans and estimates for the above mentioned crossing were received from Akron Barberton Cluster Railway (AB). They were reviewed by Jill Henry, PUCO Rail Specialist, and Shawn Zurfley, FRA/PUCO Field Investigator.

Main Street is a 2 lane urban roadway traveling north and south and intersecting a single track of AB traveling east/west. Existing warning devices include mast mounted lights and gates, advanced warning signs, pavement markings and crossbucks.

SUMMARY AND CONCLUSIONS

We reviewed the plans and estimates for the crossing. The plans and estimates appear to be fundamentally correct. Construction authorization is granted for this project with the following conditions:

1) The gate foundations need to be placed so that they are either behind or in front of the sidewalks on each side of the crossing.

Jill Henry PUCO Rail Specialist Date: May 31, 2019

AKRON BARBERTON CLUSTER RAILWAY COMPANY

Andrew Shuster Signal & Communication Supervisor 43 Second Street N.W. Barberton, OH 44203

Tel. 330-813-6133

ashuster@abcrwy.com

Fax: 330-745-4519

29 June 2018

Public Utilities Commission of Ohio Jill Henry

Re: Estimate for Railroad Crossing Warning System at Main Street in Wadsworth Ohio,

Dear Jill Henry,

I am providing this estimate for the crossing package and installation at Main St.,

CTC Managed Services, Material Package, & Installation	\$ 153,050.02			
Crosier Inc.	\$ 34,933.51			
Two Gate Foundations (note 1)	\$ 1,196.00			
Electric Service	\$ 3,500.00			
Wintrow Railroad Construction (Provide and Install Allegheny Joints)	\$ 31,825.00			
Estimated Total	\$ 224,504.53			

Please contact me if additional details are required.

Respectfully,


Andrew Shuster


Notes

1: Direct purchase from Fabricated Metals, 60' galvanized gate foundation, \$598 ea.


DWG. NO.	DESCRIPTION
00	INDEX
01	SITE LAYOUT
02	CROSSING SIGNAL ALIGNMENT
03	SITE LAYOUT NOTES
04	CROSSING CONTROL CIRCUITS
05	RELAYS
06	RECORDER
07	BGD
08	SSCC III PLUS
09	1LSP
10	СТР
11	GATE #1 MECHANISM (NEAR SIDE)
12	GATE #1 LIGHTS (NEAR SIDE)
13	GATE #2 MECHANISM (FAR SIDE)
14	GATE #2 LIGHTS (FAR SIDE)
15	BATTERY CHARGERS
16	AC POWER DISTRIBUTION
17	RACK FRONT VIEW
18	RACK BACK VIEW
19	SIDE "A"
20	SIDE "C"

	REV.		GENERAL NOTES			
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
ND DEVICES ARE CONNECTED TO FORM A COMPLETE SYSTEM, OR AN EFFECTIVE SUBSYSTEM. SUCH SYSTEM OR SUBSYSTEM MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
MUST BE GIVEN COMPLETE CIRCUIT AND OPERATIONAL TESTS BEFORE BEING PLACED IN REGULAR OPERATION.						
PICAL: N PICAL:						
PICAL: N PICAL:	ND DEVICE	S ARE CONNECTED TO FORM A	A COMPLETE SYSTEM, OR AI	N EFFECTIVE SUBSYSTE	M. SUCH SYSTEM OR SUB	
PICAL: N PICAL:	ND DEVICE	S ARE CONNECTED TO FORM A	A COMPLETE SYSTEM, OR AI	N EFFECTIVE SUBSYSTE	M. SUCH SYSTEM OR SUB	
PICAL: N PICAL:	ND DEVICE	S ARE CONNECTED TO FORM A T BE GIVEN COMPLETE CIRCUI	A COMPLETE SYSTEM, OR AI	N EFFECTIVE SUBSYSTE BEFORE BEING PLACED	M. SUCH SYSTEM OR SUB: IN REGULAR OPERATION.	SYSTEM
PICAL: N PICA: N PICAL: N PICAL: N PICAL: N PICAL: N PICAL: N PICAL: N PICA	ND DEVICE	S ARE CONNECTED TO FORM A T BE GIVEN COMPLETE CIRCUI	A COMPLETE SYSTEM, OR AI T AND OPERATIONAL TESTS	N EFFECTIVE SUBSYSTE BEFORE BEING PLACED	M. SUCH SYSTEM OR SUB IN REGULAR OPERATION.	SYSTEM
PROVER OF A DATE	ND DEVICE	S ARE CONNECTED TO FORM A T BE GIVEN COMPLETE CIRCUI	A COMPLETE SYSTEM, OR AI T AND OPERATIONAL TESTS	N EFFECTIVE SUBSYSTE BEFORE BEING PLACED	M. SUCH SYSTEM OR SUB IN REGULAR OPERATION. BARBERTON RATLWAY	SYSTEM
	ND DEVICE MUS	S ARE CONNECTED TO FORM A T BE GIVEN COMPLETE CIRCUI	A COMPLETE SYSTEM, OR AI T AND OPERATIONAL TESTS	N EFFECTIVE SUBSYSTE BEFORE BEING PLACED	M. SUCH SYSTEM OR SUB IN REGULAR OPERATION. BARBERTON RATLWAY MAIN STREET (SR 94- WADSWORTH, OHIO	SYSTEM





- - IN THE LOCATION SHOWN.
- 4.) IN THE LOCATION SHOWN.
- 5.) CREW LIGHT RED IN COLOR.



CONSTRUCTION NOTES

1.) INSTALL NEW 6' X 6' BUNGALOW IN NORTHWEST QUADRANT.

2.) INSTALL (2) NEW FLASHING LIGHTS WITH GATES.

3.) METER POLE LOCATION SHOWN ON THE PLAN IS SUBJECT TO CHANGE WITHIN RAILROAD RIGHT-OF-WAY IF UNDERGROUND OBSTRUCTIONS PREVENT THE INSTALLATION OF THE POLE

BUNGALOW LOCATION SHOWN ON THE PLAN IS SUBJECT TO CHANGE WITHIN RAILROAD RIGHT-OF-WAY IF UNDERGROUND OBSTRUCTIONS PREVENT THE INSTALLATION OF THE BUNGALOW

6.) POWER OFF LIGHT (SOLID AC) (FLASH DC)

7.) CURB TO BE INSTALLED FOR GATE PLACEMENT.



(A)GATE ; B GATE \bigcirc GATE #2 FRONT MAST LIGHTS \bigcirc GATE #2 BACK MAST LIGHTS

ALIGNMENT

ADJUST LIGHT UNIT HORIZONTALLY TO ALIGN AXIS OF BEAM TO CENTER OF APPROACH LANE IN APPROACH TO SIGNAL AT SELECTED ALIGNMENT DISTANCE, MAINTAINING VERTICAL ALIGNMENT. BOTH LAMPS SHOULD BE ALIGNED TO SAME POINT.



CROSSING SIGNAL ALIGNMENT

LEGEND

ŧ1	FRONT	MAST	LIGHIS
ŧ1	BACK	MAST	LIGHTS
10	FRANT	LUCT	

FRONT LIGHTS ADJUST LIGHT UNIT VERTICALLY TO ALIGN AXIS OF BEAM 5FT. 6IN. ABOVE PAVEMENT AT SELECTED ALIGNMENT DISTANCE. BOTH LAMPS SHOULD BE ALIGNED TO SAME POINT.


BACK LIGHTS ADJUST LIGHT UNIT VERTICALLY TO ALIGN AXIS OF BEAM 5 FT. 6 IN. ABOVE PAVEMENT AT A POINT 50 FT. IN APPROACH TO THE SIGNAL ON OPPOSITE SIDE OF TRACK.

ADJUST LIGHT UNIT HORIZONTALLY TO ALIGN AXIS OF BEAM TO A POINT 50 FT. IN APPROACH TO THE SIGNAL ON OPPOSITE SIDE OF TRACK AND IN CENTER OF APPROACH TRAVEL WAY.


AKRON BARBERTON CLUSTER RATLWAY CATION MAIN STREET (SR 94–2) WADSWORTH, OHIO CROSSING SIGNAL ALIGNMENT CTC ^{JB}WADSWORTH-RITTMAI CN18006 CTC RMP 215.57 NTS HECKER CTC ^{ot no.} 265 076N 02 OF 20

SITE LAYOUT NOTES


1.) CROSSING IS LOCATED:



ATED: LATITUDE 41.0174198 LONGITUDE -81.7296900




ST RELAY LAYOUT




LEGEND:

1TR = TRACK RELAY (1T) 2TR = TRACK RELAY (2T) 3TR = TRACK RELAY (3T) OOS1R = OUT OF SERVICE RELAY




EXAMPLE





ST1, 400000 500Ω, 6FB, NEUTRAL


✓ CONTACT, NOT USED▼ CONTACT, USED














CTC WADSWORTH-RITTMAN RAFTSMAN CTC RRMP 215.57 CHECKER CTC ^{DOT NO.} 265 076N


NTS

07 OF 20










CONTACT	CLOSED	FUNCTION	TENSION
1B	75-90 DEG.	POWER DOWN	18-28 OZ.
1F	0-70 DEG.	SNUB DOWN	18-28 OZ.
2	0-86 DEG.	POWER UP	18-28 OZ.
3	0-10 DEG.	gate down	16-24 OZ.
4	82-90 DEG.	GATE CLEAR	16-24 OZ.
5	10-90 DEG.	BELL	16-24 OZ.
6	SPARE	SPARE	16-24 OZ.
7	0-2 DEG.	SNUB	16-24 OZ.



LEGEND:

\bigcirc = insulated nut

NOTES:


REVISION


BLOCK


- * BELL TO BE ELECTRONIC.
- → = INTERNAL GATE WIRES THAT SHARE ELECTRICAL CONNECTIONS WITH OTHER WIRES THAT ARE ASSIGNED THE SAME NUMBER.

REFER TO SHEET 12 FOR GATE ARM LIGHT WIRING


ADD STRAP FROM: 3A TO 3B AND 3B TO 4B







CONTACT	CLOSED	FUNCTION	TENSION
1B	75-90 DEG.	POWER DOWN	18–28 OZ.
1F	0-70 DEG.	SNUB DOWN	18-28 OZ.
2	0-86 DEG.	POWER UP	18-28 OZ.
3	0-10 DEG.	gate down	16-24 OZ.
4	82-90 DEG.	GATE CLEAR	16-24 OZ.
5	10-90 DEG.	BELL	16-24 OZ.
6	SPARE	SPARE	16-24 OZ.
7	0-2 DEG.	SNUB	16-24 OZ.



LEGEND:

🔘 = INSULATED NUT

NOTES:


REVISION


BLOCK


- * BELL TO BE ELECTRONIC.
- → = INTERNAL GATE WIRES THAT SHARE ELECTRICAL CONNECTIONS WITH OTHER WIRES THAT ARE ASSIGNED THE SAME NUMBER.

REFER TO SHEET 14 FOR GATE ARM LIGHT WIRING

ADD STRAP FROM: 3A TO 3B










SPARE 0052R-25 CC56 0051R-35 CC52 1TR 15 EPC TD-4B 3TR 22 3TR 15	26 25 24 23 22 21 20 19	SPARE OOS2R-22 CC54 OOS1R-32 CC50 1TR 12 EPC TD-4N SPARE 3TR 12
2TR 15	18 17	2TR 12
PO DB1	. ,	PO DB3
2TR 22	16	SPARE
BGD INPUT 1	15	BGD INPUT 2
SPARE	14	RLR 7
RCDR TB6-1	13	RCDR TB6-2
RCDR TB1-4	12	RCDR TB1-3
1 1TR 22	11	SPARE
MB_BATT+	10	MN BATT-
MB BUSS (TOP)	AA	MN BUSS (BOTTOM)


ГЛ		
SPARE	48	SPARE
SPARE	47	SPARE
CC58	46	SSCC J3-9
DOOR SWITCH	45	SSCC J3-11
BGD INPUT 3	44	BGD INPUT 4
RCDR TB1-2	43	RCDR TB1-1
CC58T	42	RCDR TB4-15
1LSP B-BATT	41	1LSP N-BATT
XB BATT+	40	XN BATT-
XB BUSS (TOP)	СА	XN BUSS (BOTTOM)





av	ORIGINAL DATE	1/31/2017	TITLE AC POWER DISTRIE	BUTION	
	DESIGNER	CTC	SUB WADSWORTH-RITTMAN	CTC NO.	CN18006
	DRAFTSMAN	CTC	^{RRMP} 215.57	SCALE	1"=2'
	CHECKER	CTC	^{DOT NO.} 265 076N	SHEET	16 of 20

















	side to field Side "C"		
BUN	ALUMINUM GALOW 1000564 D—1		SIDE "D"
THIS S	SIDE "A" SIDE TO TRACKS	<u></u>	
7		RATL WA	
C	ORIGINAL DATE 1/31/201	MAIN STREET (SF WADSWORTH,	
vay	ORIGINAL DATE 1/31/201 DESIGNER CTC DRAFTSMAN CTC CHECKER CTC	ITLE SIDE "C" SUB WADSWORTH-RIT RRMP 215.57 DOT NO. 265 076N	TMAN CTC NO. CN18006 SCALE 1"=2' SHEET 20 OF 20
	0.0	200 07011	20 Ur 20

Akron Barberton Cluster Railway Wadsworth, OH. - Main Street DOT # 365 076N CTC Project Estimate

ENGINEERING						
Description	Qty	UOM	Unit Price	Amount		
SR SIGNAL ENGINEER (PE STAMP)	8	HR	\$100.00	\$800.00		
SIGNAL DESIGNER	56	HR	\$33.65	\$1,884.40		
SIGNAL CHECKER, LEVEL 1	16	HR	\$43.72	\$699.52		
SIGNAL CHECKER, LEVEL 2/FIELD ENGINEER	8	HR	\$52.88	\$423.04		
SUBTOTAL				\$3,006.96		
G&A BURDEN FOR LABOR (164%)				\$4,931.41		
FIXED FEE (10%)				\$793.84		
ENGINEERING TOTAL				\$8,732.21		

PROJECT MANAGEMENT						
Description	Qty	UOM	Unit Price	Amount		
PROJECT MANAGER	40	HR	\$36.06	\$1,442.40		
CONSTRUCTION MANAGER	40	HR	\$39.61	\$1,584.40		
ACCOUNTING	8	HR	\$40.86	\$326.88		
ADMINISTRATIVE	8	HR	\$28.85	\$230.80		
SUBTOTAL				\$3,584.48		
G&A BURDEN FOR LABOR (164%)				\$5,878.55		
FIXED FEE (10%)				\$946.30		
PROJECT MANAGEMENT TOTAL				\$10,409.33		

EAF LABOR					
Description	Qty	UOM	Unit Price	Amount	
EAF MANAGER	16	HR	\$28.85	\$461.60	
EAF LEAD FORMAN	32	HR	\$20.19	\$646.08	
LEAD WIREMAN	56	HR	\$19.25	\$1,078.00	
TEST	12	HR	\$36.00	\$432.00	
QC	8	HR	\$31.25	\$250.00	
SUBTOTAL				\$2,867.68	
G&A BURDEN FOR LABOR (164%)				\$4,703.00	
FIXED FEE (10%)				\$757.07	
EAF LABOR TOTAL				\$8,327.74	

CONSTRUCTION LABOR					
Description		UOM	Unit Price	Amount	
SIGNAL FOREMAN	80	HR	\$31.25	\$2,500.00	
SIGNALMAN	80	HR	\$28.50	\$2,280.00	
SIGNAL HELPER	160	HR	\$21.00	\$3,360.00	
SUBTOTAL				\$8,140.00	
G&A BURDEN FOR LABOR (164%)				\$13,349.60	
FIXED FEE (10%)				\$2,148.96	
CONSTRUCTION LABOR TOTAL				\$23,638.56	

Akron Barberton Cluster Railway Wadsworth, OH. - Main Street DOT # 365 076N CTC Project Estimate

TDAVEL EYDENSES

TRAVEL EXPENSES					
Description		UOM	Unit Price	Amount	
EMPLOYEE MEALS (PER DIEM)	32	EA	\$35.00	\$1,120.00	
EMPLOYEE LODGING	32	EA	\$75.00	\$2,400.00	
MOBILIZATION	1	EA	\$1,500.00	\$1,500.00	
CONSTRUCTION LABOR EXPENSES TOTAL				\$5,020.00	

CONSTRUCTION EQUIPMENT					
Description	escription Qty UOM Unit Price			Amount	
TRUCK, PU, 1 TON CREW CAB	80	HR	\$15.71	\$1,256.80	
TRAILER, UTILITY (12,000lb SC410)	80	HR	\$7.55	\$604.00	
RENTAL EQUIPMENT (FORKLIFT - 8K)	1	WK	\$1,600.00	\$1,600.00	
RENTAL EQUIPMENT (BACKHOE W/18" BKT)	1	WK	\$1,400.00	\$1,400.00	
EQUIPMENT DELIVERY/PICKUP	2	LS	\$250.00	\$500.00	
CONSTRUCTION EQUIPMENT TOTAL				\$5,360.80	

MATERIAL					
Description	Qty	UOM	Unit Price	Amount	
HOUSE MATERIAL (SEE ATTACHED DETAIL)	1	LS		\$42,981.83	
FIELD MATERIAL (SEE ATTACHED DETAIL)	1	LS		\$35,855.87	
FILL DIRT	15	TN	\$25.89	\$388.35	
COVER ROCK (3/4" CRUSHED - WHITE)	25	TN	\$26.50	\$662.50	
FREIGHT & CONTAINER PRICE	1	LS	\$5,500.00	\$5,500.00	
MATERIAL TOTAL				\$85,388.55	

TOTAL PROJECT ESTIMATE

\$146,877.20

HOUSE MATERIALS		
DESCRIPTION	QTY	UОМ
Bungalow, Alum. 6 X6 w/Heater P/N 91000564 D-1, PTMW (WLE SPECS)		EA
Assembly Board, w/Hardware, P/N R66000139PH, PTMW	5	EA
Indicator, Horizontal, 1 Eye, Red LED, P/N LC-1EY-HGS-R, Velcorp Gems		EA
Wrench, AAR terminal - 11", P/N 032619-9X, Siemens		EA
Sensor, Hermetic Door Switch, P/N 70168986, Allied Electric		EA
Actuator, Hermetic Door Switch, P/N 70168991, Allied Electric		EA
Decal, Danger 240V (5"X3.5"), P/N 3XDU5, Grainger		EA
Decal, MUTCD Emergency Notification, 30"X18", Eagle Traffic		EA
Wire, Case, #16AWG 1000' spool, Blue, P/N 152-11-3002, Okonite	0.5	
Wire, Case, #10AWG 1000' spool, Blue, P/N 152-11-3038. Okonite	0.5	
Wire, Case, #6AWG, Green, P/N N6GNM, Reynolds	100	
Wire, Case, #6AWG, Black, P/N N6BM, Reynolds	100	
Wire, Case, #6AWG. Red, P/N N6RD, Reynolds	100	
MDA-II With Current Sensors DTMF Radio and GFD-Complete, P/N NAS-WLE, NAS		EA
MDSA-1X Surge arrestor panel, P/N 250204-100, Alstom		EA
LSP, w/Arrstors, P/N 9000-91170-0001, Siemens		EA
Track Driver, TD-4 AC/DC, P/N 800-081033-100, GE		EA EA
Arresor, Track Surge, P/N 250787-000, GE Controller, SSCC III Plus, 40 Amp, P/N 9000-91190-0101, Siemens		EA
Relay, 500 Ohm, 6PT, Nuetral relay, plug-in, P/N A62-0262, Alstom		EA
Relay, 4 Ohm, 6PT, Biased Nuetral, P/N A62-682, Alstom		EA
Plugboard, Kit (1E/3E test posts) P/N 59686-019-02, Alstom		EA
Wrench, 3E test tool, P/N P03-0320, Alstom		EA
Extractor Tool, Terminal clip, P/N 032619-25, Siemens		EA
Relay, 8-pin KRPA style, 10A/240VAC, P/N 70198711, Allied		EA
Relay, 8-pin KRPA style, 10A/12VDC, P/N 70199265, Allied		EA
Socket, 8-pin KRPA style, P/N 70199343, Allied		EA
Spring, Hold down for KRPA style relay, P/N 70198576, Allied		EA
Battery Charger, ETC-12V 40AMP, P/N 520740, Railway Equipment		EA
Track Charger, ERB-C 5/5, P/N 16615-10, NRS		EA
Battery, NiCad 340 A.H., P/N SPL-340, Saft		EA
Battery, NiCad 250 A.H., P/N SPL-250, Saft	10	
Battery, Absolyte GP, 152 A.H., P/N 1-50G07, Exide/GNB		EA
Terminal, Battery, 3-PT, P/N 225481-000, J&A Industries		EA
Battery Tray 12'x27", Holds (3) Batteries, P/N 027002-001, J&A		EA
Nema Plug, Locking, 15 Amp/240V, P/N L6-15P, Reynolds		EA
Power Indicator, 2 Eye/4 Wire, Wago connector, P/N LC2-001WB-WG4, Velcorp Gems		EA
SO Cord, 14 AWG/4 Conductor, P/N SJOOW-14-4-BLK-250R, Graybar	100	
Tie-wrap, 11 1/2", PKG 100, Black, P/N LTS11-0, Vantex	1	EA
Tie-wrap, mounting, PKG 100, P/N TYM, Vantex		EA
Loom, Spiral Wrap 100', Black, P/N SW38-0, Vantex	1	EA
Panduit, Wire Duct, 2"X3"X6' Gray, P/N G2X3LG6, Graybar	3	EA
Panduit, Cover, 6' Gray, P/N C2LG6, Graybar		EA
Terminal, 2X6 W/ Flat nut/washer, P/N 220-0101, Rebel	10	
Terminal, Block, 2 3/8" center - 2 post w/hardware, P/N 220-0301, Rebel	8	EA
Terminal, 4-post, Block Kit, w/ 14-24 AAR Hardware, P/N B2700A2C1WH, Erico	6	EA
RailSurge Plane Strip Busbar (36"), P/N B2700HC36, Erico		EA
Connector, Buss strap (1" - 36 holes), P/N 9A2216-36, L&W Industries	5	EA
Connector, 1", flat, strap style, P/N 220-0501, Rebel	10	EA
Arrestor, Air Gap, With Cover, P/N 4000-44585-001X, Siemens	10	EA
Equalizer, Air Gap, with Cover/Hardware , P/N 4000-44700-001X, Siemens	2	EA
Binding Nut, P/N 13073-000, Rebel	200	EA
Clamp Nut, P/N 13079-000, Rebel	200	EA
Insulated Nut, 1 3/16" , P/N 023408-1X, Safetran	28	EA
Washer, P/N 013074-000, Rebel	200	EA
Gold Test Nut, P/N 13296-001, Rebel	100	EA
1' Test Link, Flat, P/N 32257-002, Rebel	100	EA
Terminal Ring, HD, 1/4", insulated, #14 - #16 (yellow w/blk stripe), P/N NC-10HDB, Vantex	100	
Terminal, Ring, 1/4" non-insulated, #6, Battery Lug, P/N T6-14, Vantex	15	EA

FIELD MATERIALS			
DESCRIPTION	QTY	υом	
Cable, 7/C#6, Armored, 206-11-6247, Okonite	250	FT	
Cable, 7C#14, Armored, 206-11-6887, Okonite	250	FT	
Cable, 3C#6, Armored, #206-11-6243, Okonite	150	FT	
Wire, Track, 2C/#6, Twist, Solid, 113-12-3933, Okonite	400	FT	
Bootleg Kit, Crossing complete, Wood, 1 Track, CTC Inc.	2	EA	
Bond Wire, 7 1/2" XS Style, P/N SBS24883, Erico	100	EA	
Connector, Track, Web of Rail, P/N SBTBBU4A, Erico	100	EA	
Wheel, grinding, P/N SB22122, Erico	4	EA	
Bondstrand, 3/16" Black, 500' Spool, P/N SBS8LINSUL, Erico	0.5	EA	
5/8" X 8' Copper Ground Rod P/N 615880. Erico	6	EA	
5/8" Ground Rod Weld, P/N SBNT1161G, Erico	6	EA	
Wire, Ground, #6AWG, Bare Copper, Graybar	60	FT	
Ring 10, Track Diode, P/N 800-004080-001, GE	1	EA	
Mast, Gate, 18'X5" w/pigtail (single-sided Jct Box), P/N 715-324-2-GS, WCH		EA	
Jct box, Gate, 5" single hole w/24 terminals, P/N 2149-A-139, WCH	2	EA	
Pinnacle, 5", P/N 010-9034, Rebel	1	EA	
Gate, Model 3597, P/N 3597-131-P-H-M1 (WLE Spec), WCH	2	EA	
Crossarm Assy, 5" Mtg., 2 Way, P/N 975-0804-5, WCH	2	EA	
Lights, 12" LED, P/N 433121680XLTC-00, Arms	8	EA	
Counterweight Package, P/N 070755-18X, Siemens	2	EA	
Sign, Crossbuck, No brackets/hardware, P/N 070-0065, Rebel Railway	2	EA	
5" Sign Kit, Brackets/extensions/Ubolts/hardware, P/N 070-5008, Rebel Railway	4	EA	
Wind Bracket, 36", Tusk style, P/N 2010-001-01, RDG	2	EA	
Bell, Electronic, 5" Base, P/N EB-3-360-5, GSI	2	EA	
Gate Keeper, 2-Way, w/Hardware & Buffer Spring, P/N SK-1000-2W, GSI	2	EA	
E-Z Gate (Vertical stripe) LED gate w/lamp kit, P/N 9298-6154, Railway Equip		EA	
Sleeve, 4' Aluminum, P/N 92958, Railway Equipment	2	EA	
Wrench, Torque (KIT), P/N 2590-K-9, WCH	1	EA	
Sign, Emergency, ENS, 15"X9" Blue, Eagle Traffic	2	EA	
Field cable Tag Kit, P/N FLDTGKT, CTC Inc.	1	EA	
Schedule 40 2" & 4" PVC Conduit Kit with Elbows	1	LOT	
Duct seal, 5lb, P/N 31-605, Graybar		EA	
Lock, Barrel Style	4	EA	

6/6/2018

673 Norton Ave. Barberton, Ohio 44203

ABC Railway

Tele: (330) 753-2983

Various Locations

Insulated Joints Installation - Proposal

Attn: Andrew R. Shuster Phone: 330-813-6133 Email: ashuster@abcrwy.com

Wintrow Construction Corp. will provide all supervision, labor, equipment, and specified materials to complete the following described work:

Main St., Wadsworth, Ohio

 Furnish and install 8-Insulated joints for crossing signal project New Alleghany glue joints will be furnished-39' overall length Insulated joints will be bolted in place Location of joints to be marked by others

	Total:	\$31,825
	Labor/Equip:	\$12,931
	Materials:	\$18,894
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$1,971)

Medina Line Rd., Norton, Ohio

1. Furnish and install 8-Insulated joints for crossing signal project New Alleghany glue joints will be furnished-39' overall length Insulated joints will be bolted in place Location of joints to be marked by others

	Total:	\$30,544
	Labor/Equip:	\$11,650
	Materials:	\$18,894
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$1,971)

Main St., Kent, Ohio

 Furnish and install 1-Insulated joints in curve closure rail in turnout south of road New Alleghany glue joint will be furnished-39' overall length Insulated joint will be bolted in place

Location of joint to be marked by others

	Total:	\$4,315
Labo	r/Equip:	\$1,649
Μ	aterials:	\$2,666
If new Alleghany joint made from relay rail is acceptable	Deduct:	(\$246)

673 Norton Ave. Barberton, Ohio 44203

Tele: (330) 753-2983

ABC Railway

Various Locations

Insulated Joints Installation - Proposal

Contingencies/Notes

Sales Taxes Not included in Quotation

No Warranty or Guarantees are apart of this proposal

Payment: Net 30 Days. Late payment charge of 1 1/2% (18% annum) will be charged on all past due balances.

We are not responsible for repair or relocation of Under Ground Utilities

Weather conditions prevail and may affect the construction schedule.

Track must be free of rail cars and rail traffic.

ONE Mobilization is included in the quotation.

All work is at straight time labor rates unless specified otherwise in the quotation Work description and material specifications haven't as yet been approved by the railroad

Engineering, plans and layout survey by others.

Material Subject to Pryor Sale

Progress payments are to be paid by the 15th of the month.

No costs for possible flagman services is included

Costs include continuous work windows with no train delays

*No destressing of rails is included-Rail temperature is

assumed to be within rage when installation is scheduled*

No wiring or bonding is included in pricing

Crosier Industrial Construction Ltd

8938 Peck Rd Ravenna, Ohio 44266 Ph (330) 592-3082 trailrnrbob@hotmail.com

Crosier Industrial Construction, LLC			Date	1	13-Feb-18		
Project Cost Estimate			Invoice Number	TBD			
Project: Main St. Wadsworth 265-076N				Shu	ster/Shankl	in - A	ABC
LABOR			Rate/Hr	Hou	irs	su	ıb-total
Equipment Operator (backhoe, excavator)			\$25.00		96		\$2,400.00
Laborer, skilled			\$18.00		96	\$	1,728.00
Project Manager			\$50.00		96	\$	4,800.00
Administrative			\$30.00		2	\$	60.00
			Sub-Total			\$	8,988.00
			G&A Burden fo	or Lab	or	_	5,392.80
			Total Labor			\$	14,380.80
EQUIPMENT	Quantity	rate/h	r		Hours		Total
Excavator, Bobcat E32 (331)		\$ 31.20			12	\$	374.40
E55		\$ 40.20			80	\$	3,216.00
Dump Truck		\$ 40.00			20	\$	800.00
Directional Drill		\$ 59.62			12	\$	715.44
Truck, equipment		\$ 21.35			96	\$	2,049.60
HydroTamper		\$ 17.05			12	\$	204.60
Traffic Cones		\$ 0.13			96	\$	12.48
Traffic Signs		\$ 0.23			96	\$	22.08
Tamper		\$ 4.25			6	\$	25.50
Digger Derrick		\$ 55.20			4	•	220.80
			Total Equipme	nt	-	\$	7,640.90
MATERIALS			Quantity		rice/Each	φ	Total
5" pvc conduit			150	\$	2.86	\$	429.00
5" 90 degree			3	\$	20.10	\$	60.30
5" coup			6	\$	4.98	\$	29.88
4" pvc conduit			50	\$	2.18	\$	109.00
4" sweeps			3	\$	23.50	\$	70.50
4" 90 degree			1	\$	11.50	\$	11.50
4" 45 degree			2	\$	11.50	\$	23.00
4" coup			12	\$	2.10	\$	25.20
3" pvc conduit			45	\$	1.72	\$	77.40
3" sweeps			-43	\$	21.10	\$	42.20
3" coup			4	\$	1.45	\$	5.80
2" pvc conduit			50	\$	0.94	\$	47.00
2" sweeps			1	\$	17.95	\$	17.95
2" 45 degree			2	\$	1.95	\$	3.90
Pull Rope			325	ې \$	0.13	.⊅ \$	42.25
Ground rods			325	۰ ۶	17.25	э \$	42.25
Cement			1	\$	8.50	\$	8.50
Pull Box			2	\$	315.00	\$	630.00
Gravel			50	\$	25.00	\$	1,250.00
			Material Total			\$	2,917.88
			Job Sub-Total				24,939.55
			Profit Addition		10%	\$	2,493.96
			Concrete curbs:			\$	3,000.00
			Asphalt work:			\$	4,500.00
			TOTAL PROJECT E	STIM	ATE	\$	34,933.51

Day 1: Bore road and place 5" conduit

Day 2: Excavate and place near foundation and conduit to pull box location. Place AC pole and conduit. Backfill and tamp.

Day 3: Excavate and place far foundation and conduit to pull box. Excavate and place far track wire conduit. Install far pullbox.

Day 4: Excavate and pour curbs. Excavate and install bore conduit to bungalow pull box. Backfill/tamp.

Day 5: Backfill behind curbs. Install bungalow pull box. Install near track wire conduit. Backfill/tamp. Install pull rope.

Day 6: Spread and tamp gravel. Grade area to be paved. Install ground rods.

Day 7: Pave areas with asphalt.

Day 8: Spread gravel and tamp. Finish grade.

Duties Performed throughout the project:

* Coordinate delivery of fill material

- * Coordinate curb and sidewalk construction
- * Transport foundations, conduit, pull box to site
- * Remove spoils and debris
- $^{\star}\,$ Supply and erect traffic control devices for work zone safety
- $^{\star}\,$ Call Ohio Utility Protection Service as required by Ohio Law
- * Establish Railroad Roadway Worker Protection daily to comply with Federal Regulation

This foregoing document was electronically filed with the Public Utilities

Commission of Ohio Docketing Information System on

6/3/2019 11:28:44 AM

in

Case No(s). 19-0423-RR-STP

Summary: Memorandum In the Matter of a Request for Upgrades at Akron Barberton Cluster Railway Crossings in Medina County and Portage County, Ohio. electronically filed by Mrs. Jill A Henry on behalf of PUCO/Rail Division