



American Electric Power
8500 Smith's Mill Road
New Albany, OH 43054
aep.com

July 7, 2023

Ms. Tanowa Troupe
Docketing Division
Public Utilities Commission of Ohio
180 East Broad Street
Columbus, OH 43215-3793

Re: *In the Matter of the Long-Term Forecast Report of Ohio Valley Electric Corporation, and Related Matters, Case No. 23-500-EL-FOR*

Dear Ms. Troupe,

On April 17, 2023, Ohio Valley Electric Corporation (the "Company") initiated this docket by filing its Long-Term Forecast Report ("LTFR"). At Staff's request, the Company now submits the enclosed supplement to its Form FE-T9.

If you have any questions regarding this information, please do not hesitate to contact me.


Respectfully submitted,

/s Hector Garcia-Santana
Hector Garcia-Santana (0084517)

Counsel for Ohio Valley Electric Corporation

**STATEMENT PURSUANT TO SECTION 4901:5-1-03(D),
OHIO ADMINISTRATIVE CODE**

Ohio Valley Electric Corporation's 2023 Supplemental Long-Term Forecast report is true and correct to the best of my knowledge and belief

A handwritten signature in black ink, appearing to read "J. Cooper", is written over a horizontal line.

Justin Cooper
Vice President, Chief Operating Officer
and Chief Financial Officer
Ohio Valley Electric Corporation

July 7, 2023

Dated this day in Columbus, Ohio

PUCO Form FE-T9 Supplement:
Specifications of Planned Electric Transmission Lines

1. Line Name and Number:	Pierce - Don Marquis 345 kV (s2213)
2. Points of Origin and Termination:	Pierce, Don Marquis
3. Right-Of-Way:	71.5 miles / 150 ft / 2 circuit (will be six wired)
4. Voltage:	345/345 kV
5. Application For Certificate:	2022-2023
6. Construction:	2024-2025
7. Capital Investment:	\$0.8M
8. Planned Substations:	N/A
9. Supporting Structures:	Steel
10. Participation with Other Utilities:	AEP
11. Purpose of the Planned Transmission Line	Reconfigure 345 kV circuits afer retirement of X-530 station. The Pierce - X-530 345 kV line will be six wired and reconfigured to terminate at AEP's Don Marquis station
12. Consequences of Line Construction Deferment or Termination:	Important 345 kV lines in area would be left open ended after the retirement of the X-530 station.
13. Miscellaneous	N/A

**This foregoing document was electronically filed with the Public Utilities
Commission of Ohio Docketing Information System on**

7/7/2023 2:59:55 PM

in

Case No(s). 23-0500-EL-FOR

Summary: Report Supplement to LTFR Filed 4/17/2023. electronically filed by
Hector Garcia-Santana on behalf of Ohio Valley Electric Corporation.